

THE ARCHITECTS' JOURNAL



standard contents

every issue does not necessarily contain
all these contents, but they are
the regular features which
continually recur

NEWS and COMMENT

Astragal's Notes and Topics

Letters

News

Diary

Criticism

TECHNICAL SECTION

Information Sheets

Information Centre

Current Technique

Working Details

Questions and Answers

Prices

The Industry

CURRENT BUILDING

Major Buildings described:

Details of Planning, Construction,

Finishes and Costs

Buildings in the News

Building Costs Analysed

Architectural Appointments

Wanted and Vacant

No. 3293]

[Vol. 127

THE ARCHITECTURAL PRESS


11 and 13, Queen Anne's Gate, Westminster,
W.1. Phone: Whitehall 0611

Price 1s. 0d.

Registered as a Newspaper.

★ A glossary of abbreviations of Government Departments and Societies and Committees of all kinds, together with their full address and telephone numbers. The glossary is published in two parts—A to Ig one week, Ih to Z the next. In all cases where the town is not mentioned the word LONDON is implicit in the address.

AA	Architectural Association, 34/6, Bedford Square, W.C.1.	Museum 0974
AAI	Association of Art Institutions. Secy.: W. L. Stevenson, College of Art, Hope Street, Liverpool 1.	Royal 1826
ABS	Architects' Benevolent Society. 66, Portland Place, W.1.	Langham 5721
ABT	Association of Building Technicians. 1, Ashley Place, S.W.1.	Victoria 0447-8
ACGB	Arts Council of Great Britain. 4, St. James' Square, S.W.1.	Whitehall 9737
ADA	Aluminium Development Association. 33, Grosvenor Street, W.1.	Mayfair 7501/8
ARCUK	Architects' Registration Council. 78, Wimpole Street, W.1.	Welbeck 2915
BAE	Board of Architectural Education. 66, Portland Place, W.1.	Langham 5721
BC	Building Centre. 26, Store Street, Tottenham Court Road, W.C.1.	Museum 5400
BCC	British Colour Council. 13, Portman Square, W.1.	Welbeck 4185
BCCF	British Cast Concrete Federation. 105, Uxbridge Road, Ealing, W.5.	Ealing 9621
BCIRA	British Cast Iron Research Association. Alvechurch, Birmingham.	Redditch 716
BDA	British Door Association. 10, The Boltons, S.W.10.	Fremantle 8494
BEDA	British Electrical Development Association. 2, Savoy Hill, W.C.2.	Temple Bar 9434
BIA	British Ironfounders' Association. 145, Vincent Street, Glasgow, C.2.	Glasgow Central 2891
BID	Building Industries Distributors. 52, High Holborn, W.C.1.	Chancery 7772
BINC	Building Industries National Council. 11, Weymouth Street, W.1.	Langham 2785
BOT	Board of Trade. Whitehall Gardens, Horseguards' Avenue, Whitehall, S.W.1.	Trafalgar 8855
BRS	Building Research Station. Bucknalls Lane, Watford.	Garston 4040
BSA	Building Societies Association. 14, Park Street, W.1.	Mayfair 0515
BSI	British Standards Institution. British Standards House, 2, Park St., W.1.	Mayfair 9000
BTE	Building Trades Exhibition. 32, Millbank, S.W.1.	Tate Gallery 8134
CABAS	City and Borough Architects Society. C/o Johnson Blackett, F.R.I.B.A., Civic Centre, Newport, Mon.	Newport 65491
CAS	County Architects' Society. C/o S. Vincent Goodman, F.R.I.B.A., Shire Hall, Bedford.	Bedford 67444
CCA	Cement and Concrete Association. 52, Grosvenor Gardens, S.W.1.	Belgravia 6661
CCP	Council for Codes of Practice. Lambeth Bridge House, S.E.1.	Reliance 7611 Ext. 1284
CDA	Copper Development Association. 55, South Audley Street, W.1.	Grosvenor 8811
CIAM	Congrès Internationaux d'Architecture Moderne. Doldertal, 7, Zurich, Switzerland	Trafalgar 8000
COID	Council of Industrial Design. 28, Haymarket, S.W.1.	Sloane 4280
CPRE	Council for the Preservation of Rural England. 4, Hobart Place, S.W.1.	Sloane 9116
CUC	Coal Utilization Council. 3, Upper Belgrave Street, S.W.1.	Reading 72255
CVE	Council for Visual Education. 13, Suffolk Street, Haymarket, S.W.1.	Reliance 7611
DGW	Directorate General of Works, Ministry of Works, Lambeth Bridge House, S.E.1.	Whitehall 0540
DIA	Design and Industries Association. 13, Suffolk Street, S.W.1.	Trafalgar 8855
DOT	Department of Overseas Trade. Horseguards Avenue, Whitehall, S.W.1.	Regent 4448
EJMA	English Joinery Manufacturers' Association (Incorporated). Sackville House, 40, Piccadilly, W.1.	Regent 4448
EPNS	English Place-Name Society. 7, Selwyn Gardens, Cambridge.	Welbeck 1781
FAS	Faculty of Architects and Surveyors. 68, Gloucester Place, W.1.	Kensington 4577
FASS	Federation of Associations of Specialists and Sub-Contractors, 14, Bryanston Street, W.1.	Whitehall 6711
FBBDO	Fibre Building Board Development Organization Ltd. (Fidor), 47, Princes Gate, Kensington, S.W.7.	Regent 0221
FBI	Federation of British Industries. 21, Tothill Street, S.W.1.	Sloane 1002
FC	Forestry Commission. 25, Savile Row, W.1.	Ilkerton 623
FCMI	Federation of Coated Macadam Industries. 37, Chester Square, S.W.1.	Ulverston 201
FDMA	The Flush Door Manufacturers Association Ltd., Trowell, Nottingham.	W.C.1.
FLD	Friends of the Lake District. Pennington House, nr. Ulverston, Lancs.	Chancery 7583
FMB	Federation of Master Builders. 26, Great Omond Street, Holborn, W.C.1.	Whitehall 3902
FPC	The Federation of Painting Contractors, St. Stephen's House, S.W.1.	Langham 4341
FRHB	Federation of Registered House Builders. 82, New Cavendish Street, W.1.	Monarch 8888
GPDA	Gypsum Plasterboard Development Association. 11, Ironmonger Lane, E.C.2.	Sloane 4554
GC	Gas Council. 1, Grosvenor Place, S.W.1.	Belgravia 3081
GG	Georgian Group. 2, Chester Street, S.W.1.	Whitehall 2881
HC	Housing Centre. 13, Suffolk Street, Pall Mall, S.W.1.	Belgravia 3755
IAAS	Incorporated Association of Architects and Surveyors. 29, Belgrave Square, S.W.1.	Grosvenor 6186
ICA	Institute of Contemporary Arts. 17-18, Dover Street, Piccadilly, W.1.	Whitehall 4577
ICE	Institution of Civil Engineers. 1, Great George Street, S.W.1.	Temple Bar 7676
IEE	Institution of Electrical Engineers. Savoy Place, Victoria Embankment, W.C.2.	Abbey 5215
IES	Illuminating Engineering Society. 32, Victoria Street, S.W.1.	Sloane 8266
IGE	Institution of Gas Engineers. 17, Grosvenor Crescent, S.W.1.	



THE IMPROVED

Greenwood-Airvac underfloor Conduit System

... provides for all cables to be accommodated in one duct with adequate screening between telephone and power cables.

Bankers Trust Co. (New York)
Euckersbury House, E.C.4.
Architect: O. Campbell-Jones, Esq.
FRIBA, FRICS, London, E.C.4.
Main Contractors: Humphreys
Ltd., London, S.W.1. Electrical
Contractors: Thorpe & Thorpe
Ltd., London, E.C.4.



Greenwood-Airvac

conduit systems

GREENWOOD'S AND AIRVAC VENTILATING COMPANY LIMITED
Patentees, Designers and Manufacturers of Ventilating Equipment and Electrical Conduit Systems
BEACON HOUSE, KINGSWAY, LONDON, W.C.2. CHAncery 8135 (4 lines). 'Airvac' London

Latest Developments:
★ Remote adjustable floor
frame in brass
★ Waterproof junction box

Visit Stand E 49, Factory
Equipment Exhibition,
Earls Court, April 14-19

SYLGLAS

GLAZING AND SEALING TAPE

- ★ **Permanently Waterproof**
- ★ **Guaranteed for 20 years**

SYLGLAS—guaranteed for 20 years against hardening and cracking—is permanently waterproof, solves a hundred-and-one problems.

WEATHERPROOFS window-frames, joints in corrugated roofs, garages, outhouses and caravans.

REPAIRS drainpipes and guttering—can be painted without difficulty.

GLAZES greenhouses and conservatories—eliminates the need for painting glazing bars.

PREVENTS and arrests rust wherever applied.

Available as tape—in a variety of widths—or as cord, SYLGLAS is extremely flexible and adheres to any dry surface. It is the simple, speedy and economical answer to your glazing and sealing problems. And remember, SYLGLAS makes a permanent job—it is not a temporary repair.

Sylglas is now available in Mastic form for bedding, caulking, filling, etc., and has the same non-hardening properties as Sylglas Tape or Cord.



Stocked by Ironmongers, Hardware Merchants, Builders' Merchants. If any difficulty is experienced in obtaining Sylglas, write to the manufacturers for the name of the nearest Stockist.


THE SYLGLAS COMPANY, 81 KNIGHT'S HILL, LONDON, S.E.27 Telephone: GIPsy Hill 4247 (5 lines) Telegrams: Snowwhite, London, S.E.27

7



ders'
ning
the

, S.E.27



Brightside branch offices are situated in twelve of the principal industrial centres throughout the United Kingdom.

If you are interested in these services, let Brightside know. There is a Technical Research department whose staff will be glad to help in solving your problems.

HEATING, · AIR CONDITIONING AND VENTILATING PLANT · THERMAL PROCESS WORK · AIR TREATMENT · HIGH AND LOW PRESSURE PIPEWORK · ABLUTION SERVICES

There is a
BRIGHTSIDE
branch
office
near you

BRIGHTSIDE HEATING & ENGINEERING CO LTD · SHEFFIELD

And at : BELFAST · BIRMINGHAM · BRADFORD · BRISTOL · EDINBURGH · GLASGOW
LIVERPOOL · LONDON · MANCHESTER · NEWCASTLE · PORTSMOUTH

BP71

BARCLAYS BANK LTD • HARLOW NEW TOWN




The counters and screens were carried out by our organisation to the designs and under the direction of J. Seymour Harris & Partners.



OUR DESIGN AND TECHNICAL SERVICE IS READILY AVAILABLE TO ASSIST IN THE DEVELOPMENT OF ALL TYPES OF DECORATIVE SCHEMES.

Harris & Sheldon Ltd.

The organisation with a background of 75 years experience.
BIRMINGHAM • LONDON • GLASGOW • TORONTO.



with

EVODE

ROOF WATERPROOFING SYSTEM

* Foreman Demonstrators are available to assist your own work people or, if you prefer, our contracts department can undertake the work for you.

- * Any roof can be treated
- * Permanent waterproofing for large or small roofs
- * Applied cold without any preliminary treatment
- * Used and proved for 25 years

A PRODUCT OF **EVODE** OF STAFFORD

ROOF WATERPROOFING • CONCRETE ADMIXTURES AND HARDENERS • PROTECTIVE PAINTS AND BITUMINOUS COATINGS • GAP AND JOINT SEALING MASTICS AND GUNS • INDUSTRIAL ADHESIVES

* **SEND FOR LITERATURE** EVODE LTD. (BUILDING CHEMICALS DIVISION) STAFFORD. Phone: 2241
London Office: 1 VICTORIA STREET, S.W.1. Telephone: ABBey 4622


M-W.65

everything has to be **CONTROLLED**



to control electricity


SANDERS



*The mark of superiority
in Switch and Fusegear*

A camera view of the
"Sandacled" one of the most
modern and praiseworthy
designs in the Sanders range.

WM. SANDERS & CO. (WEDNESBURY) LTD.
FALCON ELECTRICAL WORKS, WEDNESBURY, STAFFS.



The inexpensive alternative to Glazed Tiles

A glazed, easily cleaned wall surface is frequently required in canteens, schools, hospitals and many industries. Often, cost prohibits the use of glazed wall tiles and to this problem, TYLEX is the complete answer. TYLEX is applied like a paint, with no joints to harbour dirt or bacteria and is completely resistant to the effects of steam, grease, moisture and chemicals.

TYLEX is applied to new or old wall surfaces without preliminary sealing treatment and withstands frequent washing without losing its hard, brilliant glaze. The cost of TYLEX is comparable with that of a good quality paint. We shall be glad to send you full details, together with a shade card showing the wide range of attractive colours, which is based upon the B.S. 2660 colour series.

Introducing...









'Rufflette' BRAND

DOUBLE TRACK

Double Track is completely unobtrusive and meets the demand for a curtain track of better than usual appearance with concealed cording mechanism. Equally suitable for installation in new or existing buildings, it is the ideal system for any straight window curtain problems. The track is of pressed steel in a fine ivory enamel finish within which nylon gliders provide noiseless and smooth operation. Fitting to window recess or ceiling is simplicity itself; and the smooth, effortless cord control action puts "Rufflette" Brand Double Track in a class by itself.



For hotels, hospitals, schools and in large commercial buildings "Rufflette" Double Track is the ideal curtain suspension system.

 <p>TRACK LENGTH</p> <p>This diagram shows the beautifully designed lines of the track providing dust-free housing for the internal components.</p>	 <p>SINGLE & MASTER GLIDERS</p> <p>These gliders are made in nylon to give a high degree of efficiency with a minimum of noise. Curtains hang from the eyes attached to the glider.</p>	 <p>DOUBLE PULLEY UNIT</p> <p>Vertical double pulleys made in nylon are fitted in this neat housing which is affixed to the end of the track.</p>
 <p>FIXING HOLES</p> <p>Holes of $\frac{3}{16}$" diameter are drilled at intervals of $1\frac{1}{2}$" along the full length of the Double Track section to facilitate fixing. Face fixing brackets are available if required.</p>	 <p>SINGLE PULLEY UNIT</p> <p>The single horizontal pulley made in nylon is fitted in this neat housing at the opposite end of the track.</p>	

*One of the many windows equipped with 'Rufflette' Double Track at the Strand Palace Hotel, London
(by courtesy of J. Lyons & Co. Ltd.)*

Full information about Double Track suspension on request to:

THOMAS FRENCH & SONS LTD., CHESTER ROAD, MANCHESTER, 15.

London Office: Dundas House, 59, St. James's Street, S.W.1. Also at Wythenshawe. Associate and Subsidiary Companies in U.S.A. and Canada.

IT'S **FEB** AGAIN!

FIRST AGAIN...WITH THE NEW

FEBFLOW

CONCRETE PLASTICISER

that reduces cost!

ACTION:

Mix in Febflow and you can reduce the water-cement ratio and yet still increase by up to 100% the workability and flowability of the concrete.



ACTION:

Mix in Febflow and the cement is so thoroughly dispersed and evenly distributed throughout the mix, compressive and tensile strengths are greatly increased.

RESULT:

Placing and compaction time is greatly reduced, the reinforcement is fully surrounded and covered and maximum density is obtained.



RESULT:

Because the cement is fully utilised its potential value is greater than in untreated mixes and in consequence the cement content can be reduced without loss in strength.



102 Kensington High Street, London, W.8
WES 0444



(GREAT BRITAIN) LTD

Albany Road, Chorlton-cum-Hardy, Manchester 21
CHO 1063


DHB/6627

PLANTATION HOUSE
MINCING LANE • CHEAPSIDE
Architects:
Albert W. Moore & Son



THE ARCHITECTS' JOURNAL
(Supplement) April 10, 1958


ROMAN HOUSE • LONDON WALL
Architect:
R. N. Wakelin
of Campbell-Jones & Sons




MERCERS' HALL • CHEAPSIDE
Architects:
Gunton & Gunton




HOLBORN VIADUCT HOUSE
HOLBORN CIRCUS
Architects:
T. P. Bennett & Son




1 NOBLE STREET
GRESHAM STREET
Architects:
Ellis, Clarke & Gallannaugh



ROYAL LONDON HOUSE
(EXTENSION) FINSBURY SQUARE
Architect:
H. Bramhill




34-35 KING STREET • EC
Architects:
Alan W. Pipe & Sons




WATLING HOUSE • CANNON STREET
Architects:
Easton & Robertson



WALBROOK HOUSE
CANNON STREET • WALBROOK
Architect:
Henry Tanner



12-20 CAMOMILE STREET
Architects:
Fitzroy Robinson
& Hubert H. Bull




MCCANN-ERICKSON HOUSE
FETTER LANE
Architects:
Hannen & Markham



BUCKLESBURY HOUSE
Architects:
Campbell-Jones & Sons



ST. BRIDGET'S HOUSE
BRIDEWELL PLACE
Architects:
Trehearne &
Norman Preston & Partners



SADDLERS' HALL • GUTTER LANE
Architect:
L. Sylvester Sullivan



3-10 FINSBURY SQUARE
Architects:
Lewis Solomon Son & Joseph



THE AMALGAMATED PRESS
FARRINGTON STREET
Architects:
Ellis, Clarke & Gallannaugh



BANK OF LONDON
& SOUTH AMERICA
QUEEN VICTORIA STREET
Architect:
Victor Heal

**The city
re-builds with...**

CRITTALL WINDOWS



THE CRITTALL MANUFACTURING CO LTD • BRAINTREE • ESSEX • BRANCHES & DEPOTS THROUGHOUT THE COUNTRY

Specialists in high class Standard Joinery



THE MIDLAND WOODWORKING CO LTD MELTON MOWBRAY

AP/MW 18



BRABY

Pressed Steel Stairs are strong, safe and dependable

These internal stairs are load-saving, rapidly assembled at site and when erected with structural frame can be used to facilitate building operations.

Treads and landings are designed to take granolithic, terrazzo, marble, wood, etc. or prepared for rubber covering.

Designs and estimates submitted on request.

Pressed Steel Stair in a modern office building.

Associated architects:

*H. Courtenay Constantine, F.R.I.B.A.
and Arthur A. Stewart, F.R.I.B.A.*

**other BRABY
products include**

METAL WINDOWS AND PARTITIONS · STRUCTURAL STEELWORK
DOVETAIL STEEL SHEETS · COPPER ROOFING · TANKS, CISTERNS
AND CYLINDERS · DUCTING · STEEL STORAGE EQUIPMENT

ONE OF THE WIDE RANGE OF

BRABY

PRODUCTS

FREDERICK BRABY & COMPANY LIMITED

ECLIPSE WORKS, PETERSHILL ROAD, GLASGOW, N. TELEPHONE: SPRINGBURN 5151
OTHER FACTORIES AT: London Works, Thames Road, Crayford, Kent. TELEPHONE: Bexleyheath 7777
Havelock Works, Aintree, Liverpool, 10. TELEPHONE: Aintree 1721
Ashton Gate Works, Bristol, 3. TELEPHONE: Bristol 64041. And Falkirk
OTHER OFFICES: 352-364 Euston Road, London, N.W.1 (Head Office). TELEPHONE: EUSion 3456
110 Cannon Street, London, E.C.4 (Export). TELEPHONE: MANSion House 6034
Queen's Buildings, 10 Royal Avenue, Belfast. TELEPHONE: 26509
Palace Street, Plymouth. TELEPHONE: 62261


AP-283

This advertisement is produced to B.S. 1311, 1956, governing Trade and Technical publications.



to ensure
BETTER FIRE PROTECTION
use Dry Construction

The immeasurable danger of fire to life and property can be greatly reduced by the use of building materials made from Gypsum, the mineral that doesn't burn. With "Blue Hawk" DRY CONSTRUCTION products, maximum protection can be obtained easily, speedily and economically.



'Paramount' PLASTERBOARD


is graded as a Class 1 material—that is, one which constitutes no fire hazard. It is the original plasterboard for walls and ceilings. There is no drying out period—its surfaces are specially prepared for immediate decoration. A water-resisting quality is also produced for use where condensation is a problem. At less than 6d. per square foot, it is easily the most economical form of fire-safe construction.

Other Blue Hawk Dry Construction Materials:

'Paramount'


INSULATING PLASTERBOARD

for efficient thermal insulation.



'Paramount' DRY PARTITION

for interior walls and linings.



'Paramount' COVE

for eliminating unsightly cracks.



Assess the possibilities of DRY CONSTRUCTION by obtaining full particulars from

DRY CONSTRUCTION DIVISION

THE

BRITISH PLASTER BOARD

(Manufacturing) LTD

BATH HOUSE, 82 PICCADILLY, LONDON, W.1 TELEPHONE: GROSVENOR 8311.

4P95

NEW RESEARCH LABORATORY



Corner of new Laboratory showing Q-FLOOR laid in 4 ft. strips at 4 ft. intervals, with Q-cells available on 8 in. centres. Cross header ducts bring services from distribution boards to Q-cells with access points as shown.

Normally, Q-FLOOR serves primarily as a structural floor laid between supporting steelwork, the Q-cells providing a series of electrical ducts over the entire floor area.

In this instance, however, Q-FLOOR was laid on the concrete ground floor slab, as illustrated, and served solely as an underfloor duct system.

This contract involved some 8,000 sq. ft. of Q-FLOOR which was laid, aligned and fixed within four days.

Architect: T. P. Bennett & Son, London
General Contractor: Wm. Moss & Sons Ltd., London
Electrical Contractor: John Hearson & Co. Ltd., London

for
**Messrs. Smith's Aircraft
Instruments Ltd.**

(Aviation Division of
S. Smith & Sons (England) Ltd.)
at Cheltenham, Gloucestershire,
includes

ROBERTSON

Q-FLOOR



Close-up view of electrical access points. All outlets will be from the Q-cells themselves and not from the header ducts.

ROBERTSON Q-FLOOR

TRADE MARK

ROBERTSON THAIN LIMITED
ELLESMERE PORT • WIRRAL • CHESHIRE

Telephone: Ellesmere Port 3622-9



Telegrams: "Robertroof"

Sales Offices: BELFAST • BIRMINGHAM • CARDIFF • EXMOUTH • GLASGOW • IPSWICH • LIVERPOOL • LONDON • MANCHESTER • NEWCASTLE • SHEFFIELD

Associated Companies or Agents in most countries throughout the world



*'The stuff for covering furniture
is p.v.c. leathercloth!'*

"THIS CHAIR is upholstered in p.v.c. leathercloth. It lasts practically for ever. I.C.I. make it, of course, with I.C.I. 'Corvic'. As you probably know, I.C.I. p.v.c. polymers and compounds are backed by the best research and technical service in the country."

'Corvic' is the registered trade mark for the p.v.c. manufactured by I.C.I.

IMPERIAL CHEMICAL INDUSTRIES LIMITED · LONDON · S.W.1

PC.3





These houses on the Llanrunney Housing Estate, built for the Cardiff City Corporation, have all been treated against wood rot with Presotim at a total cost of £5 per house. Builders:—Messrs. G. E. Wallis & Sons Ltd., Cambrian Chambers, Cambrian Road, Newport, Mon.

£5

will keep a house safe from WOOD ROT and DECAY

**Wood treated with Presotim is proof against exposure,
dry rot, furniture beetle and other insect pests**

Builders and architects are well aware of the extensive damage that can be done to woodwork, unless it is properly protected. Consequently the structural timbers of an increasing number of their buildings are being treated with a reliable wood preservative. Roof trusses and joists are dipped into *Presotim* before erection, and the total cost of this operation, including labour, works out at about £5 per house—a small price to pay for the complete protection that it provides.

FOR INTERIOR OR EXTERIOR USE

Presotim is produced from a series of highly refined coal-tar oils blended to provide extra-deep penetration, even when applied with a brush. It is suitable for both interior and exterior use, for panelling, doors, skirtings, as well as for outbuildings, fences, gates, etc.

Presotim (interior quality) can be safely used without obscuring the natural beauty of the grain in the wood, and afterwards the wood can be polished or varnished, as required. *Presotim* is available in a

variety of different shades, and also in a “neutral” grade, which is specially suited to old and valuable timbers such as church roofs and panelling, when it is essential to preserve the wood without altering its characteristic colour.

Wherever a reliable wood-preservative is needed, *Presotim* offers long-term protection against decay at very low cost.

Also SYNTHAPRUF—an adhesive waterproofer widely used for curing damp walls and leaking roofs and for fixing linoleum and wood blocks.


PRESOMET—a black bituminous rust-preventing paint that gives a smart, durable surface to all metal work.

Presotim

Manufactured by the NATIONAL COAL BOARD

For further details and advice on technical problems, please write to National Coal Board, By-Products, National Provincial Bank Buildings, Docks, Cardiff.

“PRESOTIM”, “PRESOMET” & “SYNTHAPRUF” are Registered Trade Marks



NEW *quietness overhead!*
and **STEEL** gives fire protection too



CELOTEX

Incombustible


METAL ACOUSTIC TILE

Now, in your factory or your office, you can have a CELOTEX Acoustical ceiling which is **INCOMBUSTIBLE**.

Perforated steel tiles produced as individual panels with clean margins and bevels, are combined with a sound absorbing element to give maximum efficiency. They are easy and economical to instal.

Celotex Incombustible Metal Acoustic Tiles, with their matt enamel finish, add dignity to any room or building, whether factory or office, and they can be painted or washed as many times as you like. Resistant to vermin and rot, they last for the life span of the building, and are easily removable for access to services behind the ceiling. The Celotex Acoustical Advisory Service is at your immediate disposal—consult us without delay.

- 1 Steel Tile
- 2 Rockwool pad
- 3 Wire Grid
- 4 Steel T Bar Support



Main distributors for London, Southern Counties, Wales, the Midlands and Yorkshire:
Horace W. Cullum & Co. Ltd., The Acoustic Centre, 58 Highgate West Hill, N.6. Tel: FITzroy 1221 (PBX)

Main distributors for Scotland and Northern Counties:
William Beardmore & Company Ltd., Parkhead Steel Works, Glasgow. Tel: Bridgeton 1881


MADE IN GREAT BRITAIN BY CELOTEX LIMITED, North Circular Road, Stonebridge Park, London, N.W.10 Tel: ELGar 5717 (10 lines)



now...

low pitch—low cost

Redland stonewold



This is the Redland Stonewold—unique! It's the tile that architects and builders want; this tile solves the problem of constructing a modern, low-pitch roof inexpensively

22½° Pitch Orthodox roof tiles cannot usually be laid at pitches below 30°: the Redland STONEWOLD has been designed for use down to 22½°

Economy Smaller initial outlay than other forms of low-pitch covering—plus a permanent roof, with virtually no maintenance

Guaranteed Durability The Stonewold is made to the same high standards of consolidation as all other Redland tiles. Impermeable—as light in weight as orthodox single lap tiles—and guaranteed by Redland for 50 years

Three slate-type colours to choose from



Redland tiles

good — for 50 years and more

SEND FOR COLOUR CHART AND FULL SPECIFICATION TO

Redland Tiles Ltd • Castle Gate • Castlefield Road • Reigate • Surrey
Telephone: Reigate 4781 (10 lines)

A DIVISION OF THE REDLAND HOLDINGS GROUP


Starts 17

SMITHS

new service for the ARCHITECT & DESIGNER

Smiths Clocks and Watches Ltd. and English Clock Systems have combined to give a complete service to both Architect and Designer. All Wall Clocks in the new extensive Smiths and E.C.S. ranges together with 'specials' can now be ordered through the Architects' Service Department of English Clock Systems. Clocks can be either 'Sectric' or fitted with impulse movements for operation from E.C.S. Pendulum Master Clock.

Also available: the larger interior/exterior clocks, advertising clocks, time recorders, bell signal clocks, watchman's clocks, time switches and process timers etc. In fact, the new Architects' Service Department can supply the complete range of timekeeping equipment required for factory, school or office.



'SPECIALS' SERVICE

In case there is not a suitable clock for the particular requirements from the wide range available we can now produce to Architects' own specification from 6" Wall Clocks to the largest Tower Clock.

Monarch SURFACE MOUNTED WALL CLOCK from the E.C.S. range. Black Perpetua numerals on a circular white dial. Simple tapered hands. Hinged-type case of spun aluminium. Standard finish in bronze (any colour supplied at small extra cost.)

Dimensions: Dia. of face 9", 12". Overall dia: 11½", 14½". Projection from wall: 2½" Flush fitting model **FLINT**—Cream or white finish—wall box supplied. Also **BERKELEY**—Walnut finish Bakelite case—6", 9", 12" dials.

INFORMATION AND LEAFLETS FROM THE ARCHITECTS' SERVICE DEPT.

BRANCH OFFICE & SHOWROOMS
IN MANCHESTER, BIRMINGHAM
GLASGOW & BELFAST

ENGLISH CLOCK SYSTEMS*

Head Office and Showrooms

179-185 GT. PORTLAND STREET, LONDON, W.1

Telephone: LAngham 7226

* A BRANCH OF THE CLOCK AND WATCH DIVISION OF

SMITHS S. SMITH & SONS (ENGLAND) LTD
G1390

TROLLOPE & COLLS

(Established 1778)

Were entrusted with the building

of

FOUNTAIN HOUSE

125-135 Fenchurch Street, E.C.3.

for the

CITY of LONDON REAL PROPERTY CO. Ltd.



Architects :

W. H. Rogers, A.R.I.B.A.
Architects' Department,
City of London Real Property
Co. Ltd.

Consulting Architect :


Sir Howard Robertson, M.C.
P.P.R.I.B.A.

Consulting Engineers :

Messrs. G. A. Dodd &
Partners.

Trocoll House

ONE NOBLE STREET, GRESHAM STREET, E.C.2.



what do you look for in roof lighting?

The danger of fire spread, particularly in roofs is a matter of major concern to all associated with the building industry. Vague claims are often made about the flame spread characteristics of roof lighting sheets. The accepted authority is BS. 476:1953.

1 | safety at the point of danger

To clarify the position a series of tests, summarised below, were made by a leading independent laboratory in accordance with BS. 476:1953. The results clearly establish Corroglaze as **the only corrugated roof lighting sheet which cannot in any way assist the spread of flame**. Corroglaze is 100% pure glass, reinforced with 1" square wire mesh. It cannot flash, smoulder or drip flaming particles. Corroglaze gives better light transmission and distribution and is unaffected by exposure or fumes. It compares favourably in cost with all other forms of roof lighting and is suitable for use with corrugated sheeting.

MATERIAL	Time Lapse before Ignition	Spread of flame after 30 secs.	Condition after 3-3½ minutes
Sample 'A'	5-7 seconds	2"	Complete disintegration with molten material dripping off
Sample 'B'	5-7 seconds	2"	Completely burnt out—shell of burnt out fibre only remained
CORROGLAZE	NO IGNITION	NO IGNITION	No melting, the only effect being a slight cracking of the glass

LABORATORY REMARKS: Tests would classify Samples 'A' and 'B' as Class 4, Rapid Spread of Flame (B.S. 476: 1953 refers)



corroglaze


100% pure glass
(wire reinforced)
the non-combustible sheet



Designed and constructed under the supervision of G. A. Wilson, Esq., M.Eng., M.I.C.E., M.I.Mech.E., Chief Engineer, Port of London Authority; Main Contractors, Messrs. Tubewrights Ltd.

For further information write to:—

CORROGLAZE LTD., PALACE OF ENGINEERING, WEMBLEY, MIDDLESEX - - TEL: WEMBLEY 9411.



If you have
a Painting Problem
— bring it to **FARMILOES**

Your problem will be examined by an expert Technical Representative who will —


- visit and inspect the site to be painted
- discuss the whole job with a panel of specialist experts
- arrange, if necessary, for the Research Laboratory to produce special paints to cope with abnormal conditions
- present you with detailed specifications and Colour Schemes
- maintain liaison with the actual painters until the job is completed.

This Architectural Advisory Service is free of cost or obligation of any kind.


Write or telephone **THE MANAGER, Architectural Division,**
T. & W. FARMILOE LTD.,
Rochester Row, Westminster, S.W.1.—Tel: Victoria 4480

T. & W. FARMILOE LTD • ROCHESTER ROW • LONDON S.W.1

a name



to reckon with
for high and
low pressure
hot water
systems.




Left: Low pressure hot water circulating pumps and mains.

Right: Pump Room in a high pressure hot water system.

- Space heating in all its forms.
- Domestic Hot & Cold Water Systems.
- Ventilation and Air Conditioning.
- Dust & Fume Removal.
- Steam Plant and pipeline installations.

Our design service is at your disposal for any problem connected with comfort conditions.



STEELS ENGINEERING INSTALLATIONS LIMITED

Head Office: Crown Works, Sunderland

LONDON: 143 Sloane St., S.W.1. BIRMINGHAM: 172 St. Paul's Rd., Balsall Heath, 12. NEWCASTLE-ON-TYNE: 13 Brunswick Place, 1. GLASGOW: Merkland Works, Merkland St., Partick.



Prestressed Concrete

and

Asbestolux

**Asbestolux ceilings give
greatly extended fire protection
to prestressed concrete.**

* And what's more, ASBESTOLUX is now
available on immediate delivery.



CAPE BUILDING PRODUCTS LIMITED

COWLEY BRIDGE WORKS • UXBRIDGE • MIDDLESEX • TEL: UXBRIDGE 4313

Glasgow: Eagle Buildings, 217 Bothwell Street, Glasgow, C.2. Tel: Central 2175


Manchester: Floor D, National Buildings, St. Mary's Parsonage, Manchester 3. Tel: Blackfriars 7757

Birmingham: 11 Waterloo Street, Birmingham 2. Tel: Midland 6565-6-7

Newcastle: 19 & 20 Exchange Buildings, Newcastle. Tel: Newcastle 20488


It's **CAST IRON** for strength and **CRANE** for dependability

Crane boilers and radiators are made of cast iron for a very good reason—cast iron guarantees their strength and durability. The long life and freedom from maintenance costs of Crane heating equipment enhance the solid comfort of modern space heating and constant hot water. The Crane Carlton Boilers (illustrated) are available with or without thermostatic regulation, in nine sizes ranging from 32,500 to 136,000 B.t.u. per hour. Enamelled finish in a choice of three colours—cream, white or grey mottled.



Available for solid fuel
or oil-burning.

(Most makes of oil-burning equipment
are suitable for these boilers).



CRANE

CAST IRON HEATING EQUIPMENT


CRANE LTD., 15-16 RED LION COURT, FLEET STREET, LONDON, E.C.4. Works: IPSWICH
Branches: Birmingham, Brentford, Bristol, Glasgow, London, Manchester

**NEW HOLOPLAST
'80' panel for effective
SOUND-REDUCTION
...at an economic price!**

Now you can specify Holoplast Movable Walls with an effective sound reduction without the extra cost of infilling with sand or other materials. Fire resistance is excellent. And you get these advantages at a new, economic price.

In the new Holoplast '80' panel, there is a Viculite core with the well-known Holoplast stove-enamelled or Decorplast finishes. This new '80' panel is made in sizes up to 10' x 4' for greater economy in average office use.

*Bata Development Limited,
Oxford Street, London, W.1.*



Reed
PAPER GROUP

HOLOPLAST MOVABLE WALLS

Write for full details:—

DEPT. 105 HOLOPLAST LIMITED, SALES OFFICE, 116 VICTORIA ST., LONDON, S.W.1. TEL: VICTORIA 9354/7 & 9981.

Design Centre chooses

HAYMARKET, LONDON



NAIRN

linoleum

Nairn heavyweight linoleum


made in two thicknesses

LINTILE 6.70 mm **BATTLESHIP** 4.50 mm

Both are available in a range of **plain** colours and of **marble** markings. Together these ranges offer a wide choice of harmonious colours from which architecturally-designed floors can be built. Nairn Linoleum is chosen throughout the world for quality... fine marblings... colour... hard wear.



Forms the ideal neutral background for the Pattern Room



For the perfect display of Household Equipment



Hard-wearing to withstand heavy traffic

For full information about Nairn Linoleum
write or telephone to

MICHAEL NAIRN & CO LTD

131 Aldersgate Street, London, E.C.1

Telephone: **MONarch 3211**

or telephone Birmingham Office: Midland 5989

Manchester Office: Central 1417

Glasgow Office: South 1011



Head Office and Works:
Kirkcaldy, Scotland. Kirkcaldy 2011

Have you visited

THE PARTITIONING CENTRE

?

Since opening The Partitioning Centre last October many architects (and their clients) have come along to see it for themselves. And all of them have paid us the compliment of saying that their visit was time well spent.

It is a permanent centre where you can see a wide range of Compactom demountable partitioning and false ceiling schemes under everyday working conditions. No two rooms are the same; each has its individual method of construction and finish; each its individual decor, fittings and other special features. In addition, our design studio and drawing office are immediately available and at your service to discuss specific points in connection with your projects.

The Partitioning Centre is open Mondays to Fridays from 9 a.m. to 5.30 p.m.; no appointment is necessary. If you would prefer to come along at some other time, we will be pleased to make special arrangements for the Centre to remain open. We will also, if you wish, arrange transport. If you cannot get along to see for yourself may we send you full details of the Compactom service?

COMPACTOM

COMPACTOM LTD.,
OXGATE LANE, CRICKLEWOOD, LONDON, N.W.2
GLAdstone 6633




One of the corridors, showing full height and free standing partitions.



Director's office: Insulated double-wall Compactom partition, veneered and polished light oak. Fittings designed and constructed by Compactom. Acoustic tile ceiling with flush lighting.



View of entrance lobby and waiting room. Screen of timber spars and plate glass.



WITH
ANKARBOARD
ACOUSTIC BOARDS
AND TILES



In the factory, the office or the home, ANKARBOARD baffles noise, improves acoustics—and enhances appearances. The perforated boards are specially prepared with grooved and ship-lapped joints for easy fixing. Can be supplied with a coating of fire retardant Albi-R. for extra safety. **ACOUSTIC BOARDS** $\frac{1}{2}$ " or $\frac{3}{4}$ " thick, are available in 12" or 16" widths and in lengths up to approx. 16'. (Also available, unperforated, as insulating "longboards").

ACOUSTIC TILES $\frac{1}{2}$ " or $\frac{3}{4}$ " thick in sizes 12" x 12", 16" x 16", 24" x 24", 12" x 24" or 16" x 32". Tiles are bevelled on all four edges.

PERFORATIONS FOR BOARDS AND TILES 4 m.m. holes at 15 m.m. centres.

Depth of holes is arranged for maximum acoustic effect whilst corner holes are bored to half thickness only to ensure a good grip when tiles are screwed or nailed to fixing grounds.

ALSO
producers of

**KRAMFORS
CROWNBOARD
"ANKARBOARD"**

AND
**IVORY-FACED
HARDBOARDS**



MANUFACTURED BY

THE SWEDISH CELLULOSE CO.

SUNDSVALL · SWEDEN

For further particulars apply to:—Sole Selling Agents for U.K. and Eire

MAIN DISTRIBUTORS

John Bland and Co. Ltd., Cardiff. Cardiff 24241.

Walter S. Fry Ltd., London, S.E.1. Hop. 3511.

J. Holt and Son (Plywood) Ltd., Manchester 12. Ardwick 5551.

Rudders and Paynes Ltd., Aston, Birmingham 6. Aston Cross 3071.

The Scottish Speedwell Co. Ltd., Glasgow. Bridgeton 1143.


J. and W. Wilson and Sons, Sunderland. Sunderland 5-8244.

Dawber Townsley and Co. Ltd., Hull. Hu' 42234.

James P. Cory and Co. Ltd., Prince's Dock, Belfast, Northern Ireland.

T. and C. Martin Ltd., D'Olier House, Dublin, C.5.

MARTIN OLSSON & SONS LTD. MELBOURNE HOUSE · ALDWYCH · LONDON, W.C.2



The universal application of Rolador Steel Rolling Shutters is convincing proof of their efficiency in the protection of industrial openings. In any climate under varied and even extreme conditions Rolador are unsurpassed in service and ease of operation.

Haskins

ROLADOR
PAT NOS 257850 & 200187

Steel Rolling Shutters

GNOME HOUSE, BLACKHORSE LANE, LONDON, E.17 Telephone: LARKSWOOD 2622

Steel Reinforcement

A complete service of
Design, Fabrication
and Fixing of Steel
Reinforcement for all
types of Reinforced
Concrete Construction.

M.S. Bars to B.S.S. 785, bent,
bundled and labelled, delivered
to site ready for fixing. No loss
of time in checking and sorting
material. No loss of material due
to prolonged storage on site.

T. C. JONES

AND COMPANY LIMITED

REINFORCEMENT ENGINEERS

17 BUCKINGHAM PALACE GARDENS, LONDON, S.W.1

Tel: SLOane 5271

Head Office: Wood Lane, London, W.12 Tel: Shepherds Bush 2020

South Wales Office: Bute Street, Cardiff

Tel: 28786

Works: Shepherds Bush, London. Neasden, Middx. Treorchy, Glam.





Eric Hosking F.R.P.S., M.B.O.U.

Balanced Reflection

Wisdom . . . considered and analytical . . . goes into the production of all Duresco materials. Each material is made and inspected with the most expert, meticulous care—a care that does much to ensure the product superiority so necessary to meet the high standards of professional decorators and architects. Consult Duresco for progress in development within the sphere of their activities. Duresco Products are worthy of your consideration. You can always depend on them.

Duresco Products

"THE INVENTORS OF WATER PAINT"

*For our latest brochure which contains tint cards, and technical leaflets, please write or telephone:—
The Technical Advisory Service,*

DURESCO PRODUCTS LIMITED

LONDON: Charlton, S.E.7. GREENWICH 0034/5/6. • MANCHESTER: 65, Great Ducie St. DEAnsgate 3161.



At Golden Lane, E.C.1.

'K' aluminium alloy extrusions in natural finish were used for the curtain wall and side windows of this housing block. Extreme adaptability, freedom from corrosion, and high strength/weight ratio combine to make 'K' extrusions ideal for this type of construction. There is a very wide range of sections, and extrusions can be provided to architects' own designs.


'K' aluminium alloys are also available as rods, tubes and bars.

*Main Contractors: George Wimpey & Co., Limited
Curtain walling manufacturers: Quicktho (Engineering) Ltd.
Architects: Chamberlin, Powell & Bonn*



Aluminium Alloy Extrusions FOR CURTAIN WALLING

'DURCILUM' (regd.) and 'ALUMAGNESE'



E. & E. KAYE LTD. PONDERS END • ENFIELD • MIDDLESEX

Telephone: Howard 1601 Telegrams: Cuwire, Enfield

New depot speeds delivery of Hills doors

Part of the stock of many thousands of doors at Hills new Depot at Cuffley, Herts.



Prompt delivery has always been an important part of the Hills service. We are determined to maintain this principle in face of a widening demand for our doors.

For this reason, we have opened a new depot at Cuffley, Herts. It holds a stock of many thousands of our doors, in various designs. We can thus deliver immediately to customers in the Southern area. Alternatively customers may use their own transport to pick up supplies from the new depot.


For any building project you have in mind there is a Hills door. Sound, completely reliable, backed by a three-year guarantee—the same guarantee that Hills have offered for a considerable number of years!

Bearing in mind that we offer you first quality and outstanding service, you will find our prices most reasonable. And we can quote you more keenly still for large quantities. There is a Hills representative in your area who will gladly give you all the information you require. A card or call to your nearest Hills office will put you in touch with him.

Hills *a good name to
have on your door*

HEAD OFFICE: *F. Hills & Sons Ltd., Norton Road,
Stockton-on-Tees. Telephone: Stockton 67141.*

SOUTHERN OFFICE: *F. Hills & Sons Ltd., Sopers
Road, Cuffley, Herts. Telephone: Cuffley 2824/5.*



good thermal insulation calls for


VERMICULITE

No other material gives such good thermal insulation efficiency—at the same cost—as vermiculite. In lightweight concrete and plaster, or as a loosefill, vermiculite is being used more and more widely in modern building construction.

By constant research into the development of vermiculite and its application to modern building methods, the A.V.E. is making an important contribution to the advancement of general building design and construction.

Results have proved that this permanent, fire-proof, lightweight aggregate provides better thermal insulation efficiency—for no extra cost—than any other material.

*Specify one of these
branded A.V.E. Vermiculites.*



*Full technical information
from*

J. M. & J. Bartlett Ltd.
Lombard House
Warwick Street
NEWCASTLE UPON TYNE 2

Cape Building Products Ltd
114-116 Park Street
LONDON W1
Cowley Bridge Works
UXBRIDGE Middlesex

A. R. & W. Cleaver Ltd
Advance Works
Wood Street
NORTHAMPTON


Dupre Vermiculite Ltd
39-41 New Broad Street
LONDON EC2
23b Broadwater Road
WELWYN GARDEN CITY Herts

The Iron & Marble Company Ltd.
33-35 Victoria Street
BRISTOL

William Kenyon & Sons (MetaMica) Ltd
DUKINFIELD Cheshire
140 West George Street GLASGOW C2
50 Bloomsbury Street
Bedford Square LONDON WC1

L. Slack & Son Ltd
Courthouse Street
Pontypridd
SOUTH WALES

Issued in the interest of better insulation by the Association of Vermiculite Exfoliators 51-55 Strand London W.C.2



the finishing touch



W I N C I L A T E

slate copings

**are non-porous, inert,
do not warp, shrink or rot
and ensure a crisp,
precise skyline**

W I N C I L A T E


THE BOW SLATE & ENAMEL CO., LTD

B.R. Depot, Old Ford Road, London, E.3

Telephone : ADVance 2293

(Proprietors of the Aberllefenni

Slate Quarries)



THE OMNIA PRECAST FLOOR

combines precast and *in situ* methods of construction and appeals particularly to the Architect because it spans economically to over 30 feet and gives a level and unbroken soffit without camber or bowing.

All are important points to us, especially these

In addition it has the following advantages

- Highly competitive
- Monolithic yet flexible
- Very low selfweight
- Easily manhandled
- Cheaply transported
- Quickly erected
- Requires no shuttering
- Adaptable for services
- Available everywhere

OMNIA CONSTRUCTIONS LIMITED

121 London Wall, London, E.C.2. MO Narch 2272/6





Please address your enquiries to your nearest Omnia Licensee

THE ATLAS STONE CO. LTD., LONDON
THE BLOKCRETE CO. LTD., SOUTHAMPTON
F. BRADFORD & CO. LTD., EDMONTON
EDWIN H. BRADLEY & SONS LTD., SWINDON
BRADLEYS (CONCRETE) LTD., DARLASTON
G. W. BRUCE LTD., ABERDEEN
T. C. CAMPBELL LTD., NOTTINGHAM

DERWENT CAST STONE CO. LTD., PICKERING
DUNBRIK (YORKS) LTD., LEEDS
HYDRAULIC PRECASTS LTD., NORWICH
LANCASHIRE CONCRETE PRODUCTS LTD., CHORLEY
JAMES K. MILLAR LTD., FALKIRK
JOHN NICHOLSON & COMPANY, ANNAN
ST. IVES SAND & GRAVEL CO. LTD., HUNTS.
SAMUEL TYZACK & CO. LTD., SUNDERLAND
SPEEDIFORM STRUCTURES LTD., SHIFNAL, SALOP

PENTA gives timber longer life



The most powerful wood preservative in commercial use is Penta — Monsanto's pentachlorophenol. Penta gives sure protection against dry rot, termites, furniture beetles, and long-horned and powder-post beetles. Other significant advantages of Penta include:

1. In Penta-treated timber, dimensional changes are negligible.
2. Less leaching — safer in ground contact.
3. Penta-treated timber is clean to handle, non-staining.
4. Penta-treated timber does not require re-seasoning.
5. Penta is chemically stable, has negligible volatility, and is virtually insoluble in water.

Architects and corporations can now specify timber Penta-treated by pressure and non-pressure methods; Penta-treated timber is now available from timber merchants throughout Britain.

Builders and householders can obtain Penta-based preservatives from the majority of wood preservative manufacturers. Monsanto will be glad to provide you with a list of suppliers in your area.

Penta is one chemical from the wide range Monsanto offers industry: a range to which Monsanto is constantly adding new, better products — as well as improving those you already use.



MONSANTO CHEMICALS LIMITED,

441 Monsanto House, Victoria Street, London, S.W. 1

In association with: Monsanto Chemical Company, St. Louis, U.S.A. Monsanto Canada Limited, Montreal. Monsanto Chemicals (Australia) Ltd., Melbourne. Monsanto Chemicals of India Private Ltd., Bombay. Representatives in the world's principal cities.

Monsanto chemicals
help industry —
to bring a better
future closer

Maximum output with minimum input **Riley Oil Burning Equipment**

— is designed for consistent high-combustion efficiencies

Type HL Burner

HIGH/LOW/OFF OPERATION

For capacities above 10 gallons per hour using 220 secs and 950 secs oil. Gives clean combustion and 13% CO₂ at variable firing loads. Incorporates one small and one large air register, each with its own atomiser. On low load only the small burner is alight, at high load both are working at optimum efficiency. Large burner has tip shut off, arranged for hot oil circulation to start and self cooling on shut down.

Type F Burner

ON/OFF OPERATION

Available in capacities from 20 lbs. to 90 lbs. per hour, using 220 secs oil. Air/Oil ratios and pressures are factory set to give suspended intense flame with 13% CO₂, and do not require further adjustment on site.

Type G Burner

ON/OFF OPERATION


Generally similar to type F burner, but designed for use with 40 secs oil.

Type M Burner

FOR HORIZONTAL SHELL BOILERS

Spill return type atomiser with output range of 3 to 1. Specially developed air register to give clean narrow flame without impingement. Hot oil circulation to start and self cooling on shut down. Suitable for light and heavy fuel oils.

For booklets giving full details of these burners, also Riley Oil Fired Combustion Chambers and Air Heaters write to:—



RILEY (IC) PRODUCTS LIMITED

A Member of the International Combustion Group of Companies.

NINETEEN WOBURN PLACE • LONDON • WCI • TELEPHONE: TERMINUS 2622

TGA.R04A



Kirkby is one of the largest post-war Municipal Housing Developments in the British Isles. It is equal in size to many of the official new towns. Commenced by the Corporation of Liverpool in 1952, over 6,000 dwellings have been completed. Several thousand more are under construction. Ultimately some 60,000 people will be housed at Kirkby.

Ronald Bradbury, PH.D., F.R.I.B.A., A.M.T.P.I.
(City Architect and Director of Housing)

The City of Liverpool is justifiably proud of its Town Hall. By any standards it is an architectural gem. Built to the design of John Wood of Bath between 1749 and 1755, it was enlarged by James Wyatt in 1789 and was further altered and restored by him after the fire of 1795.

Henry T. Hough, M.I.C.E., M.I.M.U.E., M.T.P.I.
City Engineer and Surveyor.
(Responsible for the maintenance of Public Buildings)

Selected for important assignments

For many years Leigh's paints have been known and used throughout the world in applications demanding the finest decorative and protective finish. Leigh's paints are specified in the two examples shown here.

LEIGH'S PAINTS

Sole manufacturers

W & J LEIGH LTD

LONDON BOLTON GLASGOW

MANUFACTURERS OF FINE PAINTS
FOR DECORATIVE AND INDUSTRIAL USE



Money is dear but... today **BEECHAM BUILDINGS** cost less

Beecham Buildings construct high-quality commercial and industrial buildings—from office blocks and small factories to large industrial layouts covering many acres—at prices which, over the past twelve months, have actually fallen. We accomplish it in these days of 6% by working quickly and eliminating waste.

A complete organisation speeds planning


We in Beechams have the *complete* building organisation. Our staffs of architects, surveyors, builders, civil engineers and reinforced concrete experts control mobile teams of specialists on every contract. We are accustomed and happy to work with clients' consultant architects, offering them either the service of our entire organisation, or acting as general or specialist contractors, so that they may employ whichever of our specialised facilities they need. By knowing what is involved in every contract, we can quote firm prices as soon as sketch designs are agreed, and so move on to a site months earlier than would otherwise be the case.

Modern methods rationalise building

Because we employ advanced techniques, we are able without sacrificing quality, to put up a factory faster, perhaps in only half the time it would be built by older methods. With capital tied up at 6%, this saving in time is a heavy saving in money. Every contract is kept under one control so that every operation can be accurately timed to eliminate site delay. Highly mechanised casting shops produce large and varied types of structural units under ideal conditions, and our specially equipped transport fleet enables us to integrate production with erection. We also incorporate traditional construction where this is desired.

Using the finest materials, we provide an enduring structure, requiring little maintenance, and which affords a high degree of natural light and thermal insulation. Beecham Buildings lend themselves to designs which are functionally appropriate and have an individual dignity.


**Beecham
Buildings**



Office block for Messrs. Norrons-Livdale Ltd.,
Tipton, Staffs.



Interior: Central Engineering Workshop. Messrs. Bryant & May Ltd.
Architects: Messrs. Hastie, Winch & Kelly



Exterior: Messrs. Bryant & May Ltd.

*The Beecham Organisation
offers Architects the
fullest service and
co-operation*

BEECHAM BUILDINGS LTD.

SHIPSTON-ON-STOUR, WARWICKSHIRE
Telephone: Shipston-on-Stour 315 (6 lines)


AP70

TO CARRY 100 TONS
12' LONG · 18' WIDE · 8' HIGH
BUILT IN 16 MAN DAYS

TOTAL COST

£340

*Bar rack with storage installation
 in the works stores of Witton James Ltd., Electrical Engineers, London, N.W.9.*



With Dexion efficiency doesn't cost a great deal of money! For only £340 this bar rack with storage above was designed and erected by Dexion Ltd. in the works stores of Witton James Ltd. Selecting the right bar from this strong tailor-made rack is a much simpler matter now.

It's yet another example of a job completed more quickly at less cost because the material selected was Dexion Slotted Angle! Dexion can be used to construct practically anything—storage racks, work benches, conveyors, maintenance platforms. These sort of jobs can usually be erected by unskilled labour, because 80% of the work is engineered into Dexion before it reaches the customer. All that remains to be done is to cut it to length and bolt it together. Dexion structures are easily added to, reduced in size, moved or dismantled and re-erected in another form. There is no waste with Dexion.

Have you a construction problem? If you want a really efficient job completed in record time, choose Dexion. You will be astonished, too, at the money it saves.

It's amazing what you can do with DEXION slotted angle



DEXION LTD · MAYGROVE ROAD · LONDON · N.W.6 · TELEPHONE: MAIDA VALE 6031 (21 LINES)

PUTTING IN THE DAYLIGHT

...at
**Messrs Colville's
new Ravenscraig Works**



The metal windows chosen for the extension to Messrs. Colville's steel works had to be good. Steelmen have a critical eye for any product made with the materials they produce. Standard Maclean Metal Windows were chosen—because Standard Maclean make a really thorough job of rust proofing their product. Their Electro Galvanising plant is fully automated, which ensures that no damage is done by careless handling during the finishing processes.

Technical note: all Standard Maclean Metal Windows are degreased, pickled, zinc plated and phosphated, then two coats of primer are stoved on separately. 'Z' section mild steel sections are flash-welded for frame construction, whilst the fittings are of manganese brass and are screwed on.


**Standard Maclean
Limited**

STANDARD MACLEAN LTD. CADZOW WORKS, LOW WATERS RD, HAMILTON, Lanarkshire.

Hamilton 1410/4

ABERDEEN: 13 Bridge Street, Tel.: Aberdeen 52331. **EDINBURGH:** 7 Albany Street, Tel.: Waverley 2190. **NEWCASTLE:** 14a Pilgrim Street, Tel.: Newcastle 27776. **BELFAST:** 32 Ann Street, Tel.: Belfast 32003. **LIVERPOOL:** 39 Gardners Row, Bevington Bush, Tel.: North 0491. **LONDON:** W.C.1: 36 High Holborn, Tel.: Holborn 2462. **BIRMINGHAM:** 29: Selly Oak, Tel.: Selly Oak 1188. **SHEFFIELD:** Trinity Works, Eyre Street, Sheffield, 1. Tel.: Sheffield 20162. **DERBY:** Friargate Works, Tel.: Derby 48227.


PD4



Woodberry Down School . . .



is fitted with L.E.F. Raising & Lowering Gear



THE means of servicing inaccessible lights in the Assembly Hall of this new school was given careful consideration at an early stage of planning by the Architect (Robert H. Matthew, C.B.E., A.R.I.B.A.) and the Chief Engineer L.C.C. (J. Rawlinson, C.B.E., M.Eng., M.I.C.E., M.I.Mech.E.)

London Electric Firm Ltd., were consulted, with the result that they were able to supply Raising and Lowering Gear that was built into the ceiling with all working parts concealed.

L.E.F. Raising and Lowering Gear enables maintenance staff to bring light fittings down to floor level so that they can be dealt with quickly and conveniently. It outdates other cumbersome methods and is more economical in time and labour.

When you have a similar lighting problem, remember that it is most important to discuss your needs with L.E.F. at the planning stage: first to satisfy your technical requirements and secondly to ensure suitable delivery.

LONDON ELECTRIC FIRM LTD. South Croydon, Surrey. Telephone: Uplands 4871




A.E.I.

Lamp and Lighting Co Ltd

Lighting flexibility in the Science Museum

Mazda fluorescent lighting in one of the exhibition galleries of the Science Museum, London.

Four rows of 'Invertrunking', each 110 feet long, carry continuous lines of batten fittings from the 'Family' range. The Mazda Fluorescent Tubes are fitted with polystyrene clip louvers butted end to end. Shallow reflectors, specially designed by the Ministry of Works, are mounted at intervals on top of the 'Invertrunking' to provide upward lighting.



'Invertrunking' enables great flexibility to be achieved in any lighting scheme. It can be suspended as in the illustration above, built into secondary ceilings or mounted flush on to existing ceilings. By using the standard components of the 'Family' range of fittings the character and intensity of the lighting can also be changed without materially interfering with the electrical installation.


Mazda

Lamps stay brighter longer

14715

A.E.I. LAMP AND LIGHTING COMPANY LTD

Publicity Department: 18 Bedford Square, London W.C.1



ARCHITECTS: MESSRS. REDGRAVE & CLARK, A.R.I.B.A., F.R.I.B.A.

MYKO

ROOFS

FLOORS

R. C. FRAMEWORK

and
ART STONE CLADDING

FOR THESE FLATS AT ROYAL LEAMINGTON SPA

The design and erection of the R.C. framework, floors, roofs and Art stone cladding on the above contract was undertaken by the Myko organisation. We can offer competitive schemes and estimates for the design and supply of reinforcement and the design and erection of all types of R.C. structures and Myko floors, roofs and Greenco Hollow beams throughout the British Isles. Our design and Technical service is available for consultation at all times.


Myko self-insulating roofs and floors are available in the following spans. Standard Myko to 18ft. clear span. Pre-stressed Myko to 34ft. clear span. Greenco Hollow beams to 18ft. clear span. Manufactured at Leeds, Cullingworth (Bradford), Newcastle, Romford (Essex), Portland (Dorset), Wisbech (Cams.).

George Greenwood & Sons Ltd

King's Cross Street, Halifax
Halifax 3201

and 4 Ashley Place, Victoria, S.W.1.
Tate Gallery 2451

Manufacturers of: Flags, Kerbs, Ready Mixed Concrete and Reconstructed Stone, Bricks, etc.



HILLS

**Structures and
Foundations
Limited**

*offer a
complete service
covering the design and
construction in
reinforced
concrete of
foundations and
structural
frames*

HILLS Structures & Foundations Limited

HEATHER PARK DRIVE

WEMBLEY

MIDDLESEX

WEMBLEY 9481/2



CONFIDENCE

The confidence that architects have in Lead is measured in centuries—not years. Its pre-eminence for Weatherings is amply demonstrated by the extent to which it is specified for all but the cheapest work.

Bank of London & South America, City of London.

Architect: Victor Heal, M.C., F.R.I.B.A.

Contractors: Trollope & Colls Ltd.

The quality of Lead is unquestioned: it is unchanged by long exposure to town or industrial atmosphere; it can be readily dressed to the most intricate shapes.

Wherever a weathering is needed no material inspires confidence of permanent weathertightness as does

LEAD

h

LEAD LASTS


The Association's Technical Information Bureau will gladly help with problems on the use of Lead Sheet and Pipe in building work. Details of the main uses are given in a series of Information Sheets and Bulletins, which can be obtained by applying to the Association.

LEAD DEVELOPMENT ASSOCIATION

18 ADAM STREET, LONDON W.C.2

Telephone: Whitehall 4175

Telegrams: Leadevop, Rand, London



P156



- STRONG - LIGHT - TRANSLUCENT

FILON



polyester/glass fibre/nylon

STRUCTURAL SHEETING

A continuous process gives FILON structural sheeting its complete reliability: uniform strength, uniform thickness, and uniform light transmission throughout every length. It is shatterproof and resilient... you can walk on it or drop weights on it without serious damage. Non-corrodible and unaffected by climatic extremes FILON diffuses light and passes up to 85% of visible rays. Its durability makes it economical to install whilst it is light, easily handled and worked with ordinary carpenter's tools.

Write for descriptive
leaflet and prices

FILON properties

Acid and chemical resistance · Admits 85% of light
Available in any length · Easy handling
Shadow-free lighting · Standard profiles
Held by standard fastenings
Low transport and storage costs
Needs only light supporting framework
No maintenance or replacement costs after installation

FILON applications

(Indoor and outdoor)
Roof sheeting · Wall cladding · Partitions · Garages
Sheds · Workshops · Shower or bath enclosures · Barns
Greenhouses · Horticultural sheds
Concrete shuttering · Fencing · Glazing
Diffused ceiling and wall lighting · Shopfitting
Exhibition stand construction



for light with lightness and strength with economy

STRUCTURAL SHEETING

B.I.P. Reinforced Products Ltd., Streetly Works, Sutton Coldfield

Telephone: Streetly 2411



*What happens in a public building
when the mains are suddenly interrupted?*

Utter darkness? Fumbling for matches?


*Not if Pritchett & Gold Emergency
Lighting Equipment is installed. This
will instantly, automatically, switch
on emergency lights while the fault is
traced and repaired. There are
P & G equipments suitable for
all types of building.*

PLEASE SEND FOR DESCRIPTIVE BOOKLET TO:


PRITCHETT & GOLD and E.P.S. CO. LTD., 137 VICTORIA STREET, LONDON, SW1

(BATTERY MAKERS SINCE 1882)


PG34




— STRAIGHT SLIDING INDUSTRIAL —



— FOLDING DOMESTIC —




— POWERED AND SPECIAL APPLICATIONS —



— THE UPOVER —

Door Craft by **KING** craftsmen


For sheer versatility and dependability, the KING range of doors and door gear is unbeatable. It is the result of 40 years experience in the design and construction of doors of every type, from simple domestic to remote controlled power-operated giants. We can't hope to tell you all about it here, so why not tell us your problems? Our representative will call to advise you, *anywhere*, without obligation.



WRITE FOR THIS FREE
156-PAGE CATALOGUE

This is a valuable work of reference with a wealth of information about door gear. Just write 'Door Gear' on your business heading, post it to the address below, and we'll send you your copy.

GEO. W. KING LTD., 201
ARGYLE WORKS, STEVENAGE
HERTS. TEL: STEVENAGE 440



— AROUND-THE-CORNER —



REGISTERED TRADE MARK

**DOOR GEAR CRAFTSMEN
FOR 40 YEARS**

FRENGER HEATED & ACOUSTIC CEILINGS

**millions of
square feet
erected**

The credit squeeze has had the effect of making architects and property owners more cost-conscious than ever before—every penny spent must give full value for money. It is therefore very significant that, over the last few years, many millions of square feet of Frenger Ceiling have been erected—proof positive that the Frenger system gives full value for money and is 100% efficient in operation.


Commercial Banking Co. of Sydney Ltd. Architects: Waterhouse & Ripley, P.P./F.R.I.B.A.



Write for more details to

FRENGER CEILINGS LTD • 7-12 TAVISTOCK SQUARE • LONDON • W.C.1 • Telephone: EUSTON 6084-8

There's wonderful value in the 'TAY' RANGE



One-piece Flush Plate and Switch. The 'Tay' range of switches use one-piece construction. But all current carrying parts are mounted on high grade vitreous porcelain.

Plaster depth boxes. The 'Tay' range of flush plate switches are designed for use with extra-shallow plaster depth boxes. They are self-adjusting to varying plaster levels. This combined with easy wiring cuts installation costs.

AC only, solid silver contacts. The switch action is slow-break A.C. only, with solid silver contacts. The switch action is controllably silent.

Two-gang on standard 3 1/4" square plate. The two-gang 'Tay' plate switch has overall dimensions no greater than the standard 3 1/4" square plate one-gang switch.

The 'Tay' Range is ideal for the competitive domestic installation where low cost, easy installation and good appearance are desirable features.



Send for your copy of the MEM-Tucker-Kerson Catalogue List No. 370—the most complete accessories catalogue in the trade.



MIDLAND ELECTRIC MANUFACTURING CO., LTD., TYSELEY, BIRMINGHAM, 11

**MOSAIC
CLADDING
PANELS**

are now being produced
in a variety of patterns
and colours in addition
to the range of exposed
aggregate panels.




JOHN ELLIS & SONS LTD., 21 NEW WALK, LEICESTER.



The doors commanding the world's largest sale

build a rolling door over 6 men high



Over six men high—38½ feet by 21 feet wide, this Brady Roller Door operates electrically, at the touch of a button! Rolled up, it is out of the way; down, it is safe against intruders and the weather, and how easily closed! This fine example of Brady engineering was built for the Neptune Works of Swan Hunter and


Wigham Richardson Ltd, Newcastle-upon-Tyne.

Send for fully informative literature No. 3.

G. BRADY & CO. LTD · MANCHESTER 4

Telephone COLlyhurst 2797/8

manufacturers of Brady hand and power operated lifts



we shutter the world

London: Thames Works, Strawberry Vale, Twickenham, Middx. Birmingham: Rectory Park Road, Sheldon 26. Canada: David C. Orrock & Co. (G. Brady & Co. Canada Ltd.) 4925 De Sorel Street, Montreal, Que. and also at Suite 2/23 Applemoore Village, 1077, Queen Elizabeth Way, Fort Credit, Ontario. Norway: An Thorbjørnsen, Kongensgate, 14, Oslo. Hong Kong: Blair & Co. Ltd, Windsor House.

HY-RIB ceiling survives four-hour FIRE test

Plaster on a Hy-Rib base is true and sound — held fast and fortified by the steel mesh and tangs. And it is a very efficient fire shield. At the Fire Research Station recently a thin concrete floor — an uncertainty for a one hour rating — qualified with a Hy-Rib ceiling close below for four hours fire resistance. In the last stages of the test, the furnace temperature topped 1120°C., yet Hy-Rib still held the basic hemihydrate gypsum plaster intact. We will gladly advise on the fire resistance potential of any floor and Hy-Rib combination. Ask for Hy-Rib Department.

*Whatever the floor, a Hy-Rib ceiling
will much increase the fire resistance*



HY-RIB

The Tinned Concrete Reinforcing Company Limited, 25-26 Lower Marsh, London SE1 WATERLOO RD



MAKE SURE YOU KNOW ALL ABOUT THIS CTC DOUBLE-DUTY OIL FIRED BOILER

TWO IN ONE UNIT!

DOMESTIC HOT WATER SUPPLY 150°F.

CENTRAL HEATING 95°F.

and C.T.C. CUT COSTS!

THIS IS HOW:—An indirect cylinder is fitted inside the Boiler-shell thus supplying domestic hot water and dispensing with the extra piping between boiler and cylinder—heat losses are eliminated. Each circuit is independently controlled so that maximum heat for domestic water is obtained with the advantage of controlled heat for the radiators.

Over 10,000 C.T.C. OIL FIRED Boilers are in use in private homes and Industry. With C.T.C. you have the most advanced system of heating, backed by the service of heating specialists with over 25 years experience.

Architects, Heating Engineers and Builders everywhere are recommending and specifying C.T.C.—it is the sure way to ECONOMY and EFFICIENCY.



HEAT LTD.


17 SLOANE ST., LONDON, S.W.1

Telephone: BELgravia 3478/6286

Write NOW for leaflet, or 'phone for particulars

Building the modern way

with Curtain Walling



Constructed for T. Lucas & Co. Ltd., Architects, George Brown & Partners, Bristol. A.R.I.B.A., F.I.A.S.

Write for full details to

TEMPLEWOOD HAWKSLEY

**WORLD LEADERS IN
ALUMINIUM STRUCTURES**

TEMPLEWOOD HAWKSLEY LTD., SLOUGH, BUCKS.

TEL: SLOUGH 23212 Member of the Hawker Siddeley Group.



£250 design competition for a kitchen sink

BELIEVING that inventive skill has not yet produced the perfect kitchen sink, The British Sanitary Fireclay Association on behalf of its member firms is sponsoring an open Design Competition to stimulate ideas which incorporate improvements in the usefulness and appearance of this essential item of kitchen equipment.

White or coloured ceramic glazed Fireclay, of which most sinks are made, is ideal for its purpose since it can readily be moulded in complex shapes having smooth contours; it possesses great strength and resistance to wear. Already there is a choice of several good designs in fireclay sinks available to the housewife, who knows from experience how functional and hygienic they are. Now the Association is searching for designs that are even better.

The Assessors will be D. L. Medd, Esq., A.R.I.B.A., R. V. Cooper, Esq., C.G.I.A., F.I.O.P., M.R.S.H., and the President of the National

Federation of Clay Industries. After the results have been announced, arrangements will be made to produce prototypes of at least the winning design (for which the collaboration of the successful competitor(s) will be invited). The Competition has been planned to appeal especially to architects, students, designers, sanitary engineers and others with a serious interest in sanitation and design.

It is already regarded as yet another progressive move by a flourishing British Industry. Considerable interest is being shown. The Competition is indeed a challenge, and the winning designs should command widespread notice. A first Prize of £100, two Prizes of £50, and five runner-up Prizes of £10 each await those who submit the best ideas. Closing date 31st May, 1958. Entry Forms are available on application to:—

**THE BRITISH SANITARY
FIRECLAY ASSOCIATION**


57 Great George Street, LEEDS

Specify

ceramic glazed fireclay

sanitary ware for strength and durability

Ready for reference



**Write for
your copy now!**

IMPERIAL CHEMICAL INDUSTRIES LIMITED, LONDON, S.W.1.




**Hardness
+ Flexibility
= the longest life**

DECORATIVE

Based on Gay's own alkyd-type media, GAYMEL enamel combines hardness of gloss with adequate flexibility and exceptional adhesion. It is these properties that enable buildings enriched with GAYMEL to retain freshness of decoration through years of exposure.

Please write for further information about this remarkable new development in paint manufacture.



Good quality oil paint is capable of long preservative life, but is soon dulled and stained by exposure.

Hard Gloss Paints, when flexibility is inadequate, may fail to expand and contract with the slight but inevitable movement of timber surfaces.

GAYMEL is impervious to atmospheric pollution, preserving its colour and gloss. Flexibility and adhesion hold Gaymel against normal movement of all building materials.

GAYMEL enamel

another **sound paint — by GAY'S**



MANUFACTURED BY R. GAY & CO.
WESTMORLAND HOUSE, 127/131 REGENT STREET
LONDON, W.1.

Telephone: Regent 0831

BRANCHES IN • BIRMINGHAM • BRISTOL • BELFAST • GLASGOW • LEEDS • MANCHESTER

From Washington...

Free from dust

Obviously the Washington Wall Radiator can be easily cleaned—an essential factor in hospitals and schools, and wherever hygiene is necessary. The stream of warm air caused by convection carries no dust to pollute the atmosphere

Light

Being of lightweight pressed steel the Washington Wall Radiator is easily supported, economically handled

Attractive


Smooth, streamlined and slim, the Washington Wall Radiator ideally matches modern architectural trends; its touch-smooth finish is unobtrusive against any background

The Washington Wall Radiator ensures minimum projection and is attractively slim in appearance

Slim

... A Revolutionary Wall Radiator

Manufactured as single and double panel



WASHINGTON ENGINEERING LTD.

P.O. BOX NO. 4, WASHINGTON CO. DURHAM.

Telephone: Washington 2362-3.

Telegrams: Wearco, Washington Station.

(Full range of pressed steel column radiators also available)

SOLE AGENTS: Messrs. BROWN & TAWSE TUBES LTD.,

BRANCHES AT DUNDEE, GLASGOW, LONDON, MANCHESTER & BIRMINGHAM.

WEL 3

Don't delay - Post Today!

To Dept. A.J.
WASHINGTON ENGINEERING LTD.
P.O. Box No. 4, Washington, Co. Durham.

Please send me full details of the
Washington WALL Radiator.



NAME _____

ADDRESS _____

in Armitage genuine vitreous china

the 'Sanvit' urinal

single



V3009 'Sanvit'

urinal range. Assembly includes outlet strainer with china dome to each stall. 'Nuva' automatic flushing tank in vitreous china with copper syphon and regulating supply tap. Semi-concealed brackets. Flush pipes with wall clips. All fittings heavily chromium plated. Urinal sizes (each stall): Width 18". Height overall 42". Height from floor 38". Wall to front of lip 16". Recommended centres in range form 24"

Ask for catalogue 'A' and leaflet D/4 giving plumbing details

strong, hard, hygienic

Hard, vitreous china — the most suitable material of all for urinals: strong, durable, non-crazing, non-absorbent, unaffected by frost and extreme weather conditions. And it's hard all the way through — difficult to chip, and even when chipped there's no porous surface for germ-breeding

minimum installation costs — and full flexibility

No cutting or trimming of edges — no channel with joints to leak or smell. Each stall a complete unit with integral flushing chamber and independent outlet. Ranges of any number of stalls readily assembled

a high standard of cleanliness

Integral flushing chamber thoroughly washes surface. Large lipped base with sensible footspace helps to maintain cleanliness

in white — or any Armitage colour

Colour range leaflets and samples on request

Armitage Ware

Edward Johns & Company Limited

Armitage Staffordshire Telephone Armitage 253 (5 lines)

London office and showrooms

333/337 Grand Buildings Trafalgar Square WC2 Telephone Whitehall 8063 & 2488

**You have a
DATE
on TV**



hardec
regd.

**QUICKEST FIXING
PLASTIC SURFACE**

A series of

NINE COMMERCIALS

in the

LONDON TV AREA

For the first time in Commercial TV history a series of one minute spots specially produced for those professionally interested in using plastic surfaces. Full of information and full of interest. Don't miss it

See these live spots between 11-11.30 p.m.

MON. MARCH 31	WHY IS HARDEC THE QUICKEST FIXING PLASTIC SURFACE?
TUES. APRIL 1	HOW QUICK IS QUICKEST FIXING?
WED. APRIL 2	SEE HOW 'STRESSED-SKIN' CONSTRUCTION GIVES HARDEC STRENGTH
MON. APRIL 7	SEE WHAT ROLLER-SKATES CAN'T DO TO THE TOUGH HARDEC SURFACE
TUES. APRIL 8	ON HORIZONTAL SURFACES HARDEC FIXES QUICKEST
WED. APRIL 9	HARDEC—UNBEATABLE FOR WALL-CLADDING
MON. APRIL 14	BLACK CATS OR ANY OTHER DESIGNS BY THE NEW HARDEC DESIGN SERVICE
TUES. APRIL 15	DISTRIBUTION AND DISCOUNTS ARE TONIGHT'S SUBJECT
WED. APRIL 16	YOUR QUESTIONS ANSWERED ON THIS LAST PROGRAMME

hardec
regd.

*the board with
the built-on
decorative
plastic surface*


**THE AIRSCREW COMPANY AND JIGWOOD LIMITED
WEYBRIDGE, SURREY**

**INNER SPACE
YOUR PROBLEM?**



Pity the poor 'sardines' in offices and factories where expansion is the order of the day! Extra desks, cabinets and machines until there's hardly room to move. And it's definitely not efficient. Smart managers divide and rule their floor space with NSE steel partitioning—to make the most of every square inch. Non-vibrating steel and glass partitioning that can be altered in minutes, for different spaces. *Even cheaper than wood!*

*Visit our stand E30
at the Factory Equipment Exhibition—
Earls Court, 14-19 April*



NSE

**NORWOOD STEEL
EQUIPMENT LTD**

Makers of all kinds of steel office and storage equipment. Please write to Dept. G, for free illustrated brochures: "STEEL PARTITIONING", "STEEL OFFICE EQUIPMENT" or "STEEL STORAGE EQUIPMENT".

**149 Borough High Street, London, S.E.1. (Hop 5033)
and at Birmingham, Bristol and Manchester**

"astrapole"^{regd.}

featured in this Issue

the decorative wall finish

An unique spray painting process applied throughout to plaster-surfaces of Staircases, Lift Halls, Lobbies and Toilets of LONDON'S NEW SKYSCRAPER

astrapole was first applied to the Main Staircase of the Royal Institute of British Architects, Portland Place, London, W.1. in 1934. This has remained untouched for twenty-three years. Verb. Sap.

astrapole is specified by leading Architects. It can be applied in an endless variety of colour-combinations. Please write for patterns and details.


**astrapole is durable -
decorative - economic**

ROFFÉ LIMITED

213, Hornsey Road, London, N.7
Telephone : ARChway 4451-2-3

Your Enquiries are also invited for :

decorative conversions - fibrous plaster - period fire surrounds - decorations



FOUNTAIN HOUSE, Fenchurch Street, London, E.C.3

Architect : W. H. ROGERS, Esq., A.R.I.B.A.

Architects Department, City of London Real Property Co. Ltd.

Consultant Architect : SIR HOWARD ROBERTSON P.P.R.I.B.A.

STEEL
LTD

Steel office
Please write
Illustrated
IONING",
or "STEEL

5033)
ester




British Aluminium Showpiece clad in 'Wallspan'

Wherever it was possible to use aluminium in this building, aluminium has been used. 'Wallspan' curtain walling clads the outside, while inside, aluminium shows off its many and various talents from heated and acoustic ceilings to door handles and electric wiring.

In the entrance hall, the built-in furniture and the surround to the revolving doors are made in light and dark hardwoods set off with silver anodised aluminium sheeting. 'Imprest' sheeting lines the lift and clads the lift shaft and the lift doors themselves are lined with blue anodised fluted aluminium. Staircase balustrades are finished in silver anodised tube and strip and anodised aluminium is used for many of the light fittings.

The 'Wallspan' clads the building on the long north and south walls and is fitted with Williams & Williams purpose-made aluminium windows. A point of interest is in the dished aluminium spandrel panels of BA.45 alloy. This is a 5% silicon alloy which, when anodised, turns a medium grey in colour without the addition of any dye. The anodized film gives extra protection to the metal and the colour is entirely unaffected by exposure to sun and weather. The panels are all 18 gauge, backed up with medino board with a cavity in between.



The structural columns have been faced with black slate and incorporated into the decoration of the façade. They contrast with the silver colour of the Wallspan members and the grey of the spandrel panels.

*New Office Block for
The British Aluminium
Company Ltd., Rolling Mills,
Bainsford, Falkirk.
Architect: Chief Architect,
British Aluminium Company.*



When double glazing is not quite justified . . .

George Wimpey found that the noise of trains at the site of their new head office was sufficient to be troublesome, but not sufficient to justify the use of double glazing. The problem of reducing the noise level was given to the Williams & Williams technicians, who suggested the use of special square tubular aluminium window sections with extruded channels to house strips of P.V.C. These strips effectively perfect the draughtproofing and damp the noise down to a point where it is no longer fatiguing.

An interesting feature is that although these windows are double side-hung, there is no meeting rail. They are caught in their closed position by espagnolette bolts.

These are the special Williams & Williams window sections. The P.V.C. is firmly held in the channels shown and will not perish through exposure to weather.

*Architect: E. V. Collins, A.R.I.B.A.,
Chief Architect,
George Wimpey & Co. Ltd.*



Member of the Metal Window Association

WILLIAMS & WILLIAMS

RELIANCE WORKS · CHESTER



*Architect: F. Reginald Steele, F.R.I.B.A., R.I.B.A. Dist. T.P.,
F.R.I.C.S., M.T.P.I., A.M.I. Struct. E.*

Two Schools for West Sussex County Council

Left. Williams & Williams purpose-made and off-standard steel windows and doors were used in the new Weald County Secondary School at Billingshurst.*

Above. The new main entrance at the Grammar School, Midhurst has Williams & Williams purpose-made swing doors. A new gymnasium has also been built, using Williams & Williams purpose-made steel windows.

* The photograph is taken from inside the hall, with one of the classroom blocks in the background.

**THOSE CRITTALL CHAPS
REALLY KNOW A LOT
ABOUT ELECTRIC HEATING**

It makes me shudder to think of the trouble I had with heating systems before I called in Richard Crittall. No problems now, though. Those Crittall chaps *really* know how to choose between **ELECTRICITY, COAL, OIL** or **GAS** to provide the best and most economic system in each case. Their advice is completely unbiased, too! They can handle the entire heating system whatever the type and if it is decided that electricity is the answer they can also handle the general wiring. That, you will agree, is a complete service! Take my advice, if you have heating problems, 'phone those Crittall chaps at MUSEum 3366—you won't regret it!



Richard Crittall

ENGINEERS FOR HEATING

RICHARD CRITTALL AND COMPANY LIMITED
151 GREAT PORTLAND STREET · LONDON · W.1

LIVERPOOL
Central 3283


BIRMINGHAM
Midland 7211

GLASGOW
Douglas 8761-2

BRISTOL
Bristol 33062

GREENWOOD - AIRVAC ROOFLINE EXTRACTORS

for natural ventilation of industrial buildings



Photograph by courtesy of
A. Wander Ltd, Ovaltine Works, Kings Langley, Herts.

Architect: G. P. Nides, A.R.I.B.A.
Contractors: John Mowlem & Co. Ltd.

Ideal for providing either permanent or controlled ventilation by natural means in all types of industrial buildings, this patent Roofline Extractor has been designed to provide a highly efficient and thoroughly reliable roof-mounted extractor, and is included in architects' specifications

because . . . low overall height ensures an unbroken roofline
closed top design provides complete weathering
unique splitter type control ensures heat conservation
strong construction withstands all climatic conditions
heavy gauge hardened aluminium ensures high corrosive
resistance and durability

and, finally, because of Greenwood-Airvac's reputation for sound design
and good quality.

Please ask for leaflet RE 3 for further details of the Roofline.

Visit Stand E 49, Factory Equipment Exhibition, Earls Court, April 14-19.

Greenwood-Airvac ventilation

GREENWOOD'S AND AIRVAC VENTILATING COMPANY LTD

PATENTEES, DESIGNERS AND MANUFACTURERS OF
VENTILATING EQUIPMENT AND ELECTRICAL
CONDUIT SYSTEMS.



BEACON HOUSE, KINGSWAY, LONDON, W.C.2.
CHANCERY 8135 (4 LINES). 'AIRVAC', LONDON.



- The latest development in Air Conditioning
- Individual temperature control in every room
- A centralised plant silently diffusing clean air, conditioned for winter or summer
- New pressure conduit distribution system minimises duct space requirements
- Equally applicable to new or old constructions

Carrier

Conduit WEATHERMASTER^{REGD.} System

CARRIER ENGINEERING COMPANY LTD. 24 Buckingham Gate, Westminster, S.W.1
Telephone: VICTORIA 6858

The Pioneers of Air Conditioning



THE ARCHITECTS' JOURNAL

No. 3293 Vol. 127 April 10, 1958

9-13 Queen Anne's Gate, London, S.W.1. Tel. WHI 0611

Subscription rates: post paid, inland £2 15s. 0d. per annum; abroad, £3 10s. 0d. per annum. Single copies, 1s.; post paid, 1s. 6d. Special numbers are included in subscriptions; single copies, 2s.; post paid, 2s. 6d. Back numbers more than 12 months old (when available), double price. Half-yearly volumes can be bound complete with index in cloth cases for £1 10s. 0d.; carriage 2s. extra.

NOT QUITE ARCHITECTURE


BRUSSELS GETS A MOVE ON

The British, who have apparently a constitutional inability to plan for the motor vehicle, have really no right to criticize the Belgians for the astonishing feats of road building they are performing in and around Brussels. But splendid as is the determination the Belgians have shown to get the traffic moving, and exciting as it is to plunge at 50 m.p.h. or more down an underpass and then to be whisked up on to an elevated roadway, one cannot help thinking that it looks like a road engineer's crash programme executed with hardly a thought for the future appearance of the city.

But it is certainly a sign that the Belgians can get things done, and get them done quickly, and are not frightened of spending money to make the international exhibition a success. The grounds of the World Fair (or Part-World, really, as Asia, Africa and the British Commonwealth are not at all well represented) are now the scene of a last-minute frenzy as the promoters of the national pavilions and the Belgian authorities move heaven and earth (particularly earth) in an attempt to get everything ready for the press day on April 15.

Although the pessimists shake their heads knowingly, and tell you that the French have no intention now of being ready before June or even July, nobody else is prepared to admit that his pavilion will be late, however great the apparent chaos in which it is plunged, and however immense the labours that have still to be performed. The exhibition authorities refuse to commit themselves: "we hope . . ." is as much as they will say.

Only the French have completely given up hope; although the furthest behind they are making the slowest progress. The steel boom, which is intended to act as a counterweight to the cantilevered girders of the roof structure, still lies forlornly half-finished, propped up by four cranes and lying on the pedestrian bridge. It has become



Office reshuffle?

Here's a trump card

SANKEY-SHELDON Adjustable Steel Partitions provide complete flexibility of lay-out. They can be quickly and easily erected and the standard component assembly permits alterations and additions with minimum expense. Flush or Semi-flush Partitions—rigid, durable and fire-resisting—are available in a choice of colours. Our Technical Division will advise on all floor space planning problems and prepare schemes.

MOVABLE STEEL PARTITIONS BY


Sankey • Sheldon

OF COURSE!

46, Cannon Street, London, E.C.4.

Telephone: CITY 4477 (18 lines)

Also manufacturers in steel of:—DESKS • SHELVING
TABLES • CHAIRS • FILING CABINETS • STORAGE BINS
CUPBOARDS • CLOTHES LOCKERS • LIBRARY SHELVING



A Building in the Landscape

In these days of credit squeeze and cut budgets the full landscaping of new buildings is a rarity, confined mainly (and ironically) to large exhibitions. When the Congress Hall in West Berlin (seen above from the south) was opened last autumn, the landscaping was almost complete; the whole operation was achieved in the fifteen months since foundation work was started in June, 1956. Visitors to Berlin this year will consequently be able to see a modern building set in a landscape with all the appearance of maturity. Right, are two views of the main auditorium, which seats 1,200. Further pictures and a description of the building appear on pages 535 to 537.

a serious obstruction at the very heart of the international section, and it would be surprising if the French have not been given an ultimatum either to get the thing up, or to take it away and let the exhibition get on.

In a determined effort to get the work finished the authorities closed the exhibition to the press on March 31. In the few days before that, remarkable transformations were taking place, as roads, paving, lawns, hedges, shrubberies, orchards and even a small forest went down. Walking from one pavilion to another became more and more hazardous, if one wished to avoid being scooped up by a shovel, pushed aside by a bulldozer, rolled flat by a roller, or merely squashed into an irregular shape by a lorry or a fire-engine.

These are trying days for the architects, except for the happy few (among whom the Germans and the British take first place) whose pavilions seem certain to be ready. To find the architect of a large pavilion is quite a feat. Where is the Russian? The uniformed gentleman whose job it is to keep visitors at bay looks inside the vast glass pavilion, and shrugs his shoulders: he may be in the cinema, in the coal mine, in the oil-well; who can tell? The American is to be seen arguing with Belgian contractors about the way to execute the details of another architect's design. The Yugoslav has left to see about some glass. The Venezuelan has had his kitchen, finished only the day before, destroyed by fire. The Spaniard is engaged in lengthy conferences with his Minister, who seems to disapprove vehemently of the arrangements—although that may merely be Spanish eloquence. The Czechs are having to operate from a tiny little office, approached by a narrow stairway up which burly men try to force their way, ducking under scaffolding while a workman patiently tries to get on with the painting.

One thing that seems certain is that the public is going to have a bellyful of atoms, nuclear energy, reactors and electricity. The Americans, who have adopted the slogan "no boasting," and have played down their industrial might, may prove to have been far-sighted. But the more recently industrialized nations can hardly afford to take their achievements for granted. The 370-ft. high Atomium, with its nine metal balls representing the structure of the atom, dominates the entire exhibition. It is bigger, and far more impressive, than one would gather from the photographs.

But the atoms on show are strictly for peace. A visitor from Mars would never learn from Brussels that anything so unpleasant as an H-bomb exists; nobody has been so indiscreet as to put one on show. It is going to be worth going to Brussels, not only to see the architecture and the individual exhibits, but to see the nations in their party suits and on their best behaviour, trying to look not as they are, but as they would like the rest of the world to see them.

M. M.

The Editors

THE ARCHITECT'S VIEW ON EDUCATION

WHAT are the architects who are taking part in the Oxford Conference on architectural education going to say? Are they going to speak with a babel of tongues, or are they going to present some clear, well-thought out ideas? Unless they do the latter it seems unlikely that a conference which is a very mixed bag, including architects, educationalists, university dons, art teachers and builders, can come to any useful conclusions in the short space of two days. It seems obvious that as the whole building industry moves forward with increasing impetus from the craft stage into that of the application of science and industry to building and planning techniques, so a great deal more co-operation and co-ordination among the specialists becomes necessary at the educational stage. And we need at the same time both to improve our existing specialists and to create new ones. The proposal for a University Faculty for the building industry which was advanced by Percy Johnson-Marshall has met with little adverse criticism, and seems to be the soundest method of creating an educational organization which would be comprehensive and strong enough to cope with future needs. But between this idea and its achievement lie a number of stumbling blocks.

It is very sad that there is still any argument in the profession as to whether architects should be taught by the articulated pupillage method. The whole system of articulated pupillage and external examinations is obsolete and needs to be changed as soon as possible. So the first objective is to get all students into schools of architecture.

Second, schools of architecture are an odd enough collection of educational bodies at the present time. They are attached to university faculties of arts, schools of art, polytechnics, and two are even independent institutions. One might well ask what the medical profession would think of such a muddle. The second clear objective should be to get as many as possible of the schools into universities.

Third, and far more important than worrying about details of the curriculum, although that is important too, is the quality of staff. Teaching should attract the best men, and a whole session could be spent on this problem.

Fourth, busy architects criticize the schools for being too theoretical, and for not having enough practical work in their courses. Here the Birmingham School, as we said last week, has given an excellent lead in organizing practical work, and this principle, or variations of it, could be safely recommended to all the other schools.

Fifth, schools of architecture, compared with other places of learning, are extraordinarily deficient in facilities for post-graduate research. Both Liverpool and Edinburgh have been taking active steps to remedy this deficiency, and here again their lead might well be followed by the others. And, one might add, what about post-graduate refresher courses for

rusty architects and jaded teaching staff?

The suggestions outlined above would at least give us a competent educational machine for today. But we need to think in broader terms than the school of architecture by itself. Some schools have been doing this in a limited way for years, as the departments of town planning bear witness. But what about all the other associated disciplines, some of which have never been heard of within the portals of a university? Why don't the university schools take a cue from the Polytechnics and start joint courses for architects, building managers, quantity surveyors and structural engineers?

HOW MUCH DO WE EARN?

The Ad Hoc Committee of the RIBA, by collaborating with the Royal Commission on Doctors' and Dentists' Remuneration in taking a random survey of architects' remuneration, is taking another important step forward in its work. The results will be valuable to the Royal Commission, but that is of minor concern to us. The important thing is that for the first time the RIBA will be in possession of information that is absolutely vital to the work of raising the status and the rewards of the profession. Success does depend, however, entirely on the questionnaire being properly completed and promptly returned by the 20 per cent of the profession to whom it is being sent. We do urge all those who are included in the sample to realize that the questionnaire must, at the latest, be returned this week-end.



BRUSSELS: A FIRST OPINION

Political columnists don't usually take notice of architecture. But James Cameron, the *News Chronicle's* top

political writer, took time off to look at the Brussels Exhibition a fortnight before the opening. His comments were pungent. He wrote with respect of the German pavilion and was tolerant about the experimental structure of the French. This, alas, is what he had to say of the British pavilion:

"... a sad sight it is, one must admit—a group of pallid, tent-like shapes, pretentious and meaningless, something between an Atzec shrine and the Pyramids reproduced in pistachio ice-cream. . . . It is said to represent the formation of a crystal, though why it should I cannot imagine. . . . Outside this enfeebled essay in the bizarre stands a sort of seaside flagpole. The whole thing is an aesthetic aberration."

Not very encouraging for a first national press comment on Britain's major public relations effort of 1958. ASTRAGAL, who has already given some guarded opinions about the Exhibition, hopes he will be able to say something more cheerful than this in a week or two.

HATFIELD'S RUEFUL DECISION

After an eight-day sitting the Hatfield roof inquiry was still unfinished. This did not surprise ASTRAGAL who, as you will remember, was present on the first day. But what does seem surprising is that the whole thing should be adjourned for two months. Is this to suit the convenience of the lawyers? Have they got some juicy briefs that they are reluctant to give up? There must surely be a better reason. But what is it?

The architects, the builders, the clerk of works and others who have been criticized all want to know the inspector's verdict as soon as possible. So do people who have used the same or a similar roofing system. But the inquiry will not be renewed until six months after the roofs blew off. And this, of course, is the second inquiry.

Couldn't an official inquiry, in the hands of a technical man, have got to the bottom of the matter, without the help of a single lawyer, in less than eight days?

LOOK, NO HANDS!

Over the last few years the V and A has done a good job in re-organizing its exhibits on a shoe string, culminating in the great floodlit exedra—if that is the word—which backs up the big Bernini sculpture. The back of the exedra used to bulge into a cheerfully chaotic Costume Court, full of antiquated glass cases containing not-very-well-dusted period costumes. But ASTRAGAL is shocked to find that all this has now been disastrously cleared up. The dressed figures have been pushed back into large glass cases which fill the four giant niches in the diagonal corners of the octagonal court. The blocking-in of these niches has wrecked the architectural shape of the room, and what is worse, the centre of the court is now a great empty waste which gives an unobstructed view of the disaster.

Costume students are complaining that they can't circulate round the exhibits any more, and have to be content with only one view of each dress. ASTRAGAL was also disturbed by the new headless, handless dummies. They may be all right as a display conven-

tion. But when invisible wires are used to fix hand and head accessories the effect is distinctly off-putting. Free-flying fans are not too bad, but empty bonnets hovering above severed necks are really macabre.

THE TUC'S EPSTEIN

It was rather hard luck on the architect, David Aberdeen, that the news stories about the new TUC headquarters were centred on the Epstein sculpture rather than on the architecture. But the unveiling of the sculpture was, after all, the central part of the ceremony. And the building itself can hardly be regarded as news, because some parts of it have been occupied for 18 months.

*

This is a pity because, for all its faults, the building is not only a notable addition to London's street architecture, but also a superb bit of planning. But the Epstein? ASTRAGAL, who hates being on the same side as those who have decried the sculptor for years out of prejudice and bigotry—and is angry about the Blackpool Genesis story—cannot be enthusiastic about this new work.

*

His view is simple (though, of course, these things are a matter of taste). Epstein, the modeller in clay, is a great artist, and especially a great portraitist; but Epstein, the stone carver, seems a lesser artist altogether, and his unchanging mannerisms carry less significance as time goes on. At least the TUC had the courage to choose an original artist, not an academic *pasticheur*, for their memorial. But what a pity they didn't specify that it must be in bronze.

*

The building's embellishments will not be complete until the sculptural group alongside the main entrance, which is to be in bronze, is in place. This work, by Bernard Meadows, is now being cast at the foundry. You may remember that an abortive competition was held for both these groups of sculpture, and that no awards were made because the assessors (Herbert Read, J. M. Richards, the architect and a member of the TUC council) found nothing up to standard. It was after this that Meadows and Epstein were appointed.

In a way Meadows has the trickier job. A sculpture group in an enclosed courtyard is one thing. A group that has to make its mark in the bustle of a London street is quite another.

WOVEN PAINT

Graham Sutherland's final design for the 70-ft. high tapestry to hang at the east end of Coventry's Cathedral was published in colour in a recent issue of the *Builder*. Judging from this sketch (and it may not, of course, be entirely fair to do so) Mr. Sutherland has paid little attention to tapestry technique. The sketch is very much a painting, showing brush strokes and the additional marks which are characteristic of free-hand work. It seems odd that these personal, painterly touches are to be meticulously reproduced within the strict geometrical limits of a woven material. Large parts of the background to the throned Christ are roughly washed-in areas of plain green—some of them carpet size (10 ft. by 15 ft.). In the great period of tapestry design such large areas of plain colour (pointless with a hand process) were eschewed by the artist-weaver, who constantly enlivened his work with varying detail. In the Sutherland tapestry the humbler craftsman will have the extraordinary task of reproducing monochrome brush strokes enlarged to enormous proportions. Tapestry has certainly declined as a creative art.

DO IT THEMSELVES

ASTRAGAL, who likes to see new teaching methods put on trial, looks forward to hearing the results of a new AA School course on "Discovery of Materials." It was introduced by Peter Matthews, the senior construction lecturer, and it is intended to encourage individual study of building materials as an alternative to the usual straight lectures which send students to sleep with their highly-compressed mass of facts. A weekly programme provides a basis for study—required reading, useful references, appropriate exhibits and trade literature for the students' technical reference files. From time to time small groups of students discuss with the lecturer any problems they have come across, particularly problems of site supervision and practical application. The course is also designed to persuade students to use the reference library more fully.



Sir Jacob Epstein's statue of a mother holding her dead son was unveiled at the new TUC building on March 27. It is a memorial to the trade unionists who lost their lives in two world wars. See ASTRAGAL's comment on this page.

EXHIBIT FOR MOSCOW

ASTRAGAL learns, rather belatedly, that the British exhibit for the International Union of Architects' Congress at Moscow is to be on show at the Building Centre for a week only, from April 11 to 18. The theme of the Congress is Construction and Reconstruction of Towns 1945-47. The British exhibit will show post-war developments in London and Harlow.

ASTRAGAL

DIARY

Prestressed Concrete. First of three Cantor Lectures by G. W. Kirkland. At the RSA, 6, John Adam Street, W.C.2. 6 p.m.

APRIL 14

How Successful is Counter Attack? Talk by Ian Nairn. TCPA meeting at the Planning Centre, 26, King Street, W.C.2. 6.30 p.m.

APRIL 14

Presentation of RIBA Gold Medal. At the RIBA, 66, Portland Place, W.1. 6 p.m.

APRIL 15

Engineering in the Landscape, talk by G. B. Jackson and Brian Hackett. ILA meeting at the Housing Centre, 13, Suffolk Street, S.W.1. 6.15 p.m.

APRIL 17

LETTERS

Graeme Shankland,
A.R.I.B.A., A.M.T.P.I.

M. A. Booth

C. F. Colt
Director, W. H. Colt & Son Ltd.

Michael Haskoll, Student R.I.B.A.

Jack Whittle,
A.R.I.B.A., A.M.T.P.I.
Deputy Borough Architect, West Ham

SPUR

SIR,—ASTRAGAL, I am glad to see, has been converted. When I suggested, in my paper at the AA in February last year, that a new society was needed to secure the radical reconstruction of Britain's cities, ASTRAGAL'S "jaw dropped" and he contemplated emigration.

Now that this threat has apparently been averted and the new body "SPUR" has been born, may I join ASTRAGAL in appealing to all architects and others whose view of their purpose in life is wider than the confines of their immediate job to help make SPUR an informed and lively forum for urbanists?

GRAEME SHANKLAND.

London.

Now I Understand

SIR,—As a lay woman interested in architecture and a regular reader of your JOURNAL, may I say that I am not surprised at any Town Planning officer refusing to accept the elevation submitted by Messrs. Emmerson and Sherlock. The revised design has hidden an ugly chimney and masked ugly windows. It may not be what architects call architecture, but at least it looks like a house and is more pleasing to the eye.

I now understand why the average person does not consult an architect when he decides to build.

Notts.

M. A. BOOTH.

Colt Bungalow

SIR,—I thank you for the copy of the ARCHITECTS' JOURNAL in which is illustrated our Demonstration Bungalow, and it certainly looks very well in the write up.

A small point, namely, the criticism of the porch. This is not really a part of the design, but we felt a door in the wall would be a little "naked" looking, and we wished to avoid spending money on a porch. The "rusticated porch surround" is in fact made from *offcuts* from stair strings, which are normally burnt. We consider these have come in very handy for a door surround, and make an amusing entrance!

C. F. COLT.

The Canterbury Maisonnets

SIR,—In his criticism of the maisonnets in Military Road, Canterbury, Kent (AJ, March 27, 1958), Mr. Richards described the row of balconies as cluttering up the rear elevation "without serving any apparent purpose."

Before moving, about a year ago, into a flat with a similar type of detail in the living room, I wholeheartedly agreed with Mr.

Richards' criticisms. Now, for the following reasons, I must wholeheartedly recommend the inclusion of this feature.

The glazing down to floor level, in our case, does provide worthwhile lighting—we have 10-ft. of window in a 17-ft. wall. Observation leads me to believe that, in any case, the light reflected from the floor immediately in front of the door is well worth having.

It is possible to sit in an easy chair and see out of the window; a striking advantage we noticed after having lived in a flat where the sky was all that could be seen.

The air currents in a room with this type of detail are found to be far more general. Instead of a layer between the sill and head of the window and the entrance door to the room being cleared all levels in the room benefit from a more frequent rate of air change. Naturally, there is the drawback that these more general air currents can occur in winter as draughts, but that is a question of detailing. In hot weather, when no relief can be expected elsewhere, some breeze can usually be found in front of these doors.

This breeze probably occurs immediately in front of any window, but it is possible to sit in front of the doors and effectively gain benefit from it. Further it is possible to sit in the sun more easily, and completely, than can be managed with a 2-ft. 6-in. to 3-ft. high window sill.

It may be possible to detail these doors in a way more satisfying to Mr. Richards, but I disagree that they serve no purpose—indeed these reasons lead me to believe that they are a desirable feature, and more satisfactory than the usual projecting balcony with its solid floor, and often with solid front.

London.

MICHAEL HASKOLL.

SIR,—The idea shown in your article on the Canterbury maisonnets of combining architectural criticism and cost analysis is a novel one, but there are certain aspects of it which I would wish to criticize, although in doing so I do not wish to appear unappreciative of your enterprise or of the achievement of the City Architect of Canterbury.

My main interest is your comparison between the cost of Canterbury maisonnets and that of maisonnets erected at the Claremont Estate, Forest Gate, by the County Borough of West Ham. Apart from difference between prices applicable in London and those in the Provinces, I am not sure that these comparisons are valid either in detail or in total cost.

First, as to detailed costs, experience in maisonette building in West Ham has tended to show that the effect of crosswall construction on cost is at present limited, and tends to result in a re-distribution of cost within the total building figure. There is little doubt, however, that savings made are on the structure, but the variation which you quote between the 5s. 1d. per sq. ft. at Canterbury and 9s. 9d. per sq. ft. at West Ham, if expressed in percentages of the total building cost per sq. ft. shows less difference: 18.1 per cent at Canterbury and 25.3 per cent at West Ham. If floors are included, which, in my opinion, they should be, as they form an integral part of the structure and framework of the Ministry block, the figures become—Canterbury 7s. 5½d. per sq. ft. (26.6 per cent), West Ham 12s. 11½d. per sq. ft. (33.5 per cent). The difference in price between partitions is not strictly comparable in that West Ham partitions are 2-in. breeze rendered and plastered both sides as opposed to the unplastered egg crate plasterboard used at Canterbury. There is unquestionably a tangible saving in roof construction, although the experience at West Ham would not support the extensive saving quoted in your article.

On total costs the great interest arising

from the article is the opportunity it gives to compare the cost of the Canterbury maisonnets with those of similar design which are being built in West Ham as part of the Ministry of Housing and Local Government experiment. Under the direction of the Borough Architect and Planning Officer, Thomas E. North, two blocks of Ministry maisonnets, comprising 48 dwellings, are being erected as part of a larger contract of 215 dwellings. Figures comparable to your analysis are not available for this Contract, but the basic price per sq. ft. (that is, the price for the dwelling plus certain external works) is for the Ministry maisonnets 41s. 3d. The 28s. per sq. ft. of your cost analysis for the Canterbury dwellings would need to be adjusted to compare with the basic price per sq. ft., but the increase would be a small part of the difference between the 28s. and the 41s. 3d.

In order to obtain comparative costs, this contract also includes two more blocks of maisonnets totalling 48 dwellings designed in the Borough Architect's Department. The design of these is based on the crosswall construction principle, but with brickwork front and back, and pitched slated roofs; the basic price for these maisonnets is 38s. 10½d. per sq. ft. There are variations in floor areas of the dwellings which invalidate a direct comparison between two figures on the same contract at West Ham but they show that a crosswall construction with traditional materials used externally is as cheap as crosswall construction with lightweight panels, and may result in a building requiring less maintenance. It appears that in order to reduce the weight of the superstructure, extra costs over traditional methods are incurred and that until a light, durable cladding material is produced which will withstand impact, fire and require little maintenance, and which, including fixing, will compete in cost with the external materials of brick or rendered blocks, crosswall techniques will not show the savings of which they are capable.

In the architectural criticism Mr. Richards is fully justified in his dislike of the fencing and "brick sheds" illustrated. The difficulty of keeping prices down and at the same time providing attractive stores for the tenants, reasonable fencing and interesting site development is one of the outstanding problems of "low-cost" multi-storey housing development. When the building itself has to be limited in cost with an unavoidable and undoubted effect on the architecture, it seems necessary to spend more money on external works in order that the resultant effect of the scheme as a whole will be acceptable.

There would seem to be one outstanding point which calls for attention in these comparisons and that is the difference in cost between the construction of a similar maisonette at Canterbury and West Ham. The price variation here seems extraordinary and one which is apparently outside the control of the architect. An investigation as to why there should be this difference in price between two localities might well result in much more substantial savings in cost than can be achieved by the architect in redesigning within the now restricted limits of local authority housing.

The Ministry experiment in collaborating with local authorities in the construction of new types has been well worth while, but it is only a beginning. This part of the Ministry's work should be broadened and extended, with ample funds made available from Central Government sources, so that the fear of occasional failure should not hamper vigorous research and experiment which could result in economies and increased speed in housing—an essential need if the slum clearance programme is to succeed.

West Ham.

JACK WHITTLE.

NEWS

PRESERVATIONISM

John Summerson's Views

John Summerson, in a talk on the preservation of Georgian and Victorian architecture at the RICS on March 31, expressed the friendliest feelings towards the newly announced Victorian Group, but added that some recent cases suggested the "new protestants" were apt to run rather wild. "Dreadful nonsense" he said "was written about the St. James's Theatre, one very reputable Sunday paper even illustrating a disgusting piece of Victorian Louis XV pastiche over a caption exclaiming upon its elegance and beauty. With admirers of the Imperial Institute I go a long way—Collcutt's idiomatic handling of renaissance detail in brick and stone is brilliant and unique to its period; but it is curious, as Lord Salisbury unkindly pointed out in the House of Lords, that so few of us recognized it as a masterpiece till it was threatened. And, indeed, in the whole picture of Victorian achievement in architecture, I cannot see that the Imperial Institute stands as high as all that; and although I agree that its preservation was worth serious consideration, I believe the outcome was, in the circumstances, the right one.

"Where there is such a vast field of selection as in the Victorian period, preservation policy must proceed very cautiously and on ground carefully explored and continually subject to the tests of historical scholarship. Up to 1870, the Victorian genius ran mostly into church building and the major works of Pugin, Butterfield, Street and Pearson are not in any grave danger. The Houses of Parliament and the Law Courts are, I take it, likely to be with us for some considerable time. If the Transport Executive takes it into its head to remove the old St. Pancras Hotel there will be a storm indeed but it will be one of those tragi-comical storms where every protagonist knows in his heart that the subject of argument is not really a great work of art. It would be fun to keep the St. Pancras Hotel, and I believe sometimes in preserving for fun; but this might prove to be more expensive fun than we can afford.

"A rather similar case, now under review, is the extraordinary white elephant with which Baroness Burdett-Coutts sought to raise the moral tone of the East End in 1866—the Columbia Market. The pathos of its misdirected idealism belongs to the theatre rather than to real life. The costliness of its carved ornaments (£200,000 in 1866 allowed for quite a lot of carving!), its dreaming Gothic lines, make it, in decay, vocative in a high degree. Yet to preserve it would be quixotic—an encumbrance and a waste. Moreover, as a preserved monument the pathos would vanish and we should become conscious only of the rather indifferent technical powers of its architect.

"Among later Victorian things I can think of some, not necessarily famous, which should be protected with the utmost rigour. We must keep some at least of Richard Norman Shaw's town houses and country houses; he was an artistic innovator whose works will never be mere curiosities, and the name of Shaw leads one to think of the men who inherited the freedoms he claimed for architecture—C. F. A. Voysey, C. R. Mackintosh and Sir Edwin Lutyens among them; so that preservation problems begin to creep up into our own day.

"Are we trying to preserve too much? I do not think so. As public opinion stands

today, I believe we are only just keeping abreast of what it feels ought to be done, and not a jot more; for in this matter public opinion is very exacting and very suspicious of laxity. Today more people are more conscious than ever before of architecture as history and architecture as art. Such waves of curiosity and expanding interest are not easily explained but I sometimes wonder if this one has something to do with our lack of success in producing a contemporary architecture which is warmly and instinctively loved. I wonder if the present enthusiasm for historic architecture foreshadows a parting of the ways in the history of the art—if it may not be that architecture as the word has been understood since the renaissance is now virtually a closed book and if the architecture of the future will be a kind of industrial designing—fine and elegant, exquisitely convenient, but impermanent, impersonal, classless and of low emotional content. If that proves to be the case, then the retention of the ancient, from Stonehenge to the Albert Memorial, from hut settlements to model villages, may take on an even more striking significance than it does today."

VICTORIAN SOCIETY

Affiliated to SPAB

The Victorian Society was formally launched as an organization affiliated to the Society for the Protection of Ancient Buildings at a meeting held last month. It was agreed to invite Lord Esher to be Chairman, and the members of the Committee include Sir Hugh Casson, Mrs. Christiansen, Dr. N. Pevsner, W. Gaunt, Christopher Hussey and Mr. Goodhart-Rendel. The object of the society is "the study and appreciation of Victorian Architecture and Decorative Arts with a view to preserving outstanding examples." The minimum subscription is £1 1s., and life membership £15 15s.

V & A

Finnish Rugs On Show

The V. and A. Museum is to be congratulated on its exhibition of Finnish handwoven rugs, which is on display until May 4. The exhibition, beautifully and simply arranged by architect Mrs. Johanson-Pape, is in two parts—an introductory room, showing some of the 18th- and 19th-century rugs on which the work of modern designers is based, and the main gallery, containing about 40 superb examples of the present day Finnish renaissance. Although they are called rugs, these textiles are not intended for use as floor coverings; originally designed as bedcovers or wall hangings, they have now developed into works of art to be hung as are paintings.

The rugs are all *ryijy* or long pile rugs, with individually knotted tufts—a laborious technique but one which imposes no limitations on pattern or colour—and are the combined work of designers and weavers—the designers, who have weaving experience, produce sketches for weavers, with whose work they are familiar. Many of the designs are inspired by the cold light and muted colours of the Finnish scene, or in contrast, by the Finns' warm hearted reaction to their environment. Compare, for instance, Eila Annikki Vesimaa's Winter Feeling and Midsummer Bonfire and Kirsti Ilvessalo's Milky and Woodpecker. With their characteristic richness of texture and subtlety of colour, these rugs enhance considerably the simple Finnish interiors for which they are designed. Their use might well be extended to this

country, as copies of these rugs can be imported from Finland or alternatively weavers here can be commissioned to produce special designs.

RIBA

Earnings Survey

As part of their approach to the problem of establishing equitable rewards for doctors, the Royal Commission on Doctors' and Dentists' Remuneration are conducting a comparative income survey involving twelve professions. They have asked for the RIBA's co-operation in this and as it was the Ad Hoc Committee's intention anyway to undertake an inquiry into architects' incomes, the Council have readily consented. A questionnaire drawn up in collaboration with the Royal Commission has accordingly been sent out from the RIBA to a 20 per cent. sample of the corporate membership in the United Kingdom—some 3,000 architects chosen at random. With this were covering letters from both Richard Sheppard, Chairman of the Ad Hoc Committee, and Sir Harry Pilkington, Chairman of the Royal Commission. Mr. Sheppard acknowledges in his letter "the undeniable nuisance of filling in a pretty voluminous paper" but points out that this is a unique opportunity to get reliable comparative figures gathered on a common basis. "For the first time we shall have something more than hearsay to guide us in assessing how much better or worse we fare than other professions."

Members concerned are urged to return the completed forms not later than April 15. Elaborate precautions have been taken to ensure that completed forms remain strictly anonymous, and they will all be destroyed as soon as the information on them has been transferred to punched cards.

SCHOLARSHIPS

Travel Grants

The English-Speaking Union announces the offer of four Travel Grants to the United States, application for which is open to men and women of British nationality, aged between thirty and fifty, who are experienced and practising in a branch of the arts such as painting, sculpture, music, architecture or design. Each Grant will cover the cost of travel to and from the United States and travel within that country. There will also be a subsistence allowance for each day spent in the United States, up to a maximum of 70 days, the recommended length of the visit. The Grant may be taken up any time after mid-September, 1958, but must be completed by June 30, 1959. The closing date for applications is Saturday, June 7, 1958.

Further particulars and application forms are obtainable from: The Secretary, The English-Speaking Union, 37, Charles Street, Berkeley Square, London, W.1.

BASA

Students' Conference

A conference of the British Architectural Students' Association will be held at Brentwood School, Essex, from April 24 to 26, at which the report of the preliminary conference held in September, 1957, will be discussed. Any communications should go to the Secretary of the BASA, Liverpool School of Architecture, Liverpool, 7.

Rolf Rosner, an architect with British experience now working in Western Germany, attributes the success of the West German post-war housing effort to a number of factors, including modular co-ordination, the development of highly efficient traditional methods (such as the use of load-bearing brickwork for multi-storey blocks of 8-storeys or more), mechanization of small sites, and hard work both by operatives and management. He also describes the organization and finance of house-building, and refers to the failure of the Germans influenced by free enterprise philosophy, in the field of town planning.

HOUSING IN WESTERN GERMANY

What are the outstanding aspects of the West German Housing effort which has resulted in the construction of more than 4 million dwellings in nine years? After having worked for more than two years in Hamburg I shall attempt to deal with some points of interest to British architects, planners and everyone interested in housing. In 1939, 39.3 million inhabitants lived in the territory which is now the German Federal Republic. In 1951 this figure had increased to more than 50 millions through the influx of refugees from

the East and this influx continues. About 2½ million dwellings or more than one-fifth of the total number of dwellings existing before the war, were destroyed or severely damaged and most of these have been reconstructed by now, though to a large extent smaller in size than previously. 600,000 households are still

The Bogahausen estate in Munich. All dwellings are heated from a central boiler house.



housed in camps or emergency dwellings. Many of them are living in unbelievable squalor, even large families having just one room to themselves.

There are other factors which influence current housing problems: The annual setting-up of 300,000 new households and indications that the annual housing output is now likely to taper off from its peak figure of 570,000 dwellings in 1956. Furthermore, the passing of the second Housing Act last year favours the purchase rather than the renting of dwellings and so makes it practically impossible for many a poor if deserving householder to obtain an adequate form of accommodation. Lastly, quite a few re-housed families, no longer figuring on waiting lists, live in new dwellings, which must be regarded as overcrowded. From personal experience I know of a seven-person family living in a four-room flat, a five-person family living in a three-room flat; many terrace houses are Duplex types housing two families. This is not at all a rare occurrence, even if it is mostly unknown to the foreign visitor to new housing estates. Therefore the official claim that with the building of another two million-odd dwellings the West German housing deficit will be cleared by about 1961 must be regarded with some caution. It seems more likely that without any drastic change in the current situation another 10 years will be required to house all the people adequately.

Nevertheless, 4,000,000 dwellings built in 9 years is a remarkable achievement and one must ask what methods of rationalization have been used to make possible the recovery of a defeated country?

First of all there is the German system of modular co-ordination adopted by the Federal Government after the war and based on the work of Professor Neufert during the previous decade.

When the country returned to normal in 1949 the reconstruction of partially destroyed buildings required the use of traditional materials such as bricks and concrete blocks. A further factor determined the German attitude towards rationalization: the structure of the building industry had little changed since before the war; the average contractor employed no more than 10 to 20 operatives and the average housing site consisted of less than a dozen dwellings. Large building sites where advanced techniques, for instance prefabrication, could be applied economically were, and are, relatively rare. In the past the Germans have readily experimented with such techniques but the slump of 1930 and the subsequent neglect of domestic and school building as a result of rearmament prevented a fair trial of new methods.

Therefore, when considering past experience and the state of the country after the war, those responsible for introducing some measure of rationalization into the building industry decided to increase the efficiency of traditional methods: they were far-sighted in adopting the metre as the basis of measurements. However, they seem to have been unaware of any advantages obtaining from the adoption of the 10-cm. module; rather did they base the division of 1 metre on an existing grid of 12.5 cm. which permitted the placing of four handy stretchers within exactly 1 metre: the

25 cm. by 12.5 cm. brick, inclusive, that is, of one thickness of mortar, was adopted as the standard unit for Western and Eastern Germany, superseding a variety of bricks of different dimensions. As a further measure the production and use of wall blocks was boosted to an extent hitherto unknown. A few figures will illustrate this point:

Production of Wall Units in Western Germany (in percentages)

Total production		Common bricks	Concrete blocks	Sand-lime bricks
1949	100	67	18.5	14.5
1953	100	46	38.5	14.0

Experience has shown that through the use of wall blocks the pace of building can be appreciably increased and an excellent degree of thermal insulation achieved; also rendering is less problematical than in Britain because the climate of Germany is mostly continental. All wall-blocks are dimensioned to align with the standard brick. Building materials manufacturers have adapted their plant to these dimensions and most technicians and operatives now take them for granted. Preferred dimensions for windows, doors and pre-cast lintols were worked out as well but their practical use is confined to the Land of Schleswig-Holstein where a progressive group of official architects is at work. Nominally the modular system is compulsory in all federal Lands, but in fact, exceptions to the rule are only too evident when architects, and people on the site, ignore the modular rules.

It would be unwise, indeed, to read too much into German modular co-ordination in order to introduce a similar system in Britain. There are members of the Modular Society who have been impressed by one of the German Standard Specifications, which lays down a preferred series of dimensions for the interiors of dwellings based on 10 cm. This has remained unused; 12.5 cm. and 25 cm. are the governing dimensions.

Secondly, the development of highly efficient traditional methods of construction has led to the use of load-bearing brickwork, up to a height of eight storeys or even beyond. This is cheaper than any other established or experimental form of construction for multi-storey dwellings.

Thirdly, there is the mechanization of small building sites with the aid of tower cranes, auto-cranes for two-storey buildings, belt conveyors and various simple but ingenious implements such as special carts and shovels for moving concrete and mortar, and roller conveyors for moving bricks and larger blocks.

The use of machines increases every year as the following figures will show:

Type	1952	1956
Tower cranes	1,259	5,518
Belt conveyors	8,135	15,892
Hoists	28,363	42,238

These implements cost little yet improve output appreciably. They have received inadequate attention by British contractors. Fourthly, the use of the "Taktverfahren," i.e. the phasing of site operations, which means that one gang of operatives carries out the same type of work throughout a project. This, of course, requires a restricted number of type plans and



Terrace houses at the St. Lorenz-Sud estate in Luebeck. The houses are staggered to give more privacy to tenants. Most contemporary terrace houses in Germany are only provided with a small paved terrace which may be surrounded by shrubs and flowers as the tenant desires. The remaining open space between rows of houses is either looked after by the owners or by the local authority. Chain link fencing and concrete posts are unknown.



Terrace housing in a Hamburg suburb.



The outer suburban estate of Farmsen, Hamburg, with 2,000 dwellings grouped in terrace houses, and 3- and 6-storey blocks of flats. The estate was built in little more than two years.

there is the danger of monotony. In fact, a typical German housing project is likely to have less variation than a British one.

Fifthly, the proverbial readiness of the German operatives to work hard. This is based on the natural desire to see their devastated cities reconstructed and is no particular national characteristic. British workers would react likewise under similar conditions. Further incentives are widespread: bonus work and, in a negative sense, regular periods of mass unemployment, particularly during the winter. There also is the influx of workers from the East, who toughened by traditionally more primitive conditions are ready to work exceptionally hard in order to build up a new existence. They naturally tend to put a brake on improvements in general labour conditions. When a long day's work is done, and also during weekends, such people will build their own houses with the aid of relations and friends. But there is a price to be paid for all this hard work: the intense pace and physical strain, such as results from working with two-hand wall blocks (the use of which is now declining), has permanently injured the health of many a worker.

Sixthly, in this feverish rush to get the country rebuilt the top managerial people have set a good example. I know of managing directors of leading housing companies, who often start work at 8 o'clock in the morning and do not stop for 12 hours or hold conferences during weekends if there should be the need. But they, too, eventually pay the price; every week half-page obituaries headed "suddenly and unexpectedly" tell of the passing away of such men in their forties and fifties. German housing has also been furthered by the efforts of the building research institutes in Hanover and Stuttgart. These institutes undertake work studies and test site organization and the use of various materials in all parts of the country. They are not equipped like the Garston BRS; various laboratory tests are carried out by selected technical colleges or universities. The two institutes utilize the experience gained for the persistent propagation of a series of relatively simple facts: the use of the modular system, the advantages of building with blocks larger than standard bricks, careful preplanning of site operations, the use of simple auxiliary implements, the most economic depths of dwellings and many similar points likely to make traditional methods more efficient. This constant propagation of a limited set of measures likely to cheapen and speed traditional building has had a more profound effect on the average German builder than (it seems) the more diversified and discreet work of our BRS on the average British builder. This brings me to an additional point: the leading men in, and close to, the two German research institutes are of considerable professional attainment. In spite of the current adulation of commercial success, most people in Germany respect this kind of distinction and are ready to benefit from it. Can one say that a similar attitude prevails in the British building industry?

Finally it cannot be overlooked that until now Western Germany remained free of any defence commitments which in the case of Britain have cost £1,500-£1,600 million annually. More money was therefore available



A point block in Kassel.




The Wedel estate by the river Elbe. This project consists largely of terrace houses for the employees of a large industrial concern.

for housing and inflationary tendencies resulting from armament expenditure have been non-existent in the federal republic.

After the collapse of the Hitler-regime which had neglected the development of housing on contemporary lines the Germans had to draw on their valuable experience during the nineteen-twenties and also on experience gained by their neighbours, the Swiss and the Scandinavians. One cannot help being impressed by the fact that many German architects are somewhat more concerned with the well-being of the people to be rehoused than with formalisms of architectural expression and structural experiments, however important. Man is truly at the centre of things. Considering what a limited amount of sun is available in our part of the world it is inconceivable to Germans, and many other continentals, that gardens should be made to face east or even north so that an agreeable street architecture may be achieved through this kind of layout. By experience I have found that with blocks facing south-south-west and west it is possible to work out layouts which would be acceptable both in Britain and on the continent. But even schemes which, on paper, may appear monotonous with most blocks facing south-west, can look lively in reality if contours

The Hohneskamp estate in the outer suburbs of Hamburg. There are 1,600 dwellings grouped in terrace houses and 3- and 6-storey blocks of flats. The estate was built in two years, mainly because the number of type plans remained strictly limited. Superb landscaping has overcome the dangers of monotony.







The type plans in this column are all for three-room staircase access flats in Hamburg. The one above has a through living room of 281 sq. ft. and convection heating. Scale 1/100



This flat has an internal bathroom, facilitating a relatively narrow frontage. Heating is by warm air from the living room.



Another design with internal bathroom, a frontage of 23-ft. and a depth of 36-ft. All three rooms are heated from the centrally situated slow combustion stove.



The heating of this flat is by warm air passing through ducts from a large slow combustion stove in the living room.

have been fully utilized and if the site has had the benefit of landscaping at which the Germans excel; we are often carried away by geometric shapes on paper, when our imagination, and reality at eye level, ought to guide us. Point blocks and tall slab blocks are very rarely designed for families, and are regarded as unsuitable for children. I have heard the Alton Road point-blocks criticized both for that reason and because one flat per floor is facing east.

Balconies of adjoining flats are, as far as possible, kept apart so that privacy is safeguarded. Living rooms in flats tend to be larger than in Britain, and parents' bedrooms which are accepted by the LCC would be unthinkable. By-laws govern the provision of storage space per flat either in the loft or basement ranging from 90 to 140 sq. ft. according to the size of dwelling. Often space for the drying of washing is also provided. Access balcony flats are rare because they are unpopular and are regarded as slightly more expensive to build than staircase access flats. The four-storey staircase access block is regarded as the cheapest type of multi-storey block not only in Germany but in Scandinavia and the Soviet Union as well.

The most economic depth of a block of staircase-access flats lies between 33 and 36 ft. There is no lift of course. In some parts of the country it is provided from the 5th storey, in other parts from the 6th storey, upwards.

German architects have distinct ideas about the planning of kitchens. The arrangement of a kitchen, based on work studies carried out by the Research Institute in Hanover, is as follows: cooker, working top, sink, draining board top and/or dresser. For up-to-date cooking the Germans favour electricity and the provision in new estates of gas and electricity services competing with each other is unknown. Trouble is also taken to improve upon the most common form of heating; the small combustion stove in each habitable room. These stoves are not as well designed as British prototypes and it is hard work for the housewife to clean out several of them at frequent intervals. A considerable improvement is a system of warm-air heating fed by a large, slow combustion stove, which may be serviced from the entrance hall of a two-storey house or a flat. The heating of a flat by means of radiators and a boiler in the kitchen and central heating from the basement of a block of flats is more common than in Britain but not as much a routine matter as in Denmark. This is simply a matter of expense. In very large schemes like the new 10,000 dwelling development in Bremen, district heating will be provided and a similar system is being considered for the reconstruction area of Hamburg-Altona. In fact, here the planners are not only insisting on a smokeless but also a soot-less method of heating for the central boiler-house. This means no coal or coke, because storage and fuelling would cause a lot of dust. Oil or gas are acceptable.

Now a brief description of the organization and finance of housing. Subsidized housing is delegated by the authorities to agencies, be they municipal companies, co-operative housing associations or housing companies generally. Anyone can start the


Henderson

SLIDING DOOR GEAR



STRAIGHT SLIDING DOOR GEAR

Request General Catalogue 55



'MARATHON' INTERIOR DOOR GEAR

Request Leaflet M




'LORETTO' CABINET ROLLERS

Request Leaflet L




'MANSION' and 'MAJESTIC' BOTTOM ROLLERS

Request List INT




'TANGENT' GARAGE DOOR GEAR

Request Leaflet T




FOLDING PARTITION GEAR

Request List INT



'ULTRA' OVERHEAD DOOR GEAR

Request List OD and Leaflet AD



LIGHT OVERHEAD RUNWAYS

Request List OR

for any door, partition or window that slides or folds

P. C. HENDERSON LIMITED · TANGENT WORKS · HAROLD HILL · ROMFORD · ESSEX

Telephone Ingrebourne 4444

London calls dial IL4 4444

latter, but he is bound by many rules, the most important requiring limitation of profits. The most important of these companies is "Neue Heimat" in Hamburg, heading 25 subsidiary companies in various parts of Germany. This group is backed by the German Trade Union Congress with capital amounting to £10 million. It owns about 100,000 dwellings and many other types of buildings, kindergartens, laundries, offices, etc.

The landscape gardening of its own estates is also the responsibility of "Neue Heimat" and it is magnificently done. On its Hohnerkamp estate with 1,600 dwellings, 18 gardeners are regularly employed. Other activities of this organization include the monthly publication of an illustrated town planning and housing journal for architects, and a magazine of a more varied kind for the tenants. A well-equipped home is available for the tenants' children who can stay there for up to four weeks at a time. The organization also produces as a supplement to its annual report, a colour film showing the most recent estates.

Working like private business organizations, the German housing companies often are a driving force more powerful than our local authorities. At the head are financiers whose main aim is to obtain funds from all available sources and to invest them as quickly as possible in order to get the substance and rental income necessary to cover loans and credits. Speed and quantity so much govern all activities that quality suffers in some respects. The delegation of power by the State to approved housing organizations also accentuates this uneasy balancing between quality and quantity because all layouts, type-plans and elevations must be approved by the local authority and all the necessary by-laws must be adhered to. In many large towns building land has become scarce, be it through extensive reconstruction or speculation. Under the circumstances some housing companies attempt to persuade the local authorities to free proposed open spaces for use as housing sites. They may also choose to build at the fringe of the suburbs even if transport to the city centre and the chances of local employment are inadequate.

People are entitled to a wholly subsidized dwelling if they have the necessary points on the housing list of their municipality and if the weekly income of the head of a family does not exceed £13 15s. A sum of £1 10s. is allowed for any further member of a family. Fifty to 60 per cent. of the cost of such dwellings is provided by the State at an interest rate of 1½ per cent., 30 per cent. of the money as mortgages, by banks, insurance and finance companies at 7½ per cent. interest and the remaining 10-20 per cent. of the capital through the profits of the housing companies, employers' loans or contributions. In fact, employers' loans, which qualify for tax remission, have been used fairly often, particularly when industrialists have built estates for their own employees but this immediately brings up the vexed problem of the "tied cottage."

The average rent amounts to about 20s.-27s. a week, but this relates to dwellings with an area of 520 to 600 sq. ft.

However, under the provisions of the recent Housing Act steep increases in the rents of newly completed

dwellings must be expected, increases of 25-35 per cent. above previous rental levels.


Rents which are calculated on the basis of so many marks and pfennig per habitable sq. metre have been grouped into three different levels in the case of fully subsidized housing. The levels vary according to the equipment and finishes of the dwelling.

Two- and three-room flats have been the predominant types of dwellings in Western Germany so far. But they have gradually increased in size. In Hamburg the average dwelling during the period 1948-52 had an area of 535-570 sq. ft.; now the average area is 610 sq. ft. To give the relative value of the average rent of 20s. to 27s. a week, the average earnings of a German worker are between £8 and £9 a week before deductions.

For higher income groups the housing companies require contributions from tenants amounting to as much as £600-£1,000 for well-equipped four-room dwellings, but these are paid back free of interest over a period of 10 years. When dwellings are offered by private estate agents prospective tenants may be required to pay similar amounts without seeing a penny back. This is quite legal; there is still a grave housing shortage and everything is governed by the law of supply and demand.

There are special provisions for refugees from the East and the bombed-out. Special grants enable them to bridge the last 10-20 per cent. of the capital required. The miners also have a special housing programme and much American money has gone into it. Since the passing of the Second Housing Act last year nearly half of the State money available for subsidies has been set aside for the purchase of dwellings, be they houses or flats. A typical suburban terrace house with basement and central heating may now cost about £3,000 in Hamburg. One-third of this money the State will give at 1½ per cent., one-third will be taken as a mortgage at 7½ per cent. and a third the purchaser will have to provide himself. Here he may be helped further if he is a refugee or bombed-out or again his employer may give a loan.

In one field, German housing has not been allowed to develop as fully as it might have been and that is in the field of town planning. The country's economics and politics are dominated by a philosophy of private and free enterprise and if this has been successful in re-starting a broken country, it has prevented the working out of proper development plans. Compulsory purchase is a lengthy and cumbersome business and therefore rarely used. Stubborn property owners can hold the developer of a new estate to ransom, and ugly, arbitrary gaps splitting new blocks into two, show where someone is holding out to the bitter end. Speculation in the inner urban areas is rife and forces developers towards the countryside. The consequences are known in all major towns of Britain. In some instances the owners of adjoining plots have been persuaded to get together and to permit the unhampered re-development of their combined properties with the provision that they will be entitled to the accruing benefits according to the share of their interests. But this is mostly a slow business and cannot be regarded as a general solution.



ENGINEERING & ALLIED EMPLOYERS' ASSOCIATION, BIRMINGHAM

John H. D. Madin, Dip. Arch. (Birm.), A.R.I.B.A.

HOPE'S

HOT-DIP GALVANIZED WINDOWS

HENRY HOPE & SONS LTD



Smethwick, Birmingham & 17 Berners Street, London, W.1

Local Office: 319 Broad Street, Birmingham

MEMBER OF THE METAL



WINDOW ASSOCIATION



Site plan



Out of the wholesale ruins of war the City of Berlin created a site for its new international congress building which could be called "ideal" if it were forgotten how these eleven acres of level land at the geographical, political and historical heart of the city, came to be available for new building on such a scale. The site is bounded by the Tiergarten, the River Spree and the Platz der Republik, and the building has been organized by the architects, Hugh Stubbins and Associates, into two distinct elements: the congress hall itself, and a low base block containing all the ancillary accommodation and roofed with a paved plaza. The lower floor of the base block is at the former natural level of the site, and the ground has been given a slope upwards from this level on the east and west sides (see top photograph, from the west), subordinating the base block to the more important congress hall. The crown of the rise occurs opposite the support points of the hall roof so that the twin arches of the roof continue the upward sweep of the site. On the south side of the building, shown in the frontispiece on page 522, the main entrance is approached by a looped driveway, while a separate paved pedestrian way leads across a pool with fountains (left) and gives access direct to the plaza at the higher level by means of steps. On the north side the lower floor of the building gives directly on to a boat landing stage on the River Spree. Parking is provided on the east side, where stairs and ramps give access to all levels of the building. On the ground floor, offices for conference personnel open off the large central lobby. A two-level lounge and snack bar on the east side is furnished for informal meetings,

IN THE MARLEY TRADITION...

THE NEW MARLEYFLEX DE LUXE

This new Marley Floor Tile has been formulated to give maximum flexibility, clear lustrous colour and an impeccable smoothness of surface. A higher vinyl content gives a softer tread, greater comfort — and silence. Yet it is tough, giving not only long life but life-long richness and good looks. Where there is a risk of contamination from grease, Marleyflex de Luxe is strongly recommended

MARLEY

Visit our London Showrooms at 251 Tottenham Court Road, W.1.
The Marley Tile Company Limited, Sevenoaks, Kent. Sevenoaks 55255




CONGRESS HALL IN BERLIN: continued




with adjacent small conference rooms. On the west side there is a large exhibition hall, opening into a garden, and a small theatre. There are also committee rooms for groups of twenty-five to a hundred people, some of which open into a walled garden. Stairs from the ground floor rise to the upper lobby—a mezzanine balcony overlooking the main lobby—which gives access to the plaza and the

- KEY:**
- Ground Floor
 - 1. Entrance
 - 2. Great Hall
 - 3. Congress administrative facilities
 - 4. Exhibition hall
 - 5. Theatre
 - 6. Telephone and wire facilities
 - 7. Bar and lounge
 - 8. Conference rooms
 - 9. Restaurant
 - 10. Kitchen
 - 11. Boiler room
 - 12. Receiving room
 - 13. Services
 - 14. Caretaker's apartment
 - Auditorium
 - 1. Main auditorium
 - 2. Stairs and platform
 - 3. Resting rooms
 - 4. Elevator
 - 5. Main entrance
 - 6. Projection booths
 - 7. Translators' TV and radio booths



Ground floor plan



Auditorium plan



ARCHITECTS: FITZROY ROBINSON & PARTNERS CONTRACTORS: HOLLAND & HANNEN and CUBITTS LIMITED

Erection of the new office building on the site of the former Holborn Restaurant

expedited by off-site fabrication and on-site assembly

By using BISON PLANK composite floor in this building, major economies were effected through the minimum use of on-site shuttering, reduced floor installing time and reduced floor depth. The savings from thinner floors alone included 520 sq. ft. of Portland Stone and some 1,570 sq. ft. of brick cladding.

The electric service conduits and other services are laid within the structural topping and this work is synchronised with floor fixing as a whole, effecting still further savings.

The BISON PLANK composite floor is a major contribution to reduced building time and costs.



SPEED & STRENGTH

BISON floors, beams and concrete frame structures

CONCRETE LIMITED are the largest structural precast concrete manufacturers in the world

CONCRETE LIMITED Green Lane, Hounslow, Middlesex Hounslow 2323 and Dovehouse Fields, Lichfield, Staffs. Lichfield 3555

London Sales Office: 16 Northumberland Avenue, W.C.2 Whitehall 5504

CONCRETE (NORTHERN) LIMITED Stourton, Leeds 10 Leeds 75421 Manchester Office: 40 King Street West, Manchester 3 Blackfriars 5676

CONCRETE (SCOTLAND) LIMITED Elmbank Street, Glasgow C.2 City 3292



ON.95B

CONGRESS HALL IN BERLIN: continued

main congress hall. The clerestory windows beneath the provision for the press, photographers, and radio and with an extra compression ring surrounding the auditorium. Of this roof the architect has said, "It is a roof of great promise, and puts no limitations on the achievements that may be made beneath it."


- Mezzanine
1. Foyer and wardrobe
 2. Restaurant
 3. Entrance ramps
 4. Serving pantry
 5. Permanent administration
 6. Conference rooms
 7. Reception
 8. Booths

- Plaza
1. Upper part of Great Hall
 2. Foyer
 3. Press
 4. Cafe bar
 5. Stairways



Mezzanine


Plaza



New
High School
for girls
at Oxford . . .

**COSTAIN
BUILT
ahead of
schedule**

Architects:
RAMSEY, MURRAY, WHITE AND WARD
Quantity Surveyors:
J. J. TAYLOR AND SON
Consulting Engineers:
WALTER C. ANDREWS AND PARTNERS



The Oxford High School accommodating 430 pupils, is a splendid example of modern school architecture. It was constructed on a site which presented those particularly difficult initial conditions under which Costain methods always show to their greatest advantage. Once again the forward planning and organisational efficiency of Costains has resulted in completion ahead of schedule. For your next project . . . make Richard COSTAIN Limited a part of your planning.

Building & Civil Engineering Contractors

Richard
COSTAIN
Limited

LONDON · MIDDLE EAST · RHODESIA · NIGERIA · CANADA · WEST INDIES

THE INDUSTRY

This week Brian Grant describes a new use for venetian blinds, a range of reversible windows, a method of fixing plasterboard and data sheets on laminated sheeting.

Blinds for skylights

The illustration on the right shows Venetian blinds used for a factory skylight. Apart from light control during the day they have the further advantage that they can be closed at night, when they will reflect a very large proportion of the artificial light which would normally be lost through the skylight, while they also provide a certain amount of heat insulation during the winter. Operation is by remote cord control and offers no particular installation difficulties. (Horsley, Smith & Co. (Hayes) Ltd., Dawley Road, Hayes, Middlesex.)

Reversible windows

Not long ago Hopes held quite an interesting small exhibition, at their Berners Street showrooms, of standard centre-hung reversible windows. It seems that architects have been asking for windows on a larger than domestic scale for tall blocks of flats and offices, where it is desirable for painting and cleaning to be possible from inside the building. The windows are horizontally pivoted casements hung on specially designed watertight friction pivots which hold the windows firm in any position, while for ventilation and safety a side arm restricts the opening to a few inches so that children cannot fall out. For cleaning, the side arm can be released and the casement will then turn through 180 degrees, allowing both sides of the glass to be cleaned from within the building. When reversed, the casement is held fast by an automatic catch. These windows are produced in widths of 3 ft. 3½ in. and 4 ft. 0½ in., and in heights varying from 3 to 4 ft.: they can also be coupled, either together or with other types, to form larger composite windows. (Henry Hope & Sons Ltd., Smethwick, Birmingham.)



Venetian blinds by Horsley, Smith & Co. used on factory skylights.


Plasterboard fixing

One of the things which one couldn't see at the Ideal Home was the method used to provide a wall finish in a number of the houses. In four out of the six the Artex Backbond system was chosen, largely, one imagines, because of the amount of time which it saves, but there should also be considerable advantages in houses built to a less tight time schedule, as the U value of the walls is improved to about 0.17, and also because the drying-out period necessary with normal plastering methods is to all intents and purposes eliminated. The Backbond system is a method of applying standard plasterboards to brick or block walls. Strips of plasterboard are fixed horizontally to the top and bottom of the wall in plumb with one another, and vertical strips are applied between them at 18-in. centres. The strips are fixed with dabs of Backbond adhesive, which has a setting time long enough to allow the strips to be properly plumbed, and the strips thus perform the same function as the floating coat in traditional solid plasterwork, that of straightening the wall, but at the same time it provides an air space to improve the thermal insulation. When the

dabs of adhesive have set hard the face of the strips are given a coat of the adhesive, and plasterboards, cut to wall height, are pressed into position and nailed to hold them tight against the strips while the adhesive is setting. Before papering, the nail head and the joints between boards are filled and rubbed down and then coated with a sealer before the paper is applied in the ordinary way. (Artax Products (Decorations) Ltd., Rustington, Sussex.)

Laminated sheeting


A series of quite well prepared data sheets provide information about the uses and working of Pagwood, a laminated product made from veneers of beech bonded with a thermo-setting melamine plastic. The material is available in sheets up to 5 ft. by 2 ft. 6 in. and also in channel, beading and angle form, and is intended for decorative panelling and furniture of all kinds, and has the advantage of being proof against acids and alkalis, as well as cigarette burns. Moulded shapes for such things as chair seats are also available. (C. M. Sanderson (London) Ltd., 9, Southampton Place, London, W.C.1.)



VECTAIR-FLOORLINE

HEATING

A convection heater which replaces the usual wooden skirting board. That is "Vectair—Floorline" heating. A heating element concealed within the attractive casing ensures a steady flow of warm air, which is distributed evenly throughout the room. A finger-tip controlled damper which provides flexibility of distribution is an added feature. With only three basic units, installation is simple, quick—and cheap. Suitable for use with accelerated two-pipe or series flow hot-water and low steam systems.



Write for full particulars

F. H. BIDDLE LIMITED

16, UPPER GROSVENOR STREET, LONDON, W.1.

Telephone : HYDe Park 0532 (9 lines). Cables : Efbiddle-Audley-London.

technical section

1 SOCIOLOGY

social enquiry on Scottish housing estate

Records of what use people make of the buildings architects provide for them are all too few. We have great satisfaction, therefore, in publishing this week a report prepared by John Madge and Vere Hole* of a study made by BRS of the reactions of Scottish tenants who had been moved from 19th century tenement dwellings to a variety of types of houses and flats on a new estate. Among the more interesting findings were that people *must* be able to eat in the kitchen, that the storage of the bicycle is more of a problem than that of the pram (since the pram is regarded as a movable cot which will not be out of place in a bedroom), that there is a real need to provide somewhere to put dirty working clothes out of sight, and that 10 sq. ft. per person seems a workable basis for providing storage space.

Following the introduction of space-saving designs for local authority housing, the Building Research Station carried out a field study in Lanarkshire with the object of discovering how acceptable various economies were to the tenants themselves. The facts disclosed in the study were used in the recent revision of the Scottish Housing Handbook, but certain of the more detailed findings may well be of interest to architects as well as to housing authorities. While the detailed results of a small-scale inquiry, carried out in one area, do not necessarily apply elsewhere, such work can suggest the kind of innovation or economy which will be accepted easily, and that which is likely to meet with resistance on the part of the tenants. To some readers some of the results disclosed in surveys of this kind may seem self evident, but the fact remains that some houses, for the design of which architects have been responsible, continue to be built which ignore them. The design of the study was such that the experiences of tenants in a space-saving house were to be compared with those of tenants in more orthodox types of housing. The space-saving house chosen (Fig. 1) was one which had been designed by the Department of Health for Scotland and was then being erected in substantial numbers; this house was of timber and

illustrated in a practical form the economies then being advocated. The study itself was carried out on a new housing estate in one of the industrial burghs of Lanarkshire, where a number of such houses, together with other types suitable for comparison, were located. According to the declared policy of the burgh, tenants were distributed amongst the various house types on the basis of family size, and were charged the same rent, whatever the house type of given family capacity they occupied. With such a design, any differences in satisfaction between occupants of the various house types could be attributed to the houses themselves, and not to initial differences between types of tenants, or different localities.


The study was based on 88 families who were interviewed by two trained sociologists on four or five occasions during the course of a year after these dwellings were first occupied. Each visit provided an opportunity to see how the dwelling was being used and to discuss a great variety of relevant topics with the housewife.

THE NEW HOUSES

Most of the tenants moving into these new houses came from nineteenth-century tenements from which they were being transferred either because they were overcrowded or because the building was condemned.

Fig. 1, ground and first floor plans of the three-bedroomed space saving house. (Note these plans are diagrammatic only. The actual construction of these houses was timber; the external walls were therefore thinner than shown).

[Scale: $\frac{1}{4}$ " = 1' 0"]



* A Case Study of Tenant Experiences in Some New Scottish Houses. By V. Hole, M.A., and J. Madge, M.A., A.R.I.B.A. Crown Copyright reserved.




and a

BILSTON

ATLANTA

... what more could we ask!



When buyers are considering a new home, the bathroom can often be the deciding factor! A Bilston Atlanta appeals instantly because of its distinctive line and brilliant finish. Made for lasting beauty, Bilston baths are in White, or the exact colour required for any decorative scheme. Specify the Atlanta—it costs no more than an ordinary bath.

*Bilston Baths
for lasting beauty*

Atlanta •
Magna •
Cresta •
Marina •
Mermaid •
Bermuda •

THE VERSATILE ATLANTA

The Atlanta can be specified for any bathroom, large or small! As well as the 66", the Atlanta comes in 54", 60", 61" (available in two widths), and 72" lengths.

The Atlanta 54, 60 and 61 must be preferred to any other baths of these sizes because they are exact replicas of the full size bath, scaled down to small proportions.


Atlanta flat bottom helps to prevent slipping—ensures comfort.

Atlanta shallow step is safe for young and old. The Atlanta can be fitted to give an overall height of only 16".

Taps can be fitted in three different positions to meet all possible requirements.

Corner tap mounting facilitates installation and maintenance.

The Atlanta is supplied with or without overflow—with or without handgrip.



BILSTON FOUNDRIES LTD • BILSTON • STAFFORDSHIRE • Illustrated literature is available on request.




Fig. 2, plan of typical tenements from which the tenants had come. Note the shared w.c. accommodation on the stairs and the built-in beds in the kitchen.

[Scale: $\frac{1}{8}" = 1' 0"$]

About one-fifth of the families had been living in more modern houses, but most of these were occupied under sub-tenancies, so that cooking and sanitary arrangements were shared with another family. The tenements were usually built in 3-storey blocks, each dwelling consisting of one or two rooms

About one-fifth of the families had been living in more wall of the kitchen, which also served for cooking, eating, personal washing and so on. W.C.s were shared, being located on landings or in the yard behind the block, where the communal washhouse was also situated. Some of these tenements were in poor structural condition, but many were found to have been very carefully decorated and furnished by the occupants, and within the overriding limitations of space and equipment made warm and comfortable homes.

The new houses offered a very substantial increase in the area and subdivision of living space, in the provision of storage and in the standard equipment. When allowance was made for the communal w.c.s and washhouses and the coal cellars in the two-roomed tenements, their average area was just over 500 sq. ft., whereas in the new houses the areas ranged between 740 (two-bedroomed flats) and 985 sq. ft. (three-bedroomed houses). Equipped kitchens and bathrooms, with circulating hot water, offering full privacy, took the place of the primitive installation in the tenements. Instead of the single built-in cupboard of 5-6 sq. ft. in the tenement, the provided storage space in the new houses was at least 40 sq. ft. and in most cases was very much greater.

The new dwellings included in the survey were all either 2-bedroomed (50 dwellings) or three-bedroomed (38 dwellings).^{*} They included 12 flats in a three-storey block, 16 flats in two-storey flatted houses (Fig. 3), 32 houses of what had previously been orthodox post-war standards (Fig. 4), and 28 houses of the special space-saving design. The space-saving houses, all of which were three-bedroomed, were 180 sq. ft., or nearly 20 per cent. less in area than the largest three-bedroomed house of orthodox post-war standards.

The orthodox standard houses were built in blocks of four. The specially designed space-saving house was semi-detached and could not easily be adapted for use in terraces. The plan incorporated a number of slightly unusual features which were not found in the orthodox standard house plans. The bathroom is downstairs off the front hall, thus preventing any direct way through from hall to kitchen. The staircase runs straight up across the front elevation, which achieves a well-lit stairway and landing at some expense to the front end and front window of the




Fig. 3, plan of two-bedroomed flatted house. Note the awkward shape of bedroom 1. The shape of bedrooms was felt to be more important than their size. [Scale: $\frac{1}{8}" = 1' 0"$]

Fig. 4, plan of house built to orthodox post-war standards. The hatch was on the whole not favoured and the narrow space between fire surround and the opposite wall made placing of furniture round the fire difficult. [Scale: $\frac{1}{8}" = 1' 0"$]



^{*} Usually referred to as 3-apartment and 4-apartment houses in Scotland.

technical section

through living room. The kitchen provides no reasonable position for a table. Storage space, particularly in the bedrooms, is less than in other plans. The space-saving house is also unusual in that it is built of timber with tongued and grooved boarding on a timber framework. Heat insulation is increased by incorporating a plasterboard leaf between the inner skin, also of plasterboard, and the outer skin of timber.

RESULTS OF THE SURVEY

The method of investigation provided a great deal of detailed information and the following sections are confined to points that have the closest relation to design decisions.

Living rooms

The old tenement kitchen-living rooms had been required for such a variety of purposes that little zoning or specialization was possible. With the sink in front of the only window and the cooker beside it, the typical large table in the middle of the floor, and one wall given over to bed recesses, there was no great scope left for other furnishing.

In contrast, the living rooms in the new homes are designed solely for sitting and eating. The furniture provided by the tenants followed a standard pattern, consisting of a dining suite comprising a table, sideboard and about four upright chairs, and a three-piece suite of settee and two matching armchairs. All except three of the 88 tenants had acquired a dining suite and almost all were buying a three-piece suite, although at the date of the survey only three-fifths had got all three pieces. The armchairs were placed on either side of the fireplace. In the houses with through living rooms the dining table and chairs were normally against the back window and the sideboard either grouped with the dining table or opposite the fireplace.

In the flats, whose living rooms are squarer and more like the tenement kitchen-living rooms, the dining table was usually in the centre of the room. In all cases the function of the fireplace as focal point for furniture arrangements tends to produce some congestion across the centre of the room, and this is clearly aggravated in those plans in which the room narrows to as little as 8 ft. opposite the fireplace (Fig. 4). Circulation is further impeded where direct communication between kitchen and dining table is only through a hatch, and a door such as was provided in the space-saving house was much more acceptable.

In addition to the basic furniture mentioned, some other pieces tended to recur. A glass-fronted cabinet for the display of ornaments or china was the most prized; tallboys, desks and bookcases were occasionally found. About half of the sewing machines (usually treadle) owned by the tenants stood in the living room, so that wall space is needed for these extra items.

As the single living room is almost universal in Scottish

housing, much attention was paid in this survey to whether the varied activities taking place there tended to conflict with each other, since this is an argument usually advanced in favour of parlour-type houses. In spite of questioning, very few complaints were expressed, even with respect to entertaining visitors. In other respects it was important to householders that their living rooms should be suitable for guests, and tenants were ready to criticize rough joinery or the presence of an inappropriate feature such as an airing cupboard.

Kitchens

All but two of the kitchens in the new houses are too small to be classed as dining-kitchens, and this emphasizes the difference in intended function between the tenement kitchen and the new. However, very few families ate all their meals in the living room; when no allowance of space had been made for a table in the kitchen, an eating position was improvised. In the kitchen of the space-saving house, which was 65 sq. ft. in area, some tenants deliberately blocked their back door by a table, this being the only position available. Other kitchens in the sample were between 80 and 100 sq. ft. All these kitchens left space for a small work table, but such tables were commonly used for meals and they, and the kitchen as a whole, were generally regarded by the tenants as adequate in size. Few housewives commented on the working sequences provided, although many of such sequences fell short of the recommendations of kitchen planners. In general, the idea of convenience was taken to mean easy to clean or plenty of cupboards rather than the saving of time, movement or physical effort.

As most of the housewives had been previously accustomed to using a communal washhouse in the tenement yard, using the kitchen for clothes washing meant acquiring a new habit. All the kitchens in the sample incorporated the normal Scottish "tub" and the hot water supply must have been more convenient than the washhouse copper, but it became clear that some housewives regretted the loss of freedom to splash water about without messing up their homes. Up to the last interviews, there were still some complaints about the location of the washing equipment in the kitchen. One-third of the tenants would have preferred their own separate utility room, to avoid steaming up the kitchen and to keep the kitchen work surfaces free for food preparation. Half the housewives mentioned difficulties in drying clothes in the kitchen, although a ceiling rack was provided: this was mainly because the new kitchens had no heating other than the cooker, and the tenement kitchens had had fires.

Bedrooms

As many of the tenants in the sample had been transferred because of overcrowding, the new homes brought a great improvement in privacy for sleeping, quite apart from the separation of sleeping and living




Fig. 5, diagram showing the positions chosen for the bed in bedroom no. 1, of the space saving house (see fig. 1). Note

that the most popular position was facing towards the window.

accommodation. Habits of sharing sleeping accommodation still continued, however. The majority of beds acquired as replacements for bed recesses used in the tenements were small double beds (4 ft. wide), which were chosen partly because families possessed bed linen for this size of bed but partly also for preference. Such a double bed was commonly put even into the smallest (72 sq. ft.) bedroom, which left little room for other furniture. These beds were shared by two children, or sometimes were provided for a single child; such an arrangement allowed guests to be accommodated without the necessity of a special room for this purpose.

It was common for parents to have their youngest child sleeping in their bedroom from choice rather than necessity (in some cases another bedroom was thereby left unoccupied). The parents' bedroom was also regarded as a show room of the house, second in importance only to the living-room, and it was the aim of most families to furnish it with a bedroom suite, though only one-third had completely achieved this by the end of the field work. The following four items were found in addition to the bed or beds in at least one-half of the first bedrooms studied: wardrobe, tallboy or chest of drawers, dressing table and chair. Four first bedrooms contained no more than bed and chair.

The second and third bedrooms were generally much more sparsely furnished. Apart from the bed or beds, a chair and a chest of drawers were the only articles found in nearly one-half of the second bedrooms and in nearly one-third of the third bedrooms. Wardrobe and dressing table were each found in one-quarter of the second bedrooms, but while dressing tables were again found in one-quarter of third bedrooms, these small rooms rarely contained wardrobes. Nearly a tenth of second bedrooms were furnished only with bed and chair and a few, mainly in the two-bedroomed houses, were not furnished at all. Of the third bedrooms, over a third were furnished only with bed and chair, but in only one case was this bedroom left unfurnished.

The much fuller furnishing of the first bedroom justifies this room being made substantially larger than

the second double bedroom. At the same time, the probability that the occupants will provide wardrobes and other storage space makes it less necessary here than in the smaller rooms to provide cupboards.

The tenants were critical of rooms with no clear wall space suitable for taking furniture. In general, flexibility was regarded as more important than size. It is sometimes suggested that bedrooms should not be designed so that the bed faces the window (*i.e.*, the foot of the bed towards the window), but tenants were not found to have any widespread objection to such an arrangement, and in about one bedroom in four the bed was facing the window (see Fig. 5). There was very little evidence of the regular use of bedrooms, whether heated or not, for study or entertaining. Some informants clearly disapproved of using the bedrooms for purposes other than sleeping or dressing, and the possession of a heating appliance did not seem to extend the daytime use of the bedroom.

Bathroom and w.c.

In the old accommodation, only three families had their own w.c.; the remainder had to share with up to four other families. Two families had a bath for their exclusive use, eleven shared a bath with one other family, but the majority had no fixed bath available at home. Hence the provision of a bathroom with running hot and cold water and of a private w.c. probably constitutes the most important amenity in the new home, and was clearly regarded as such by the tenants who complained of the lack of privacy afforded by the facilities in the tenements.

It was not found, however, that personal washing in the new homes was confined to the bathroom. Infants were sometimes still washed in a portable tub by the living room fire and older children were washed in the tub in the kitchen on the nights they were not given a bath. Furthermore, the kitchen sink was used for washing by at least three-quarters of all families in the sample although all bathrooms were provided with hand basins. In particular, the men returning dirty from work almost invariably washed in the kitchen sink even when the kitchen was farther from

technical section

the entrance door than the bathroom basin. Washing in the sink was preferred for a variety of reasons, such as that the kitchen was warmer than the bathroom in the morning because the cooker was on, or because it was handier for kettles of hot water used when the backboiler was not lit or because the bathroom basin was too small* to have a thorough wash or because the bathroom was too clean and precious to be dirtied by regular use.

In the space-saving house the bathroom with w.c. was on the ground floor, whereas in all other houses it was upstairs. Two-thirds of the tenants preferred the arrangement obtaining in their houses; some tenants, in the absence of a second w.c., expressed a preference for the w.c. downstairs within easy reach of children during the day and the bathroom upstairs.

Storage

The old tenements had been provided with little storage space, and it had therefore been customary for many possessions to be kept under beds, while bicycles, toys and so on were kept in lobbies or bedrooms. Removal to the new homes offered a considerable expansion in storage space, even though the space-saving house provided less storage space than had hitherto been incorporated in post-war dwellings.

In the new homes, it was found that the storage of bicycles raised difficulties. Nearly half of the families possessed at least one bicycle. In one house type, bicycles could be kept under the stairs, though there were some complaints that bringing the bicycles in messed up the hall and carpet. Tenants of other houses had no such suitable storage space for bicycles; one-quarter stored bicycles out-of-doors in the garden while others stored them away from home.

On the other hand it appeared that a separate storage space for prams, as commonly provided, was not felt to be so important. In the 3-storey flats, for example, pram stores had been provided in the common staircase hall, but by the end of the inquiry nearly all tenants were using their pram store for coals and taking their prams and bicycles upstairs. It was not felt to be inappropriate to keep a pram in the children's bedroom, and the pram was often used as a cot, especially during the day.

The storage of coal frequently constituted a problem which was aggravated by the fact that some tenants received concessionary coal which was delivered in half-ton loads, while other tenants tried to store up coal in the summer months. The space-saving house design had an outside bunker with a capacity of 8 cwt. Many tenants found this inadequate, although the outside position seemed quite acceptable. The commonest arrangement was to have the fuel store in the kitchen, and in this case complaints of inadequate size, though encountered, were overshadowed by the inconvenience of having the coalman delivering coal straight into the kitchen. In one plan (Fig. 4) the door

to the fuel store was in a narrow neck 3-ft. wide so that the opposite wall was frequently marked. Many tenants felt that an outside bunker would have been preferable, and one-fifth had themselves provided outside bunkers, reserving the original fuel store for the storage of other possessions such as step-ladders, garden tools and working clothes. This desire for a suitable place to put dirty working clothes was frequently found; pegs in the space-saving house which were clearly visible from the front door were removed by half the tenants and in other house types such pegs were often unused. Provision for these clothes might be more suitably located in the kitchen.

In the houses studied there was no direct relation between the provided storage space and the size of family to be accommodated. In fact, nearly all the two-bedroomed houses had a greater total area devoted to storage than the three-bedroomed houses. Examination of some of the plans suggested that storage space was made up of corners in the house for which the designer could find no specific use; this is illustrated by the fact that the two floors of the flatted house, otherwise almost identical in plan, differed substantially in storage area (58 sq. ft. on the ground floor and 77 sq. ft. on the first floor).

In the analysis a comparison was made between households provided with up to 10 sq. ft. per person storage space and households provided with 10 sq. ft. or over (measured in terms of floor area). While this division is arbitrary, it is of interest that a significantly higher percentage (94 per cent. as opposed to 66 per cent.) of those with 10 sq. ft. or more per person expressed themselves as satisfied with their storage arrangements. There was no evidence from this study that families supplemented their provided storage space to bring it up to some previously-conceived level. The purchase of some articles of furniture used for storage would appear to have been determined less by convenience than by custom.

Circulation

Most of the tenements from which the tenants came were reasonably up-to-date in their circulation layout, providing a small hall or lobby (often occupied by the cooker) leading to the kitchen. In most cases the bedroom, where there was one, opened off the kitchen but in some tenements there was also independent access to the bedroom.

Of the new homes, the space-saving house was unusual in that, in order to conserve space, there was no direct access through the house from front hall and staircase to kitchen. Although these houses were semi-detached, giving direct access out-of-doors from the street to the back door, this feature was criticized by nearly half of the tenants, largely on the grounds that it made the living room into a passageway between kitchen and bathroom-w.c., an inconvenient arrangement especially in homes with children. Of the objecting tenants, however, only two would have liked a through way at the expense of the area of the living room.

* The wash basin in all the houses conformed to the standard i.e. 22 in. x 16 in.) advocated by the Department of Health for Scotland, which is the smaller of the two British Standard sizes. The deep sink in the kitchens measured 21 in. x 17 in. x 15 in.

technical section

In the three-storey flats and the flatted houses, the living-room had to be crossed to reach the kitchen and this was objected to by a few of the tenants. Two of the house types had rather large halls, which appealed to some tenants because they enabled the entrance to the dwelling to be made more attractive.

Ceiling heights

Many of the tenements had high ceilings, some as much as 12 ft. high, and it seems that the heights of rooms in Scottish houses have traditionally been greater than in England. Apart from the space-saving houses, which had 7 ft. 6 in. ceilings, all the new dwellings had 8 ft. ceilings.

The great majority of those tenants in dwellings with 8 ft. ceilings would not have liked them to be any higher. There was evidence of some increasing acceptance with experience of the 7 ft. 6 in. ceiling, but there remained a small, though not negligible proportion of householders, who were not entirely happy about the lower ceilings.

Some objections were perhaps a little fanciful, for example, that the low ceilings were bad for health or that they encouraged steam from cooking to go right through the house, but others were more straightforward, for example, that tall members of the family hit their arms against lighting fittings or found that ceiling clothes-drying racks got in their way.

Windows

One of the big changes in the new houses concerned windows. The tenement property with its high rooms had mostly tall sash windows. Owing to the density of development, these were large and expensive in curtain material in relation to the light that they let in.

In the new houses the windows were lower and wider and admitted much more light. The windows varied greatly in type, including wooden sash, wooden casement and metal casement.

Tenants did not much like to have windows that were out of the ordinary. For example, the space-saving houses had a staircase running up inside the front elevation, so that there was only room for a small front window in the through living-room: this drew adverse comments.

With fairly small front gardens, the problem of privacy was raised by many tenants, particularly in respect of living-rooms. This was partly the reason for the widespread custom (followed by three-quarters of all tenants) of leaving living-room curtains permanently drawn across at least half of the window area. As is well known, however, the "dressing" of living-room windows is very susceptible to local fashions and at least some of the curtains may have been kept partly drawn for reasons of display rather than of protection.

As has been found in other surveys, there were some complaints about the difficulty of cleaning windows that cannot be reached from the ground outside the house. Cleaning difficulties were mentioned by one-

quarter of tenants with sash windows and by two-fifths of tenants with casement windows. The "easy clean" hinges at present in use on most casement windows do not appear to give sufficient clearance for the housewife's arm.

Sound insulation standards

In the new homes, a very big contrast between houses and flats was found in respect of noise. The houses were built to a normal modern standard with party walls in cavity brickwork or lightweight concrete, and there was a negligible number of complaints of noise disturbance from neighbours.

A very different situation was found in the flats, where noise was a constant cause of irritation. The offence was mainly due to noise transmission through the floors, which were constructed of T and G boarding floating on glass-silk quilting. This type of floor gives sound insulation 3-4 decibels below the B.R.S. Grade II and this is sufficiently low to account for the dissatisfaction on this score.

The difference in the two standards is shown by the fact that only 14 per cent. of families in houses were disturbed by noise while 69 per cent. of families in the two and three storey flats were disturbed.

Heating

In the one or two roomed tenements from which the majority of tenants had come, the problem of heating had seldom been serious. Furthermore, as the kitchen-living room was also the main bedroom the problem of heating sleeping quarters hardly existed. On the other hand, only 30 per cent. of the tenants in the sample had had any form of water heating apart from kettles.

The new houses were all equipped in living rooms with improved open fires with back boilers for water heating. Provision for heating in the bedrooms varied. Before 1950 it was customary to provide a fireplace in at least one bedroom but at present nothing more than an electric point need be installed in bedrooms. In the present sample, however, the flatted houses had a fireplace (first bedroom), the three bedroomed flats in the 3-storey blocks had a gas fire; the space saving houses had electric power points only, and the remaining houses had either warm air ducts from the living room fire to the first and second bedrooms or contained an airing cupboard in the first bedroom.

The open fires in the living rooms were generally satisfactory; there were few days in the year on which they were not lit for part of the time, and the back boilers therefore assured a fairly regular supply of hot water. Only the longest of the through living rooms proved difficult to heat at each end; the hatch was also said to be a source of draughts. There were fairly frequent complaints of inadequate heating in other rooms, particularly in the bedrooms. In the flatted houses, about 70 per cent. of tenants sometimes lit the bedroom coal fire in very cold weather. These fireplaces were appreciated particularly for possible

technical section

use in case of illness; where no fireplace was provided the sick bed was sometimes moved into the living room. However, there was some criticism of these bedroom fireplaces because, due presumably to their being added to standard plans, they increased the awkwardness of an already awkwardly shaped room (Fig. 3).

Either for intermittent use in bedrooms or for heating other cold spots, two thirds of all tenants had some supplementary heating device. Most of the appliances brought from their previous homes were electric fires, but those who had bought a heater since moving had usually chosen a paraffin heater. Only a fifth of tenants complained that their kitchens were cold.

The space-saving house, although the only type in the sample with no regular provision for heating apart from the living room fire, was on the whole found to be comfortably warm. This may have been due partly to the plan, which omitted a through passage, and partly to the construction, which incorporated triple leaf external walls*.

CONCLUSIONS

Any conclusions on the success of the new houses in meeting the needs of their occupants must be related to the wider context of the change. Removal to the new scheme involved many changes in school and church attendance, shopping habits and friendships, as well as a change in physical environment. Furthermore, this particular estate was believed by tenants and housing authorities alike to be socially inferior to others, and this may have affected the tenants' views on their new homes.

On the whole, satisfaction with the new locality was at its highest just after removal, and specific criticisms of the different houses tended to emerge only in later interviews. On first moving, for example, tenants were prepared to make the best of whatever house type they had been given; for example, those allotted a flat when they hoped for a house, or *vice versa*, said at the first interview that they were just as well pleased with what they had. As time went on, tenants tended to become identified with the type that they were occupying, and the majority of them came to claim that theirs was the best type on the scheme. There is some indication, however, that tenants of the space-saving houses and of the three-storey flats were less convinced of the merits of their houses than occupants of the other types. The space-saving house, with its unusual form of construction and external appearance, was commented upon adversely both by them and by tenants of other house types; there is evidence that the rather low standing of this house reflected the general local feeling that it was a "utility design" and was not directly based on criticism of any particular design features. There is little evidence that those living on the estate had any specific knowledge of the design

of interiors of house types other than the one that they themselves occupied, and those occupants of the space-saving houses who would have preferred another type were attracted to one on the estate of more substantial appearance than theirs. The acceptability of the economies introduced into the design of the space-saving house was undoubtedly reduced by the fact that this house was of timber construction.

The attitudes of tenants interrogated in this inquiry do not suggest that satisfaction increases directly with the size of rooms. Different housewives expressed themselves as satisfied with rooms of widely differing sizes, and only complained when some inconvenient feature caused a specific difficulty, for example in arranging furniture. As the rooms in the space-saving house were well shaped, their reduced size was acceptable. In general, the cost of furnishing and heating large rooms is an important curb on the demand for space.

The kitchen in the space-saving house was considerably smaller than that in any other type. This made it extremely difficult to eat any meals in the kitchen, thereby conflicting with a widespread custom. The space-saving kitchen is well designed, with a better working sequence than in some of the other houses, but with tenants the desire for dining space overshadowed appreciation of the layout of equipment, the amount of work surface or the provision for storage.

The objections raised to the absence of a through passage from front to back of the space-saving house were no greater than complaints of inconvenience in the more orthodox houses which were provided with hatches; certainly a reduction of living space to provide a through passage would have been less acceptable.


Various other economies were incorporated into the design of the space-saving house. As has been stated, the reduction of the ceiling height to 7 ft. 6 in. was accepted by the majority of tenants, and among those dissatisfied feeling was not strong. Tenants were sorry to have pegs in the hall instead of a downstairs cupboard for dirty working clothes, and the elimination of cupboards from all but the third bedroom was felt to be rather a severe lowering of standards in comparison with other house types being built on the estate. In these houses, kitchen-storage space was not much below normal in contrast to storage elsewhere, and this enquiry suggests that if there is to be any economy in storage provision the reductions should be shared more evenly between kitchen and bedrooms. One general principle to be applied to decisions involving reduction of costs is that the need for utility should not allow poor craftsmanship; it may even be better to omit an item of equipment than to countenance rough joinery or finishing, which may lead tenants to conclude that they have been given an inferior product and are therefore victims of discrimination.

The investigation described was undertaken as part of the programme of the Building Research Board; this paper is published with the permission of the Director of Building Research.

* The U values for the various house types show that the space-saving house did provide the best insulation. For this house the U value was 0.22, for the two traditional houses 0.28 and 0.31, for the three-storey flats 0.31 ground floor, 0.27 upper floors, and for the flatbed houses 0.36.




planning study

TOWER OFFICE BLOCK IN THE CITY OF LONDON



One of the commonest forms of real estate activity in big cities is the redevelopment, by a large company, of a group of adjacent sites in separate ownerships after sometimes lengthy negotiation. In London—and the City in particular—the disagreeable results of this activity can be seen on every hand; squat blocks of building of six or seven storeys, hugging all frontages and set back at the top to comply with bylaws and private rights of light, and invariably “in the classical manner.” The purpose of this kind of redevelopment is, of course, to provide the maximum permissible accommodation (and hence revenue) on each site, and this is usually achieved by the laziest method—cramping the accommodation into the precise form of the “jelly mould” dictated by the “bylaw angles” and rights of light.

There is, however, the optional use of the daylight factor protractor as an alternative and the advantages to be gained are often considerable. Fountain House, Fenchurch Street, which we illustrate here, is the first large redevelopment scheme in the City of London to depart from the usual practice. Here it was found that a tower-shaped block could be built at the centre of the site with no restriction on height, giving better daylighting to surrounding properties than a lower, wider building. The photograph (left) shows how the main tower is disposed in relation to

Ground floor plan [Scale: $\frac{1}{4}$ " = 1' 0"]

Typical upper floor plan

planning study

TOWER OFFICE BLOCK IN THE CITY OF LONDON: continued

the two-storey block which covers the entire site. This lower block is perhaps the least successful part of the building; it follows the exact frontage lines (perhaps because of a belief that this gives maximum "foot run" of display window) and in its splayed corners, entrance doors and general detailing reveals the classical pedigree of the building. The second photograph on page 547 shows the 14-storey tower from the opposite corner, looking down Fen

Court. At the top right-hand corner is the window-cleaning cradle which is slung from the pergola on the roof.

The size of the building in relation to the surrounding properties can be seen below. The height above road level is approximately 170 ft. The building provides 100,000 sq. ft. of office space and cost approximately £750,000.

The clients are the City of London Real Property Company Ltd., the chairman of whom, Edmund Howard,

was nominated one of the Men of the Year by the AJ in our 1956 New Year issue, for taking the initial decision to depart from the City's classical jelly-mould tradition. The architect is W. H. Rogers of the clients' own architectural department, the consulting architect was Sir Howard Robertson, and the structural consultants were G. A. Dodd and Partners. The general contractors were Wimpey & Co. Ltd. and Trollope & Colls Ltd. For sub-contractors see page 556.



building illustrated

OFFICES


in FREDERICK ROAD, EDGBASTON, BIRMINGHAM; designed by JOHN M. D. MADIN; architect-in-charge DOUGLAS V. SMITH; quantity surveyors SILK and FRAZIER; consultants (acoustics) B.R.S.

St. James' House at Edgbaston is the new headquarters of the Engineering and Allied Employers' Association, the objects of which are to promote good relations between management and labour and to negotiate conditions and rates of pay with the trade unions on behalf of the employers. The clients therefore required a building to house their own office staff, dining rooms and other facilities for members, and conference suites.

Viewpoint 1: the building from the north-west.




building illustrated




Site plan with photographic viewpoints.


The building has been organized in two blocks, one squarish in plan with greater storey heights, and the other long and thin in plan. These can be seen in the photograph taken from viewpoint 2, above. The main block is of framed construction and the subsidiary block of load-bearing brickwork. The architect states that "the external appearance has been designed in order to create a dignified building which would also be in keeping with the Regency character of Edgbaston"; but at times this has meant using Regency motifs, such as the first floor balconies and windows or the achievement of an almost neo-classical character, as in the main entrance porch, viewpoint 3, right. This last view shows the cream travertine used as a veneer to some of the faces of the main block, and the green marble pierced slab on the south side of the porch.



Cross section



First floor plan



analysis

SITE

The site is a long narrow one at the corner of Frederick Road and St. James's Road, previously occupied by two houses that were destroyed by enemy action. The long side is orientated north and south and there is a fall to the eastern end. When excavations began in 1955 extensive cellars were uncovered; also three old wells, which may have provided a water supply in the 19th century.

PLANNING AIMS

The aim of providing a south aspect to as many rooms as possible dictated the general plan. The building is in two units, a main block and subsidiary block, the former of r.c. frame construction with brick infilling panel walls, the latter of brick load-bearing construction for economy reasons. The larger and more important rooms are within the main block, and the spans of these called for frame construction. The subsidiary block contains anterooms, dining rooms, caretaker's flat and offices, all of a reasonable size. The flat comprises a living room, two bedrooms, bathroom, hall, cloakroom and kitchen, and has a private entrance and kitchen entrance. All conference rooms and parts of the building to which the public is admitted are on the ground floor, while the first floor is used for administrative offices. The entrance hall separates a self-contained trade union suite, consisting of conference room, anteroom and lavatory accommodation on the west, from the Association's suite, comprising a large boardroom, with adjoining anteroom and dining rooms and a separate entrance, toilet accommodation and lobby for members of the Management Board. Negotiations with trade union representatives are held in the boardroom, and this arrangement allows both sides to retire for private discussion to their own respective conference rooms. The remainder of the ground floor at the eastern end contains the kitchen and service pantry and the caretaker's flat. The more important offices, i.e. those of the chairman, deputy chairman and secretary of the Association, have been placed in the main block, where the storey height is greater, enabling the plenum ducting to be installed above suspended ceilings. The other administrative offices have been placed in line along the south side of the subsidiary block, with an access corridor to the north. The architects designed the fitted carpets, curtain material and furniture for all the principal rooms and selected the remainder, but this was carried out under a separate contract.

price per sq. ft.	s	d
preliminaries and insurances	2	6½
contingencies		8

Work below ground floor level

Strip foundations and r.c. stanchion bases and ground beams. Separate basements for ventilation and heating plant. Connecting crawlways and underground ducts. Walls within ducts of fair-faced semi-engineering brickwork. Granolithic floors and skirtings to basements, etc. Steps down to heating chamber, concrete with granolithic finish.

STRUCTURAL ELEMENTS


Frame or load-bearing element

Main block: r.c. frame, i.e., columns, beams and ground beams, and *in-situ* concrete floors and roof. Subsidiary block: load-bearing walls, facing brick externally and common brickwork internally.


9 1



Viewpoint 4 shows the south side of the main block. The ground floor windows on the right are those of the boardroom; above them is the balcony of the chairman's and typist's offices. The deputy chairman has the smaller balcony on the left of the photograph.



Ground floor plan [Scale: 1" = 1' 0"]




Basement plan

building illustrated



The subsidiary block contains dining rooms, a kitchen and caretaker's flat on the ground floor, and less important offices on the first floor. The porch in the foreground of the photograph (viewpoint 5), above, is the entrance to the caretaker's flat; the glazed porch in the background is the members' entrance.



The largest room in the building is the boardroom, where negotiations with trade unions are carried on. The photograph above shows the boardroom seen through the leather-panelled doors which separate it from the main entrance hall.



The ante-room and dining room, above, are separated by sliding folding doors. The furniture in the ante-room was designed by the architect, together with the lighting fittings and carpet. The furniture in the dining room is reproduction Regency. Quite apart from blending the exterior of the building with the character of Edgbaston, it would seem that a preference for things Regency has decided the character of the building.

analysis

s d
17 2½

External walls

Main block: 11-in. cavity panel walls to frame in common brickwork with external cladding of 1-in. polished travertine on front elevation, and of facing brickwork elsewhere.

Subsidiary block: 11-in. cavity walls with external facings of buff bricks. Window surrounds to west and south elevations of 1-in. Westmorland slate.

$$\text{Ratio: } \frac{\text{solid wall}}{\text{floor area}} = \frac{.599}{1}$$

Windows

3 0½

Hot-dipped galvanized heavy universal section with metal head for glazing internally. Boardroom and entrance hall windows, box section pressed metal mullions and transoms with aluminium glazing beads externally to fixed lights. Staircase window, solid steel mullions with pressed metal transoms arranged to take polished teak glazing beads on both sides.

$$\text{Ratio: } \frac{\text{windows}}{\text{floor area}} = \frac{.231}{1}$$

External doors

7½

Armour-plate glass to main entrance and members' entrance.

Elsewhere, softwood, glazed in one pane or solid-core flush doors, with external quality ply.

$$\text{Ratio: } \frac{\text{external doors}}{\text{floor area}} = \frac{.010}{1}$$

Upper floors (cost included in frame)

In-situ r.c. on steel shuttering, using a retarder to obtain a good key for plaster. (Cost of screed is not included here but under floor finishes.)

Span of each type: in the main block span varies depending on planning. In subsidiary block greatest span is 14 ft. 9 in. between walls.

Area in main block: 4,264 sq. ft.

Area in subsidiary block: 2,748 sq. ft.

Super loads: 50 lb. per sq. ft.

Staircases

2 10½

In-situ r.c. Cost of tread finishes, whether granolithic or rubber, are given under floor finishes. Number of staircases: 3.

Widths: one, 6 ft. 6 in.; two, 3 ft. 6 in.

Total rise: one, 14 ft.; two, 10 ft. 6 in.

Roof construction

2 7½

In-situ concrete with lightweight screed to falls, averaging 4 in. thickness. This is a floated bed of lightweight concrete, weighing 31 lb. per cub. ft., coefficient of thermal conductivity, 0.68 B.Th.U./sq. ft./hr./deg. F./in.

Area: 936 sq. yd.

Roof lights

7½

Steel lantern type with gearing to six and with wired cast glass domes.

Number of lights: 10.

Total area: 192 sq. ft.

Glazing

2 11

All windows are double glazed in laminated glass with exception of panes over 20 sq. ft., for which patent sealed double glazed units are used.

Total of structural elements 39 0½

analysis

Internal partitions

Types of partition: half brick, hollow block.
Area of each type: 412 sq. yd.; 558 sq. yd.

Screens

Walnut screen to telephone operator's room.
Softwood screen in general office.

Internal doors

Flush doors, some in Australian walnut veneer,
others painted.

Some double doors in mahogany.

Number of single doors: 80 (18 veneered).

Number of double doors: 21 (8 veneered).

Ironmongery

Mortice locks or latches (master key system).
Lever handles in bronze or polished aluminium
depending on whether the door is polished or
painted. Floor springs to double doors.

Fittings

Cupboard units to chairman's office, and secretary's
office. Telephone booths; entrance doors to
boardroom covered with leather. Sundry cupboards
etc.

Total of partitions and fittings 8 7½

Floor finishes

Type of finish	Area in sq. ft.	Price per sq. yd.
		s. d.
Grano	2,169	13 6
Terrazzo tile	1,269	38 6
Rubber tile	1,152	50 0
Teak block	8,946	42 3

Wall finishes

Generally plastered.
Boardroom treated with moulded sycamore strip
panelling on plywood backing and studding to two
ends. Acoustic blanket hung behind studding.

Ceiling finishes

Generally plastered.
Suspended ceiling to offices where there is plenum
heating and to boardroom and trade union
conference room (plaster on expanded metal
lathing).
Slotted acoustic panel ceiling to corridors, cloak-
rooms and lavatories on timber bearers.

Roof finishes

Two layer asphalt on felt sheathing. Area: 8,424
sq. ft.

Decorations

Gloss or flat paint to woodwork and metalwork.
Emulsion paint in BSS colours to ceilings and walls.
Wallpaper has also been used in a number of public
rooms and offices.

Total of finishes 22 8½

External plumbing

Cast-iron r.w.p.s, copper flashings and covering to
ventilation housing, roof traps, etc.
Graphited copper strip under roof slab of subsidiary
block for thermal movement.

s d
1 2

Cold water installation

Copper, painted. Lagged in crawlways.

3½

Sanitary fittings

Type of fitting	No. of each type
Sinks, stainless steel	2
Lavatory basins, vitreous china	
pedestal	10
Urinals, glazed fireclay	3
W.c.s, vitreous china, low level	9
Baths, porcelain enamel	1

3 0½

Heating, ventilation and hot water

A system of radiant heating units with plenum
heating system to boardroom, anteroom, dining
rooms and five principal offices on first floor.
Boardroom heating can be run at 55 deg. F., when
the room is not in use.
Boiler, oil fired and fully automatic, capacity,
811,000 B.Th.U.s per hour. Three accelerators,
1 for plenum, 1 for water circulating and 1 standby.
Hot water system for two calorifiers is run off
heating with electric immersion heaters for summer
use.

2 10½

The plenum is controlled by a time clock.
2 inlet fans with filters and heater batteries are fed
from the boiler plant, and there are 2 extract fans.
All fans are of low speed type, mounted for quiet
running.

6 10½

Internal temperatures: 65 deg. F. in offices; 60 deg.
F. in corridors, lobbies and cloakrooms, 55 deg. F.
in lavatories.

Air change: 9 changes per hour in boardroom, 3 in
anteroom and dining rooms, with reversing switch.
5 to 7 changes per hour in principal offices.

"U" of walls, 0.30

"U" of roof, 0.12.

5 8

Electrical installation

Cost of electrical fittings

Type of point	No. of each type
Lighting	283
Cold cathode tube	206 ft.
Power points	76
Bells	6
Clock points	3

5 5

Wiring to fan motors, circulating pump, immersion
heaters, motorised valves, electric fires, etc.

Total of services 18 3½

2 3½

Drainage

Combined system in salt glazed pipes, brick
manholes with medium duty manhole covers.

2 5

Other elements not shown above

External works: boundary walls in facing bricks
with reconstructed stone coping. Tar macadam
paving to car park and roads. Grassed areas and
planting. Timber gates to St. James's Road exit.
Concrete flower tubs.

10

£77,946 (net cost excluding
external works)

Total per sq. ft.: $\frac{£77,946}{15,293 \text{ sq. ft. (floor area mea: ured inside external walls)}} = 101 \text{ 11½}$

s d
11 4½

11

11 3

3 11
1 0

1 4½

6 11½

analysis

SUMMARY

Ground floor area: 7,385 sq. ft.
 Total floor area: 15,293 sq. ft.
 Type of contract: RIBA
 Tender date: May 1955
 Work began: September 1955
 Work finished: July 1957
 Tender price of foundations, superstructure, installations and finishes: £77,946
 Final contract price not yet available.
 Tender price of external works and ancillary buildings: £5,333
 Total: £83,279

COST COMMENTS

The long narrow plan shape chosen in response to the various site conditions has had its repercussions on the cost.

(a) The high perimeter walling area is reflected in an unusually high cost of 17s. 2½d., although it should be noted that this includes large areas of travertine and the slate window surrounds, both of which would increase the cost of walling above the average.

(b) The long service runs from the heating chamber at the extreme end of the building have required more circulation pumps and larger flow and return pipes than would have been the case had the plant been centrally placed. But the complicated heating and ventilation system has affected the cost of other elements besides that of the boiler and ventilation equipment, and this very substantial influence is not easily shown in the analysis. The underground crawlways and ventilation chamber, the extensive suspended ceilings with ventilation trunking above, and the provision of double glazing must all be considered as stemming from the requirement of first-class comfort, and therefore any comparison with other forms of heating must take these extra constructional requirements into account. It is to be hoped that the feeling of warmth and well-being induced by these conditions will contribute to an atmosphere of goodwill in the negotiations for which the building has been designed. The high standard of finishings provided in the boardroom and main conference rooms also increases the cost. Finishings in the greater part of the building are of normal office standard.

CONTRACTORS

General contractor: W. J. Whittall & Son. *Sub-contractors—Steel fabric and bar reinforcement:* Guest, Keen & Nettlefold (Reinforcements) Ltd. *Special facing bricks, air bricks and sill tiles:* Blockleys Ltd. *Common bricks:* London Brick Co. Ltd., Kings Norton Brick Co. Ltd. *Engineering bricks:* Aldridge Brick & Tile Co. Ltd. *Broughton Moor slate surrounds and marble work:* W. H. Fraley & Son Ltd. *Asphalt*

roofing and paving: The General Asphalte Co. Ltd. *Insulating roof screeds:* Celcon Ltd. *Reconstructed stonework and coping, granolithic floors and steps:* John Ellis & Sons Ltd. *Special steel windows, lantern lights and gearing:* Henry Hope & Son Ltd. *Special double glazing and armour plate doors:* Glass (Coventry) Ltd. *Luve Tile plastic ceiling louvers:* Harris & Sheldon Ltd. *Aggregates:* Midland Gravel Co. Ltd. *Cement:* Cement Marketing Co. Ltd. *Electrical installation:* B. French Ltd. *Switchgear, general lighting fittings and installation of cold cathode tube lighting:* General Electric Co. Ltd. *Other light fittings:* Merchant Adventurers Ltd. *GPO and internal telephone systems:* Greenwood's & Airvac Ventilating Co. Ltd. *Internal telephones:* Siemens Bros. & Co. *Electric switches:* Britmac Electric Co. Ltd. *Drying cabinet heater:* E. K. Cole Ltd. *Venetian blinds and electrically controlled venetian blind:* Venetian Vogue Ltd. *Cellar drainage pumps:* James Beresford & Son Ltd. *Heating, hot water and Plenum systems:* Brightside Heating & Engineering Co. Ltd. *Electric fires:* H. Frost & Co. Ltd. *Acoustic blanket and insulating materials:* Stillite Products Ltd. *Special leatherwork and light fittings:* H. M. Roberts Ltd. *Gas services:* West Midlands Gas Board. *Gas Appliances:* Ascot Gas Water Heaters Ltd. *Gas cookers and kitchen extraction equipment:* Radiation & Group Sales Ltd. *Wrought iron balustrades and steel staircases:* Best & Lloyd Ltd. *Special folding sliding doors:* The Bolton Gate Co. Ltd. *Duct covers and general metalwork:* H. E. Breaker (Metalwork) Ltd. *Tarmacadam paving and felt roofing:* Neuchatel Asphalte Co. Ltd. *Steelwork:* Charles Wade & Co. Ltd. *Waterproofing compounds and mastics:* Evoid Ltd. *Stone pitching:* Rowley Regis Granite Quarries Ltd. *Wood block floors:* Vigers Bros. Ltd. *Terrazzo floors and paving:* Standard Pavement Co. Ltd. *Rubber flooring:* Marshall Davies & Co. Ltd. *Glazed tiles:* Pilkingtons Tiles Ltd. *Tile fixing:* J. W. Meredith. *Sliding door gear:* P. C. Henderson Ltd. *Special flush and veneered doors:* Leaderflush Ltd. *Suspended ceilings:* The Expanded Metal Co. Ltd. *Door furniture designed by the architect, locks and general ironmongery:* James Gibbons Ltd., Parker Winder & Achurch Ltd. *Sanitary fittings:* Charles Winn & Co. Ltd. *Plasterers:* T. Hawkins. *Plaster, plastering materials and acoustic panels:* Gyproc Products Ltd. *Plumbers:* David F. Wiseman & Sons Ltd. *Decorators:* J. Patrick & Co. Ltd. *Decorating materials:* Docker Bros. Ltd., Permoglaze Ltd. *French polishing:* A. Woodward & Son. *Furniture, carpets and curtains to the architect's design, made up and fitted:* Hampton & Sons Ltd., I.C. Steel Ltd. *Special curtains designed by the architect:* Tibor Ltd. *Other furniture:* Bell Barn Ltd., Restalls Ltd. *Wooden door handles to design of architect:* Richard Swale. *Hat and coat racks designed by architect:* A. Edmonds & Co. Ltd., *Fireplaces:* W. H. Fraley & Sons Ltd., The Griffin Foundry Fireplace & Sanitary Fittings Ltd. *Safes:* Thos. Withers & Sons Ltd. *Haulage:* C. Williams & Sons Ltd. *Scaffolding:* Horstel Ltd. *Doormats:* Birmingham Royal Institute for the Blind. *Landscape gardening:* Garden Developments Ltd. *Concrete flower tubs:* Stuart's Granolithic Co. Ltd. *Flag pole:* Poles Ltd. *Indoor plants:* Neale Bros. (Nurseries) Ltd.

lating
ping,
pecial
& Son
doors:
Harris
Ltd.
ation:
and
ic Co.
GPO
Airvac
& Co.
abinet
rically
ninage
er and
Ltd.
t and
rwork
West
Water
ment:
s and
doors:
work:
nd felt
harles
astics:
arries
rs and
oring:
Tiles
P. C.
rflush
Ltd.
eneral
hurch
erers:
annels:
Sons
erials:
shing:
to the
Ltd.,
hitect:
Ltd.
Swale.
& Co.
Griffin
Thos.
Ltd.
Royal
Deve-
ic Co.
Bros.

ENTRANCE DOORS: SHOP IN ROTTERDAM


Marcel Breuer and A. Elzas, architects




The quality of these doors seems to derive from the simplified (but appropriately massive) form of the gear and the use of extruded aluminium beads of constant section to hold the glass and cover the joint with adjacent materials.

ENTRANCE DOORS: SHOP IN ROTTERDAM


Marcel Breuer and A. Elzas, architects






ELEVATION. scale 1/4" = 1' - 0"



PLAN. scale 1/4" = 1' - 0"




PLAN AT B-B. scale 3/8" full size



SECTION A-A.

note: figured dimensions in feet and inches are approximate

ROOF TRUSS: CHAPEL AT OTANIEMI, FINLAND

Heikki Siren, architect (material supplied by Imre Weores)

This celebrated roof truss is a good example of the expression proper to timber. Technical interest lies in the liberal use of mild steel tie and fishplates to reduce the size of the timber sections. Note the unobtrusive fixing of the lights at the foot of each post.

ROOF TRUSS: CHAPEL AT OTANIEMI, FINLAND

Heikki Siren, architect (material supplied by Imre Weores)




note: figured dimensions in feet and inches are approximate



Architect: S. Vincent Goodman, F.R.I.B.A

Specialist Contractor: Rowan & Boden, Ltd., Luton.

flooring is child's play...



to the flooring specialists with the largest range of flooring materials for all types of building — Armstrong. Shown above is an installation of Accotile thermoplastic tile at Shortstown County Primary School, Bedford. Chosen for colour brilliance, design scope and hard wear — it will give long service under the arduous conditions of school life! . . . In addition to Accotile, with its many advantages of low cost and durability, Armstrong offer Accoflex, the grease-resisting Vinyl-Asbestos tiles, Cork Tile, Linoleum in tile or sheet form, and Plasco jointless flooring. Specialist Contractors throughout the British Isles. Fully informative literature available on request.

Armstrong Flooring

ARMSTRONG CORK COMPANY LTD., Flooring Dept., Bush House, Aldwych, London, W.C.2 COVent Garden 1101



More scope

for creative achievement in floor styling



Acknowledgements to K.L.M.-Royal Dutch Airlines


Architect: J. Stroud Foster, A.R.I.B.A. Linoleum Installation: Cellulin Flooring Co. Ltd.



... stands for The Linoleum Manufacturers' Association, 127 Victoria St., London, S.W.1.
For further information write to the Association or to any of the following members :-

Barry, Ostlere & Shepherd Ltd., Kirkcaldy
Dundee Linoleum Co. Ltd., Dundee
Linoleum Manufacturing Co. Ltd., 6 Old Bailey, E.C.4
Michael Nairn & Co. Ltd., Kirkcaldy
North British Linoleum Co. Ltd., Dundee
Scottish Co-operative Wholesale Society Ltd., Falkland, Fife
Jas. Williamson & Son Ltd., Lancaster

82



A Linoleum floor at the Bond Street offices of K.L.M.-Royal Dutch Airlines. Notice how skilfully the architect has selected a contemporary pattern muted in tone to accentuate his decorative theme. Linoleum, more successfully than any other modern flooring, provides resistance to wear coupled with quietness of tread, which a busy office demands.


PLAN FOR

LINOLEUM

, Ltd.

-
t
o
-
o
e


FACULTY OF ARCHITECTURE BUILDING AT UNIVERSITY OF SANTO DOMINGO



Work has just started on a new building for the faculty of Architecture and Engineering in the University of Santo Domingo, Dominican Republic. The building, of which a model is shown here, will cost half a million dollars and cater for 1,680 students. It contains 14 lecture rooms, seven drawing offices, two large laboratories, a library and reading room, an amphitheatre seating 350, and general faculty and administration offices. The Centre was designed by Dominican architect Jose Antonio Caro.

Two more good reasons for choosing **EZEE** kitchens . . .

Perfection of design and finish, typical of the whole Ezee range, is a feature of these two units. Cabinets made of Zintec steel sound-deadened and stove-enamelled. Other units both 24" and 21" deep incorporating refrigerators, clothes and dishwashers available.



Very competitive prices. Special terms for bulk orders. Quick delivery. Free planning service at disposal of Architects and Clients. May we send you our illustrated booklet T.1?

EZEE/REFRIGERATOR SINK UNIT


VJF4 with Vitreous enamel sink and drainer. SJF4 with Stainless steel sink and drainer W.42½ ins. x D.21 ins. x H.36 ins., plus 1½ ins. backsplash. Sink and single drainer right or left handed with cupboard under sink and 3 cu.ft. refrigerator under drainer. Colour Cream or White. This model is available only in the 21" range. Other Sink/Refrigerator units are to be found in 24" depth.



EZEE-REACH WALL CABINETS

. . . at last, a top shelf you can always reach! Middle and top shelves pull out and down with smooth, steady action. Springs built into the mechanism take the weight and assist operation. Size of cabinet: 36 ins. high, 21 ins. wide, 12 ins. deep. Made of Zintec steel. Bonderised and stove-enamelled cream or white. Double-panelled sound-deadened door, hinged right or left hand.

CO-OPERATIVE STORE AT WESTON-SUPER-MARE



This glass-roofed store, with a flat roof which could become a landing stage for helicopters, is designed by the Bristol Co-operative Society's architect, S. T. Wyatt, and is to be built in the next 18 months in Weston-super-Mare, and will replace all the Society's local shops, except the food shops. The store is being built on a concrete raft, since trial holes going down 80 ft. revealed nothing but silt under the site, at the corner of High Street and St. James Street. Both frontages are identical and almost entirely of plate glass, and on the side facing the sea an electronic eye will control the shop's blinds according to the strength of the sun. Counters, stands and lighting within will all be movable since flexibility is needed in a shop catering for local people all the year, and for large numbers of summer visitors.


Contractors

Fountain House, Fenchurch Street, London, E.C.3 (Pages 547-548). For the City of London Real Property Co. Ltd. Architect: W. H. Rogers, A.R.I.B.A. Consulting architect: Sir Howard Robertson, M.C., A.R.A., P.P.R.I.B.A., S.A.D.G. Consulting engineers: G. A. Dodd & Partners. Consultants, heating and electrical: Engineers Department, C.L.R.P. Quantity surveyors: E. Howard & Partners. Clerk of Works: G. S. Peters and C. W. Thomas. General contractors (demolition and foundation): C. Wimpey & Co. Ltd.; (Superstructure): Trollope & Colls, Ltd. Sub-contractors: Steel frames: Boulton & Paul, Limited. R.c. work: Caxton Floors, Limited. Stone: The South Western Stone Co. Ltd. Granite: Brookes, Limited. Marble: J. Whitehead & Sons, Limited. Asphalt: Faldo Asphalte Co. Ltd. Lifts: Otis Elevator Co. Ltd. Wood blocks: Vigers Bros. Glass infill: Plyglass, Limited. Plaster infill: The Unit Construction Co. Ltd. Lightning conductor: J. W. Gray. Heating and ventilation: Rosser & Russell, Limited. Electrical work: The Berkeley Electrical Engineering Co. Ltd. Plumbing: Ellis (Kensington), Limited. Sanitary fittings: W. N. Froy & Sons, Limited. Terrazzo, internal and external: Alan Milne, Limited. Artificial stone: Copper Wettren & Co. Ltd. Metal staircases, balustrades and metal handrails: S. W. Farmer & Son, Limited. Paints (emulsion): H. E. Gaze; (Gloss): I.C.I. Astrapole wall finishes: Roffe, Limited.

Announcement

R. Seifert, F.R.I.B.A., has taken into partnership H. G. Marsh, A.R.I.B.A., and A. G. Henderson, A.R.I.B.A. The title of the firm will be R. Seifert & Partners, practising at 28, Great Ormond Street, W.C.1.

Designer: NOEL VILLENEUVE



A standard fitting for vertical lamping in three sizes, for 100, 200 or 300 watts.

**ALLOM
HEFFER**

AND COMPANY LIMITED, 17 MONTPELIER STREET, KNIGHTSBRIDGE, LONDON S.W.7 · TELEPHONE: KNIGHTSBRIDGE 6897-8



There is a Weatherfoil System for any type of building.

EVERY WEATHERFOIL SYSTEM — a Model Installation

Designed exclusively for your project . . . planned to suit your programme . . .
priced to your budget . . . engineered to produce a discreet, effective installation.

ACKNOWLEDGMENTS:

L.C.C. Brandon Estate, Southwark. Hubert Bennett, F.R.I.B.A., Architect to the Council.


British Railways, Great Eastern House, Cambridge. H. H. Powell, B.Arch., F.R.I.B.A., Regional Architect (Eastern Region) British Railways.

Monsanto Chemicals Limited. Oil additives engine test laboratories, Newport.

St. Aldens Church, Speke, Liverpool. Architect: Bernard A. Miller, B.Arch. F.R.I.B.A.

Office Building, Slough. Architect: Richard Sheppard & Partners.

WEATHERFOIL HEATING SYSTEMS LIMITED
19 Berkeley Street, London, W.1. Tel. GROsvenor 5146 • 185 Bath Road, Slough, Buckinghamshire • Broadgate House, Coventry, Warwickshire



"To a chap like me –
and I'm proud of my work – my pencil's
my living.
The pencils I use have to stand up to fast
hard work, their grading's got to
be absolutely spot on – not almost
or nearly but bang on the dot every
time.
The leads must hold their points
and flow smoothly throughout a long line –
no crumbling or 'clinkers' mark you! –
and if I erase a line it must go cleanly –
there's no 'furrow' left in my paper
so you won't find ghost lines in prints
made off my drawings. As a matter of
fact you can tell from a print when it is
my drawing – the print's always first class."

"What pencils do I use?"

"Venus drawing pencils of course, the
ones with the crackle finish! – how else do
you think I keep up my high standard?"

V
ENUS
DRAWING
PENCILS

*VENUS Drawing pencils are made in 17 accurate
grades from 9H to 6B.

THE VENUS PENCIL CO., LTD., LOWER CLAPTON RD. LONDON, E.S.

ELLARD

SLIDING DOOR GEAR


ESTATE FOR THE HOUSE



The illustration on left shows yet another example of ELLARD "Estate" Sliding Door Gear in the modern dwelling-house. See how simple it is to convert a spacious room to one of cosy and intimate atmosphere. Elegant appearance, ease of operation and long service are the main selling features of this attractive ELLARD Door Gear. The obvious choice for both council estates and private houses is ELLARD Door Gear.

FOR THE RADIAL GARAGE

The illustration on right shows ELLARD "Radial" Sliding Door fitted to a private garage. Valuable working space is offered at the entrance to the garage. ELLARD Door Gear provides easy access to and from the garage by a personal entry door. ELLARD "Radial" Sliding Door Gear is low in price and gives long service without maintenance. This gear is also suitable for the larger openings of commercial and industrial garages.



OVERDOR FOR THE GARAGE



ELLARD "Overdor" Gear, illustrated on left, represents the best method of operating an overhead-type door, and it requires the minimum space, fixing time and maintenance. An entirely clear threshold is achieved, and both side walls are available for windows and shelves. ELLARD "Overdor" Gear is designed for doors from 6ft. to 7ft. 3in. high and up to 200lbs in weight. The door is safely balanced and can be opened and closed with ease.

Fully descriptive literature will be gladly sent on request.

ELLARD SLIDING DOOR GEARS LTD.
(DESK 6) WORKS ROAD, LETCHWOTH, HERTS.

Tel. 613/4
BMJ


BRICKS AND DOMESTIC ARCHITECTURE

FLETTONS AND FOUNDATIONS

BELOW D.P.C.

In this country where frost rarely penetrates more than a few inches below ground and subsoil moisture conditions remain comparatively uniform the use of 'Phorpres' Flettons for footings is long established practice. Although bricks in footings may be wet they are not subjected to long spells of frost.

Whilst calcium sulphate and magnesium sulphate are present in some soils and other soils are naturally slightly acid, these salts and acids have no effect whatsoever on properly burnt clay bricks. They can and do attack Portland Cement and some limes used in mortar and concrete. For this reason it is good practice in heavily contaminated soils to use sulphate resisting cement to avoid disruption of the mortar.



'Phorpres' Flettons being laid in foundations of the Birmingham Corporation Housing Development at Laurel Road, Handsworth, Birmingham

BETWEEN D.P.C. AND GROUND LEVEL

Practical experience has shown that 'Phorpres' Flettons are entirely suitable for use between D.P.C. and ground level.

Although conditions might in theory seem more severe the building above D.P.C. undoubtedly affords some protection and the conditions obtaining are hardly those of 'extreme exposure' as defined by the Building Research Station.

No case of failure has ever been reported and 'Phorpres' Flettons are specified for foundations by many leading architects and over 400 principal authorities engaged in domestic architecture.



LONDON BRICK COMPANY LIMITED

*in the service of the
building industry*

Head Office: Africa House, Kingsway, London, W.C.2. Telephone: Holborn 8282
Midland District Office: Prudential Buildings, St. Philip's Place, Birmingham 3. Telephone: Central 4141
South-Western District Office: 11 Orchard Street, Bristol 1. Telephone: Bristol 23004/5
Northern District Office: St. Paul's House, 20-22 St. Paul's Street, Leeds. Telephone: Leeds 20771



BY APPOINTMENT
TO HER MAJESTY
QUEEN ELIZABETH II
BRICK MAKERS

PHORPRES

“Window Gazing” at Modern Glazing?



Look first at

QUICKTHO


FAMED for faultless action and perfect ventilation **QUICKTHO** windows are made in an extensive range of designs adaptable to most requirements.

TOP HUNG VENTILATORS
in high corrosion resisting aluminium alloy, sizes to suit apertures up to 7' wide. Factory glazed for direct mounting into timber sub-frames.

HORIZONTAL SLIDING WINDOWS
in high corrosion resisting aluminium alloy to dimensions up to 4' in height by 11' wide or equivalent area—factory glazed and ready for direct mounting into timber sub-frames.

The Quicktho Technical Department is always at your service.

**QUICKTHO ENGINEERING LTD., POINT PLEASANT
WANDSWORTH, LONDON, S.W.18.**
Tel: VANDyke 4115/6 Telegrams: Quicktho, PUT., London



AN EXAMPLE
Suite of offices
constructed from Medino
Partitioning — photo
by permission of INSTITUTE OF
LONDON UNDERWRITERS;
Architect: George Poles, F.R.I.B.A.

MEDINO

for complete
adaptability

- * efficient insulation
- * soundproofing
- * rigidity
- * attractive appearance


specify

full details from
SARO LAMINATED WOOD PRODUCTS LTD.
EAST COWES, ISLE OF WIGHT
TEL COWES 704-8

REPRESENTATIVES AND ERECTORS:	GREATER LONDON William Verry Ltd., 11 Hart Street, LONDON, E.C.3	S.E. ENGLAND & LONDON Firmin & Collins Ltd., Dover Road, Northfleet, KENT	MIDLANDS T. Elvins & Sons Ltd., Naden Works, Soho Hill, BIRMINGHAM 19	NORTHERN ENGLAND Thomas Scott & Co., (Manchester) Ltd., Knowsley St., MANCHESTER 8	SCOTLAND Andrew Bennie & Sons, 100 Barrowfield Street, GLASGOW, S.E.
--	--	---	---	--	--

ONE ORDER, ONE PRICE, ONE DELIVERY—

ONE 'POTTERTON' OIL-FIRED BOILER



Each 'Potterton' Oil-fired Boiler is supplied as *one* complete packaged unit. The unit is delivered in *one* consignment—right down to the last nut! Only *one* company is responsible for its overall efficiency. Boiler, burner and controls are a matched, tested and proven combination. There are no extras to buy.

Because of its high efficiency and accurate controls, the 'Potterton' Oil-fired Boiler is surprisingly economical to run. It is designed specifically for oil, and utilises the maximum heat from the fuel. Its thermal efficiency of 80% is close to the theoretical maximum. More important still, every 'Potterton' Boiler continues to maintain this efficiency for long periods. In this way there is a saving of one gallon of oil out of every five that would be consumed by a converted solid fuel boiler—an important point to bear in mind when you are specifying a boiler.

The consequent low running costs, the facilities for speedy maintenance, the ease of erection and installation can be demonstrated to you. If you would like such a demonstration, please do not hesitate to write for further details to the address below.

Another good reason for specifying


'POTTERTON' BOILERS *Oil-fired or Gas-fired*

the Key to comfort



POTTERTON DIVISION, Thomas De La Rue & Co. Ltd.,
20/30 Buckhold Road, London S.W.18.

DL810/1



coming shortly: the third, revised and enlarged edition of

NEW WAYS OF BUILDING

edited by ERIC DE MARÉ Ariba; contributors:

DR. K. HAJNAL-KÓNYI and H. TOTTENHAM on *concrete*

DR. H. GOTTFELDT on *steel*

PHILLIP O. REECE on *timber*

K. CHEESMAN on *glass*

W. B. MCKAY on *brickwork*

BRIAN GRANT on *light metals and plastics*

C. C. HANDISYDE on *insulation*

THIS, THE THIRD EDITION of a book already well known to practising architects and architectural and building students, has been very extensively and thoroughly revised. The chief revisions include the following: many new technical developments in the use of *Concrete* are discussed; the chapter on *Steel* has been almost entirely re-written by a new member of the team of specialist authors; considerable changes and additions have been made to the chapter on *Glass*, notably concerned with that important new application—the curtain wall; a valuable new section on designed load-bearing walls has been added to the *Brickwork* chapter; *Light Metals* has been almost entirely re-written. In addition to these extensive textual revisions, approximately half the illustrations are new: as in previous editions the new illustrations have been carefully chosen to stimulate the designer's visual imagination, as well as to inform on recent technical developments.

Size 10 ins. by 7½ ins. 264 pages, over 240 photographs, plans and drawings. 45s. net, postage 1s. 9d.


THE ARCHITECTURAL PRESS

9-13 Queen Anne's Gate, Westminster SW1

Beacon
REGISTERED TRADE MARK

front adjustable

roller catch



**the catch that's...
Caught On!**

Popular with householders and builders alike, because it is efficient in operation, yet neat and unobtrusive in appearance. Tension of catch easily adjusted after fitting with small screwdriver through hole in centre of roller.

Zinc diecast construction and finished Florentine Bronzed or Bright, Lacquered. Faceplate dimensions 2¼" x ¾".

SMITH and DAVIS LTD.


LONDON OFFICE: 61/62, BROAD STREET AVE., BLOMFIELD ST., E.C.2.
Tel: LONDON WALL 2181

1, Beacon Works
WEDNESBURY

Tel: Wednesbury 0721-5

Friar Park Road,
STAFFORDSHIRE

'Grams: "Beaconite" Wednesbury.



COULD THIS *
BE YOUR
ANSWER ?

Photograph by courtesy of the Westminster Medical School.


* For one reason or another, tomorrow may find you face to face with a complex building problem demanding an urgent solution . . . or funds will not permit the expense of a traditional brick structure. Whichever it is, YOU are expected to find a speedy, efficient, yet simple answer.

Just such an answer is provided by THORNS TIMBER-FRAMED BUILDINGS. Prefabricated in BASIC units, they combine economy with ease of erection—and are easily adaptable to your own design. The photograph shows a Sports Pavilion at Cobham, Surrey, consisting of two units 48ft. by 25ft. and 40ft. by 25ft. Basic widths available—12ft., 15ft., 18ft., 20ft., 24ft., 25ft., 30ft.

get ^{your} quotation from **THORNS**

J. THORN & SONS LTD. (Dept. 188) BRAMPTON ROAD, BEXLEYHEATH, KENT

BD960A



Part of a large Warehouse for the Air Ministry for which we supplied all the steelwork

LATTICE BEAMS

BEAMS OF RIVETED AND WELDED CONSTRUCTION

Enterprising Architects continue to specify our Standard Beam System for modern Schools, Factories, Canteens etc. It is most economical and allows complete freedom of design.

Our Structural Design Office are pleased to advise and quote for THE COMPLETE STEELWORK OF ANY PROJECT. Please write for full details and data sheets.

ECONOMY

RIGIDITY

PROMPT DELIVERY

SOMMERFELDS LTD.

Head Office WELLINGTON SHROPSHIRE ENGLAND Tel: Wellington 1000
London Office 167 VICTORIA STREET LONDON S.W.1. Tel: VIC. 8843 and 1000


Put the sun into your ceilings

Step outside into sunshine from a normally heated room, you feel more comfortable don't you? That is because sun heat is RADIANT heat. Radiant heat and a low air temperature keep the body warm naturally, comfortably. Other types of heating systems can't do this, STRAMAX Radiant heating CAN.



STRAMAX


HEATING · SOUND ABSORPTION · COOLING



A Stramax system in the ceiling keeps the room surfaces warmer than the enclosed air—the ideal conditions for health and comfort. Stramax radiant heating scores from the design angle too. It's independent of the main building structure—doesn't need to be 'embedded'. Ceiling heating leaves the floor and walls entirely free from ugly pipes and heaters and it's suitable for any size of room. STRAMAX Radiant heating is easy on fuel as well, it warms up quickly, and is easier to control thermostatically.

STRAMAX CEILINGS (G.B.) LIMITED
19 REA STREET SOUTH, BIRMINGHAM 5
Telephone: MIDland 4674
Telegrams: STRAMAX BIRMINGHAM 5

This is no BULL!



Uni-Bond

Bonds anything to anything

TRIED TESTED PROVED AND SPECIFIED BY LEADING ARCHITECTS CONTRACTORS AND GOVERNMENT AUTHORITIES.

NOW IN ITS FIFTH YEAR ON THE MARKET

Ample supplies of Uni-bond are available. It grips and holds two surfaces together—for good. There are a 1,001 uses for Uni-bond on building sites, in factories, offices, stores and around the home . . . inside and out.

- ★ Ready for use. No mixing—no heating.
- ★ Dries clear. No mess—no waste!
- ★ Waterproof, weatherproof, mouldproof.
- ★ Resists petrol and oil—is non-brittle.
- ★ Does not crack, craze or deteriorate.
- ★ Backed by money-back GUARANTEE.

For the PLASTERER—Bonding Plaster. Will bond plaster without keying to existing smooth plaster, cement, painted surfaces, timber, painted anaglypta walls and ceilings, hardboard, glazed tiled surfaces—and each to one another. In fact any surface.

For the CEMENT WORKER, CONCRETOR, BRICKLAYER, CEMENT BONDINGS. Will bond cement mixes to Plaster, Asbestos, Old Cement, Timber, Steel, Hardboard, Chipboard, Bricks, Quarry Tiles, Glazed Tiles, Slates, Flags, in fact any surface. A masterpiece for screeding.

For the FLOORING TRADE, TILE or BLOCK LAYER or IN-SITU LAYER. Unsurpassed for the fixing of all wood blocks, lino or rubber, plastic tiles, and making plastic levelling screeds that will lay from paper thickness up to 2in. over any base. For fixing without keying all types of composition floorings, such as Magnesite etc. A lasting floor seal against dusting surface.

For the CARPENTER and JOINER—Bonding Timber. For joinery use, it being possible to make grain end bonds that are almost impossible to break. Fixing pelmets, shelves, pads, etc.

The GLAZE TILER. A Uni-Bond cement/sand slurry will fix a tile for keeps, no bedding required. Tile over any level surface plaster, hardboard, painted surfaces, existing glazed tiles.


For PAINTER and DECORATOR—MAKING PLASTIC PAINT, FILLERS, PRIMERS. For priming timber, asbestos and all surfaces with suction. Sealing off efflorescence on plaster and brickwork. Making a permanent stopping. Making a Plastic paint from cheap distempers.

FOR WORKING INSTRUCTIONS
Cut out this slip—attach to your trade-card or letter-head—and post to us today.

Write for address of your nearest stockist.

THE LIQUITILE SUPPLY CO.
48 HIGH STREET, CAMBERLEY 7, SURREY

Telephone: CAMberley 2263



YOU COULD MARCH AN ARMY ACROSS THIS FLOOR

The vinyl-plastic flooring that laughs at heavy traffic

This modern flooring material is supremely easy to lay and once laid virtually never wears out. It can be supplied in rolls for welding into an integrated, continuous surface with no cracks to harbour dirt or it can be supplied as tiles.

Phenco is resistant to fire and proof against spilt liquids, including hot

fats, oils and spirits. It is so easy to clean and the range of over thirty different colours and patterns enables any colour scheme to be matched. Write now for free descriptive literature.

Also supplied: P.V.C. Stair Nosing and Coving (can be welded to Phenco to form jointless surface). Phenfoam insulating material.

PHENCO

Vinyl-plastic Flooring

PHOENIX RUBBER CO. LTD.

91, BISHOPSGATE, LONDON E.C.2

Phone: London Wall 3564 & 1622

Manchester Office: 472 Royal Exchange Buildings, Manchester 2.

There is a Growing Need for the **FINEST WOOD CHIPBOARD**

most people will find the Answer with

BRITISH PLIMBER



BRITISH PLIMBER LIMITED, Dovers Corner, New Road, Rainham, Essex. Tel. Rainham 5500



Enjoying the fruits!

After years of the daily perusal of various financial columns, you may conclude, without much fear of contradiction, that "nothing succeeds like success". It seems logical, therefore, to ally yourself to organizations which have attained such an enviable reputation. Thus you too can enjoy a share of the fruits of success.


This is one very sound reason for insuring with the Legal & General.

But in addition to being one of the oldest and most successful assurance companies in the Commonwealth, it also prides itself on having never lost the personal touch. For anything insurable, from your wife's engagement ring to a pension scheme for the largest of firms, the Legal & General will be glad to help you.

LEGAL & GENERAL

ASSURANCE SOCIETY LIMITED

CHIEF ADMINISTRATION: 188 FLEET STREET, LONDON, E.C.4.
TELEPHONE: CHANCERY 4444



There's rosemary,
that's for
remembrance.

SHAKESPEARE



and ROSEMARY CLAY ROOF TILES


The name "Rosemary" is one that springs to mind whenever roof tiles are needed. Year in, year out, this old-established brand of roof tile is specified by the same architects and ordered by the same merchants and builders regularly. The reason is—super quality, coupled with the range of lovely fadeless colours in which these tiles are made. The next time you require roof tiles, remember to ask for "Rosemary" Clay Roof Tiles. Write for our illustrated brochure "Colour in the Roof."

Manufactured by
G. W. LEWIS' TILERIES LTD., STOCKINGFORD, NUNEATON

Phone: NUNEATON 3125

In association with THE HAUNCHWOOD BRICK & TILE CO., LTD., NUNEATON

PHONE: NUNEATON 3419 & 3410



Haywards Wallpaper No. 1077. Drawing by Audrey Levy.


A SERVICE FOR ARCHITECTS

ARCHITECTS CONCERNED
WITH THE SPECIFICATION OR DIRECTION
OF DECORATIVE SCHEMES
ARE INVITED TO USE THE FACILITIES
OFFERED BY OUR
ARCHITECTS' DEPARTMENT

Though the primary purpose of
the ARCHITECTS' DEPARTMENT is to give
advice on the use of wallpaper it is also able to deal with
enquiries concerning the
use and choice of paints and fabrics.



THE ARCHITECTS' DEPARTMENT
THE WALL PAPER MANUFACTURERS LIMITED
125 HIGH HOLBORN LONDON WC1
OR KING'S HOUSE KING STREET WEST
MANCHESTER 3



Where is Newcastle anyway?

Far and frozen North old boy.
Up above the timber line. Savages.
Live in holes in the ground.

Seems funny . . . all this glass . . .

Can't sell it at home. No place for it.
Got to come South to civilization
to find a market. That's why it's got
to be so damn good.

Wonder what this chap Millican's like?

Never seen him. Wears skins most
likely. Paints himself with woad.
Probably where he got the idea for this
"exclusive Reed Millican* colour
process." Descended from
the border raiders no doubt.

— and true to type!



.. ARTISTRY IN



GLASS





THE WONDER BAKERY, NEWCASTLE-ON-TYNE

Mellor Bromley

HEATING, VENTILATING AND AIR CONDITIONING
ENGINEERS AND CONTRACTORS

THE PERCIVAL WHITLEY COLLEGE OF FURTHER EDUCATION. Architect: Mr. Richard Pickles. A.R.I.B.A., Halifax



WOOL INDUSTRIES RESEARCH ASSOCIATION, TORRIDON, LEEDS
Consultants: Messrs. Rosser & Russell, Leeds

MELLOR BROMLEY (AIR CONDITIONING) LTD., BARKBY ROAD, LEICESTER (Member of the Bentley Group)

Telephone Leicester 66651 AC 28


above all for complete adaptability

The patent SLYDA-LONG Lighting system provides for flexible lighting installation. Trunking is supplied in 12' 6" lengths complete with wiring clips at 12" intervals and 3-way 15 amp. Mains Connectors at 6' 0" intervals. Lighting Units may be removed or added to alter lighting layout without disturbing the mains wiring.

Write for new catalogue No. 1062

SLYDA-LONG TRUNKING

A typical illustration of 3,000 lampways of Thorlux high quality vitreous enamelled trough reflectors on SLYDA-LONG Trunking.




INDUSTRIAL LIGHTING EQUIPMENT

THORLUX

REGD. THROWS LIGHT ON INDUSTRY

Manufactured by
F. W. THORPE LIMITED
Welby Road, Hall Green,
Birmingham, 28
Springfield 3318-19-10
Grams: THORLUX B'ham






An Important Amenity

Friction between employees and confusion at going-home time may be avoided by providing separate receptacles for clothes and personal belongings. Such provision is also important in the interest of hygiene. 'Harco' Clothes Lockers provide the answer. They are made in sheet metal or wirework, in nests of up to five in one unit, with short or full-length compartments as required. Steel lockers are fitted with six-lever locks which can differ up to 1,600; wirework lockers carry hasps and fasteners for padlocks. Height of both types is 72in.

'HARCO' CLOTHES LOCKERS

IN WIREWORK OR SHEET METAL

Please ask for Lists Nos. AJ 960 and AJ 1009



Harvey

G. A. HARVEY & CO. (LONDON) LTD.
Woolwich Road, London, S.E.7 GREENWICH 3232 (22 lines)



THE TWIN ENEMIES OF CHAIN LINK

FENCING DEFEATED BY

PLASTELLA

THE GALVANISED CHAIN
LINK FENCING
with the **PLASTIC COATING**


- ★ Plastic coating gives greater protection against atmospheric corrosion and rust—that's the great advantage of Plastella. Available in green, yellow and black.

Write for further details to :

FLEXTELLA

FENCING & ENGINEERING LTD
PETERSFIELD . HAMPSHIRE

TYPE SIX



OFFICES
HOSTELS
LIBRARIES
CANTEENS
PAVILIONS
CLASSROOMS
VILLAGE HALLS

PREFABRICATED TIMBER BUILDINGS

VIC HALLAM LTD.

Phone 2301(7 Lines) LANGLEY MILL, NOTTINGHAM

A Good Example of "TUBECLAMP" Composite Construction

When you require a Tubular Steel Framed building to suit specific and irregular measurements, consult our Drawing Office service.

WE DESIGN
WE MANUFACTURE
WE ERECT

Tubeclamps
Limited

TUBECLAMP CONSTRUCTION



Cask Washing Shed by courtesy of Messrs. Ushers, Wiltshire Brewery Ltd.
Architect to the Company, Arthur G. Wright, F.R.I.B.A.


TUBULAR & STRUCTURAL ENGINEERS

6 LYGON PLACE, LONDON, S.W.1

Telephone: SLOANE 1698

ST. LUKES WORKS • OLD HILL • STAFFORDSHIRE

Telephone: Cradley Heath 69181 (P.B.X.)




**IF IT ISN'T ONE PROBLEM,
IT'S ANOTHER!**

... and another, and another. Wherever, and whatever, buildings are being erected or modified or converted, some problem of protection will arise.

It may be protection from damp or even x-rays, but it doesn't matter, because when you discuss it with R.I.W. it ceases to be a problem!

The R.I.W. range includes protective and decorative materials for the protection and preservation of all types of surfaces against a wide variety of destructive agencies. These products have been consistently specified by architects and engineers for many, many years.

R.I.W. Protective Products can be supplied direct or through your nearest builders' merchant. The Sales and Technical Department will be pleased to send you fully detailed technical literature on all R.I.W. products.



**R.I.W. PROTECTIVE
PRODUCTS**

R.I.W. PROTECTIVE PRODUCTS CO. LTD.
325 WHITEHORSE ROAD, CROYDON SURREY
TELEPHONE: THORNTON HEATH 6121

See the latest developments in

HEATING AND VENTILATION

at the Sixth

Factory Equipment

Heating, Ventilation & Thermal Insulation

Exhibition



EARLS COURT - LONDON

APRIL 14-19

10 a.m. - 7 p.m. (Saturday 5 p.m.) Admission 2/6d

**Thousands of
interesting exhibits**

**ADMISSION TICKETS FOR READERS
OF THIS JOURNAL**

*Fill in this coupon or send us your
letter-heading*


To The Organiser, Factory Equipment Exhibitions Ltd., Dept. 33,
4, Snow Hill, London, E.C.1. Please send me free of charge.....
admission tickets and brochure of the Sixth Factory Equipment,
Heating, Ventilation & Thermal Insulation Exhibition.

NAME

ADDRESS

Sponsored by "Factory Equipment News" and "The Factory Manager"

The Problem of Channels and their Gratings



tackled with down to earth efficiency

Channels and Fittings complete with Gratings and Frames detailed and selected to suit lay-out.

Assembled at one source and delivered ready for installation

Detailed Layout Drawings submitted to suit requirements

Illustrated Brochures sent on request

BROADs

4, SOUTH WHARF, PADDINGTON, W.
Tel: PADDINGTON 7061 (20 LINES)



The Navy's gone all modern! As a tribute to Alf, they have changed the brass to copper and have made him Honorary Admiral of the Copper Joint, piping him aboard with the honours due to a plumber who can fix the bo'sun's pipe, the stoker's tubes, and the commander's choleric temper in two minutes flat. He needs just a 'Securex' joint, a spanner, and the special tool to make your plumbing as ship-shape as today's Navy.

And 'Securex' saves you pounds. Well, maybe we should qualify this — it will make so much profit that you can boast that your super-tax maintains the Senior Service!

Send for details of the compression joint made to make profit for you.

SECUREX
SOLDERLESS COMPRESSION
JOINTS

JAMES H. LAMONT & CO. LTD.
ENGINEERS — BRASSFOUNDERS

GYLEMUIR WORKS, CORSTORPHINE, EDINBURGH 12, SCOTLAND
Telephone: Corstorphine 2241/2 Telegrams: "Solderless, Edinburgh"

LONDON OFFICE: NORFOLK HOUSE, LAURENCE POUNTNEY HILL, E.C.4
Telephone: Mansion House 5700 Telegrams: "Yutaka Cannon, London"

This attractive facade incorporates "Standard" Patent Glazing with lead-clothed steel glazing bars. The continuous horizontal features are of extruded aluminium.

SPARTAN STEEL & ALLOYS LTD.,
BIRMINGHAM.

ARCHITECTS :
LEONARD J. MULTON
& PARTNERS.

"Light" Construction

THE STANDARD PATENT GLAZING CO. LTD


WORKS: DEWSBURY

Phone 1213-4

LONDON OFFICE

Phone: HOUnslow 3079

Branches at BIRMINGHAM and BRISTOL



DOORS NEED NOT S-L-A-M

—specify



ALSO

- WINDOW GEARING AND FANLIGHT OPENERS
- 'X-IT' PANIC BOLTS
- LOCKS
- DOOR FURNITURE
- CASEMENT FITTINGS
- SPRING SASH BALANCES

"VICTOR" fittings are specified by all leading Architects.

ROBERT ADAMS (VICTOR) LTD

139 STAINES ROAD, HOUNSLOW, MIDDX

Telephone: Hounslow 5714

An essential fitting with self-contained check for Public Buildings, Housing Schemes, Office Blocks, etc. In shallow and watertight floor patterns. Overhead types to suit every purpose.

FOUNTAIN HOUSE

FENCHURCH STREET

Architect: W. S. Rogers, A.R.I.B.A.

Hollow Tile and
Reinforced Concrete Floors,
Structural Staircase construction and
Stanchion casing
designed and executed by

CAXTON FLOORS LIMITED

45 Bedford Row,

W. C. 1.

Tele: CHAncery 7322

WATERPROOFED INSIDE & OUT

The Dussek range of waterproofing materials offers complete protection from rooftops to foundations. Whatever the need - Dussek have the answer.

BITROL & BITITE 752/18

Bitumen solutions in liquid and plastic consistencies for the protection of metal and for waterproofing roofs of all types, jointing gutters, corrugated sheets etc.

PLASPHALT

Fibre - reinforced plastic bitumen emulsion. Applied cold from the drum by trowel or float to tiles - zinc, concrete. Can also be mixed with cement, sand and other aggregates for jointless flooring etc.

LACOL

- Rubber-Bitumen Emulsion in two grades for flooring - 1290, the positive fixing compound for wood blocks to concrete, and 1281 the sealing membrane between layers of concrete. Also for waterproofing roofs, walls etc.

PLASBESTOS

- a thixotropic bitumen emulsion for waterproofing roofs, walls and floors, for sound deadening, for jointless flooring etc.

DUSSEK

DUSSEK BITUMEN & TAROLEUM LTD.
Empress Wharf, Bromley-by-Bow, E. 3

Tel: ADVance 4127. Grams: TRINIDITE, Bochurch, London

Warrington: Loushers Lane, Wilderspool, Glasgow: Barrhead South Goods Station. Associated Companies and Agents in Australia, Belgium, British East Africa, Denmark, Malta G. C., New Zealand, Norway, Sweden, and West Africa

dm DB 233

Around every Corner

BLAKEY PATENT *Galvanized* METAL ANGLE BEAD


This galvanised Metal Angle Bead protects external angles against accidental damage and provides a neat arris.

Economical and time saving, it will not shrink, corrode or chip.

Full details on application to the manufacturers.

Over 10,000 miles have been fixed in Housing Estates, Factories and Hospitals. In fact, Blakey Metal Angle Bead can be found around almost any corner in Great Britain.

BLAKEY CABINET & METAL WORKS LTD.
61, SCOTLAND ROAD, NELSON, LANCs.



CONCRETE SECURITY FENCING

• HEIGHTS UP TO 8 FEET PLUS
OPTIONAL EXTENSIONS FOR
BARBED WIRE

• NO MAINTENANCE—PALES
REPLACEABLE IF DAMAGED

• GOOD APPEARANCE—AVAILABLE
IN COLOUR

• FENCE FOLLOWS GROUND
CONTOUR WITHOUT STEPPING
POSTS & PALES REMAIN VERTICAL

• PATENTED PALE FIXING FOR
GREATER SECURITY AND
SIMPLE REPLACEMENT

By Courtesy B.S.A. Co. Ltd

COMPLETE ERECTION SERVICE

FOR FRAMES UP TO 60' SPAN, COMPLETE SERVICE ERECTION SITE WORKS ETC. SECTIONAL BUILDINGS UP TO 25' SPAN
CONCRETE FENCING, PALISADE, PANEL, POST AND RAIL, ALL WITH VARIOUS FINISHES

WRITE FOR BROCHURES

BELL & WEBSTER LTD HODDESDON HERTS

PHONE HODDESDON 3737 • 4 LINES



QVOD ERAT DEMONSTRANDVM

This country's most valuable treasures and records, housed in the Tate Gallery, The National Gallery, The Victoria and Albert Museum, Somerset House, etc., are all protected against fire by installation of Dreadnought Fireproof Doors. What is more logical than that factories, warehouses, public buildings and office blocks should give similar efficient protection to personnel and stocks? Dreadnought Fireproof Doors are of course approved by the F.O.C. and L.C.C.

DREADNOUGHT

Fireproof Doors

DREADNOUGHT FIREPROOF DOORS (1930) LTD., 26 VICTORIA STREET, WESTMINSTER, S.W.1



durability

A building is expected to last a long time. The materials of which it is built have to resist many different influences during its life and these are so complex that their *combined* effects cannot be measured in the laboratory—only experience can prove durability. Lean cement mortars with air bubbles entrained by chemical plasticisers may have good resistance to frost, but their durability in relation to the combination of the many other agencies—some of which are listed in the British Standard Code of Practice on Durability of Buildings (C.P.3—Chapter IX)—is still unknown. LIME-Sand mixes gauged with cement used in accordance with established practice are well known by experience to have adequate resistance to all the various causes of deterioration which may affect buildings. *The correct mix can be chosen to give satisfactory durability for all practical conditions.*

THERE IS NO ADEQUATE SUBSTITUTE FOR LIME.

THE LIMESTONE FEDERATION

Manfield House, 376-8 Strand, London, W.C.2

Tel: COVent Garden 0621

or

THE SOUTHERN LIME ASSOCIATION

Hanover House, 73-78 High Holborn, London, W.C.1

Tel: HOLborn 5434



use **LIME** tested by time


A booklet on LIME/sand mixes gauged with cement and conforming to British Standard Codes of Practice will be sent free on application to either of the above.

**LIME
MANUFACTURED
TO COMPLY WITH
B.S. 890**

**This is your safeguard
to ensure satisfaction.**

FELIX WALTER, F.R.I.B.A.

House conversion and improvement



THIS IS THE FIRST comprehensive illustrated book to be published on the subject of the conversion or improvement of properties of all kinds. It is based on the series of articles printed from time to time in the *Architect's Journal*, with the addition of a certain amount of fresh material. This book is designed to be of value to those architects concerned with the conversion of old or out-worn houses into groups of smaller units suited to present-day needs; to local housing authorities engaged in the rehabilitation of derelict urban and rural areas; and to those private owners who, for the purpose of investment or for their own occupation, are planning to turn old houses into new flats, or maisonettes, and seek the latest ideas on layout, materials and equipment.

A great many successful conversions, ranging from luxury Belgravia terrace houses to remote rural cottages, are thoroughly illustrated and described; in the majority of cases full details of building costs, rents, rates, &c., are given. Chapters written by acknowledged experts in their own fields deal in simple language with the legal aspects of conversion, mortgages, loans and grants, management, and town planning.

Size 9½in. by 7½in. 258 pages including over 420 halftone and line illustrations. 42s. net, postage 1s. 9d.

THE ARCHITECTURAL PRESS

9-13 Queen Anne's Gate Westminster S.W.1

FERROGRAN FLAGS



**EAGLE WORKS
WEDNESBURY**




TEL WED 1821 9 LINES

THE EXTRA LONG LIFE FLOORING

- MANUFACTURED IN 12" x 12" x 1 1/2" and 2" thick in RED & GREY ●
- THE TOP SURFACE HEAVILY IMPREGNATED WITH STEEL ●
- SUPPLIED ONLY, OR LAID BY SKILLED CRAFTSMEN ●

Write now for our brochure on Ferrogran Steel Faced Flags



The only plywood that has been proved for over 8 years in Service equipment. Each veneer separately impregnated with

Celcure

The wood-preserving salt with 30 years' successful experience behind it; approved by all the Ministries to Specification L/9763—CG2584A—CG2606—IEME/E/4860—IEME/E/4241B—PP/SPEC/56—DEF-7—CEA No. TC/3001/1—CA/B/12938/51 of 24/6/55—BWPA Std 100—Indian Standard 401—1954—etc. Thames-Celply can be cut or machined without fear of exposing any untreated surface. It is widely used throughout the world for ship and boat construction, farm building, road and rail bodies, all forms of outdoor construction.

Standard size 8' x 4'. "Specials" up to 30' x 9'. Also supplied with untreated MAKORE faces for decorative polished finish, MAKORE (cherry mahogany) being a species naturally resistant to insects and fungus.

wherever wood may rot — use

THAMES-CELPLY

Have you ever thought of plywood with this 100% protection in place of metal needing eternal repainting?

Available from all distributors. Samples and quotations from

THAMES PLYWOOD MANUFACTURERS LTD

HARTS LANE, BARKING, ESSEX

Telephone: RIPPleway 5511



Right from the first . . .

A job completed in METALLIC conduit is a job completed for good. METALLIC finishes ensure complete protection against corrosion, and will withstand bending without the slightest flaking. This durability, coupled with consistent accuracy, ensures easier installation and maintenance.

**they're made
to last . . .**

METALLIC

**CONDUIT TUBES
& FITTINGS**



THE METALLIC SEAMLESS TUBE CO. LTD., LUDGATE HILL, BIRMINGHAM 3
ALSO AT LONDON, NEWCASTLE-ON-TYNE, LEEDS, SWANSEA & GLASGOW

A Flexible P.V.C. TILE FREE FROM RUBBER

As laid at the British-American Tobacco Co., Ltd., in Liverpool.

Fibrolene floor tiles can be laid on concrete or timber. Sizes 12" x 12" and 9" x 9". Thickness 3/32". Available in a range of seventeen colours. Delivery two to three weeks.

High resistance to acids, alkalis, oils and greases. Hard wearing, warm to the tread, fadeless, resilient, non-absorbent.

FOR HOSPITALS	KITCHENS
LABORATORIES	BATHROOMS
CAR SHOWROOMS	OFFICES

FIBROLENE

FLOOR TILES



Section of the 70,000 square feet of Fibrolene flooring laid at the premises of the British-American Tobacco Co., Ltd. in Liverpool.

FIBROLENE, HARTFORD MILL, WESTON STREET, BOLTON, LANCs. PHONE: BOLTON 5000



STRENGTH IN TIMBER

BOWSTRING

LAMINATED TIMBER ROOF TRUSSES

Pre-formed on modern scientific principles, immensely strong, quickly erected, the 'Bowstring' Roof Truss has set a new standard. Erected complete, or delivered to site ready for erection.

Write for full details.

DELIVERY THREE TO SIX WEEKS!

WILLIAM KAY (BOLTON) LTD


BARK STREET, BOLTON, LANCASHIRE

TEL: BOLTON 3925/6

CW2342/116

WRITE
FOR
BROCHURE

The glasshouse of the century



Growing gladioli for Leeds —

and lots of other things for Kew Gardens; Brighton; Fisons; The L.C.C.; The John Innes Horticultural Research Institute; Glasshouse Crops Research Institute; the Ministry of Agriculture, Fisheries & Food; Manchester University; growing things all over the world. At home and abroad the Hartley is the world's most chosen glasshouse.

Features: Maximum light-patent putty-less glazing—surrounded in P.V.C. Extrusion—unrestricted growing and working space. Built in Aluminium Alloy.


**HARTLEY
GLASSHOUSES**

Full details of The Hartley "27" and other glasshouses on request
V. & N. HARTLEY LTD • GREENFIELD • Nr. OLDHAM • LANCs

Telephone: Saddleworth 444

MARRYAT-SCOTT

REVISED Lift Planning Rule
now available FREE
to Architects.




LIFTS

The new revised edition of the Marryat-Scott Lift Planning Rule first published in 1936, incorporates the new British Standard and International Standard dimensions. Information is given on every type of lift including Hospital Lifts, Goods Lifts and Service Lifts.

Hatton Garden, London, E.C.1. Telephone: HOLborn 8181

Established in 1860
MARRYAT & SCOTT LTD
THE LIFT MANUFACTURERS
Wellington, Works • Hounslow • Middlesex

Telegrams: MARRYAT LONDON. Telephone: HOUNSLOW 6284. Branches at—LIVERPOOL • MANCHESTER • BIRMINGHAM
LEEDS • BRIGHTON • BRISTOL • GLASGOW • EDINBURGH • DUNDEE • DUBLIN and OVERSEAS



just published

The Design and Practice of Joinery

by John Eastwick-Field, B.A.ARCH.(HONS), A.R.I.B.A. and John Stillman, DIPL.LONDON, A.R.I.B.A.

Foreword by Robert H. Matthew, C.B.E., M.A., F.R.I.B.A.

THIS, THE ONLY AUTHORITATIVE, UP-TO-DATE BOOK about present-day joinery practice, is published at the recommendation of the Text and Reference Books Committee of the Royal Institute of British Architects and is intended primarily for architects, assistants and students of architecture. But, because its scope is broad and because it is concerned with the basic principles of design and practice, it will also be of great interest and value to all who are engaged in the handling and conversion of timber, including joinery manufacturers, joiners, cabinet makers, carpenters, shop fitters and other woodworkers.

The text includes chapters on the timber yard; moisture movement in timber; an analysis of construction; the design and machining of sections; and of joints; specification and practice. Among its useful appendixes are a selection of timbers suitable for joinery, set out in tabular form, a complete list of British Standard Specifications and Codes of Practice applicable to joinery, and a general bibliography. It is comprehensively illustrated: there are nearly 90 photographs and over 200 specially drawn line illustrations—more than 80 in the chapter on joints. And there is a good index.

Size 9½" by 7½". 224 pages, over 290 illustrations in halftone and line, including 200 line drawings specially drawn by Robert Maguire. Price 42s. net, postage 1s. 9d.

THE ARCHITECTURAL PRESS, 9-13 Queen Anne's Gate, London, S.W.1.

SZERELMEY
Waterproof
ENCAUSTIC

SO EASY TO APPLY.
STRAIGHT OUT OF THE
CAN ONTO THE WALL!

decorates and preserves Cement, Concrete, or any porous surface

- ★ Encaustic is a waterproof decorative material giving exterior walls a pleasing stonelike appearance.
- ★ It is available in a wide colour range.
- ★ Special Architectural Service—specified colours matched at short notice for quantities of five gallons and over.
- ★ It is inexpensive, as labour time is cut. No preparatory mixing is necessary. After stirring thoroughly it is brushed straight on to the surface.

OUR REPUTATION
Architects will be familiar with our first-class reputation for the Preservation and Restoration of many well-known buildings. Encaustic has been proved in extensive use in this work.

AN INVITATION
We will be pleased to advise on the use of Encaustic, or any waterproofing problem. Write or 'phone Szerelmey Ltd., Sorata Works, Rotherhithe New Road, London, S.E.16. Tel.: Bermondsey 3094.



SZERELMEY LTD · LONDON S.E.16
ESTABLISHED OVER 100 YEARS
SPECIALISTS IN PRESERVATION

BATLEY

BRICK-FACED CONCRETE GARAGES



A luxury garage of the most advanced design, ingeniously combining the appearance of the finest sand-faced brick exterior with the advantage of pre-cast concrete.

- * Fully portable—Easy to erect.
- * Available in multiple form, one, two or more in one block.
- * 3 years' guarantee and 5 years' free fire insurance.
- * Prices from £87. Attractive Deferred terms available.

FREE DELIVERY IN ENGLAND AND WALES.

Write for illustrated leaflet.

ERNEST BATLEY LTD., 63B, Colledge Rd., Holbrooks, Coventry. Tel. 89245/6



New German Architecture

by Gerd Hatje, Hubert Hoffmann and Karl Kaspar. *With an Introduction by Hubert Hoffmann*

The first illustrated survey of post-1945 German Architecture. The modern movement in Germany, under the leadership of Gropius, van der Rohe and Breuer, was forcibly halted in 1933; not until rebuilding began about six years ago were architects in Western Germany again free to develop a contemporary German architecture. Many of Germany's new buildings are outstanding. This book illustrates and describes 134 carefully chosen examples, Hubert Hoffmann, a former Bauhaus student, shows in his Introduction that although these present-day buildings are inevitably influenced by ideas developed elsewhere during Germany's intellectual isolation, the best of them have evolved directly from the German architecture of the modern movement in the 1920s. The building types illustrated include: houses, flats, hospitals, hotels, hostels, schools, churches, theatres and concert halls, sports buildings, department stores, offices, factories and transport buildings. Size $10\frac{1}{2} \times 7\frac{1}{2}$ ins., 256 pages with over 540 illustrations in half-tone and line. Price 56s. net, postage 1s. 9d.

The Architectural Press, 9-13 Queen Anne's Gate, London, S.W.1

THE ACME FLOORING & PAVING COMPANY (1904) LTD

ESTABLISHED 1864

River Road - Barking - Essex

THE COMPANY WILL GLADLY SEND

on request their latest

TECHNICAL BROCHURE


on IMMOVABLE-ACME HARDWOOD FLOORS for Public Buildings, Offices etc.,
and ACME PAVING for heavy duty factory floors.

Telephone :

RIPpleway 2771 (7 lines)

Telegrams:

Dowelled-Easphone-London



FOR over fifty years Libraco Ltd., have been designing and manufacturing furniture and woodwork of all descriptions for

LIBRARIES

SCHOOLS & OFFICES

The illustration shows the new Shoreditch Library, Lending Department rebuilt after bombing and furnished by Libraco Ltd.

Write for Illustrated Booklet.

LIBRACO

LOMBARD WALL, WOOLWICH ROAD,
CHARLTON, LONDON, S.E.7.
Telephone : Greenwich 3308 & 3309

Nikolaus Pevsner


The Englishness of English Art

THE 1955 REITH LECTURES, re-written to almost twice their original length, and fully annotated. With 130 illustrations in line and half-tone. $8\frac{1}{2}$ in. by $5\frac{1}{2}$ in. 208 pages. Price 16s. net, postage 1s. 4d.

THE ARCHITECTURAL PRESS, 9-13 QUEEN ANNE'S GATE, S.W.1.

Bearing surfaces are larger

BALDWIN BUTT HINGES are craftsman-made, as they have been for over a century. They are smoother in action and last longer, because the solid drilled knuckles give larger bearing surfaces and can never unwrap. The graphite content of cast iron too, provides permanent partial lubrication while helping to resist corrosion.



See name BALDWIN on every hinge. Illustrated list of full series from Sole Makers:

ARCHIBALD KENRICK & SONS LTD., WEST BROMWICH, STAFFS.



Having trouble with air?

Our experience in the design, manufacture and installation of Air Conditioning plant covers buildings of all types in many parts of the world.

If you think we can be of assistance please contact us.

Hall & Kay Ltd.

AIR CONDITIONING ENGINEERS

ASHTON-UNDER-LYNE, LANCASHIRE.

Tel. ASHTon-under-Lyne 2281/2/3.

Grams: "Hank" Ashton-under-Lyne.

LONDON OFFICE: 4, GRANVILLE GARDENS, NORBURY, S.W.16.

Tel.: POLLards 3233

FOR DRAWINGS . . LAY-OUTS . . COLOUR COPIES



With the famous
"DERWENT"
COLOUR
PENCILS

All the 72 shades are manufactured under scientific control to meet exacting requirements. Many of these shades are identical to the various B.S. specifications.

Can we help with your colour matching problems at the drawing board stage?



A PRODUCT OF
THE CUMBERLAND
PENCIL CO. LTD.

STOCKED BY ALL LEADING
DRAWING OFFICE STATIONERS

DROP A P. C. FOR SAMPLE PENCIL TO

BRITISH PENS LTD. (DEPT. A)
BEARWOOD ROAD, BIRMINGHAM 41

**CLEAR
THE AIR**
with


XPELAIR

DRAUGHT-PROOF VENTILATION

for kitchens, offices, hotels, restaurants

Write for fully illustrated leaflet AJ. to
address below:—

Xpelair Sales, 59 62 High Holborn, London, W.C.1.
Telephone: CHAncery 5474/8



Hundreds of Trades & Professions have a use for them

NESTLER SLIDE RULES

(MADE IN GERMANY)



**The ONLY Slide Rules with
ALL THESE 6 GREAT ADVANTAGES**

- Engine divided — durable — non-wearing.
- Body spring loaded against the slide.
- Colourfast — cannot change colour with age.
- Unbreakable — long life expectancy.
- Bevel of body utilised as scale—may be used for pencil or ink layout.
- New ineffaceable constant value table on plastic label inset on the reverse side assures good legibility.

STUDENT MODELS ACCURATE, EFFICIENT

The student models are slightly cheaper and splendid for all student purposes.

In case of difficulty apply:

**W. PATTERSON & CO.
LIMITED,
Beckenham, Kent.
Telephone: BECKENHAM 5023
(7 lines)**

Obtainable from Drawing Office Dealers and High Class Stationers

NESTLER MEANS PRECISION

USE...

the **NEW** Tannating Primer

PLUS-GAS

FORMULA 'E'

External Metal Treatment

SAFE • NON TOXIC • NON ACID

- ★ Prolongs the life of paint
- ★ Provides a perfect key
- ★ Removes corrosion
- ★ Easy to apply

Consultants available throughout the United Kingdom

PLUS GAS COMPANY Ltd

1/11 HAY HILL, LONDON, W.1.

Telephone: HYDE PARK 9566/9

Manufacturers of the well-known **Anti-Corrosion Fluids**:
Formula 'A' Dismantling Fluid (Rust Remover) and
Formula 'B' Protective Fluid

Edited and with 250 illustrations chosen by Edgar Kaufmann, author of The Taliesin Drawings of Frank Lloyd Wright

AN AMERICAN ARCHITECTURE

by FRANK LLOYD WRIGHT

THIS BOOK IS A BRILLIANTLY EDITED SELECTION from the writings and speeches made by Frank Lloyd Wright throughout his sixty years as a practising architect. Mr. Wright, now universally acknowledged to be one of the greatest innovators and most influential teachers in twentieth-century architecture, has built houses, skyscrapers, industrial plants, housing projects, hotels, theatres, schools and churches. However greatly these works differ from each other, however unique in beauty and originality each may be, they have all grown naturally out of certain basic principles, summed up in the now world-famous phrase of the master himself—'organic architecture'. It is the chief purpose of this book to distil from Mr. Wright's published writings and lectures and informal talks the most precise and lucid statement of these basic principles: 'to make the principles and aims of Organic Architecture more generally available by assembling statements dealing with architecture as Mr. Wright has experienced it and practised it . . . and, by illustration, to relate these to Mr. Wright's architecture' as the editor writes in his introductory note.



Each chapter is devoted to a major aspect of his work: *Architecture Presents Man; From Generals to Particulars; Obstacles and Protests* (including the epoch-making talk on his revolutionary destruction of the box, interwoven with drawings to illustrate each successive development in his liberation of space to be lived in); *The Nature of Materials; Some Case Histories; Out of the Ground into the Light; Where Principle is Put to Work there Will Always be Style; The Future of Organic Architecture*. And the illustrations, carefully juxtaposed with the text, serve to illuminate and clarify each important point.

Edgar Kaufmann, the book's editor, was an apprentice with Mr. Wright and has since organized many important exhibitions of progressive design in the U.S.A.

Size: 12½ in. by 9½ in., 270 pages, 262 illustrations. 84s. net. Postage 2s. 3d. inland.

THE ARCHITECTURAL PRESS, 9-13 QUEEN ANNE'S GATE, S.W.1


Electrical Installations

*a handbook
for architects*

and assistants

edited by

Brian Grant



THIS BOOK DOES NOT SET OUT TO BE a technical work on electricity, but is designed to provide architects and their assistants with all the essential information they need for the efficient planning and supervision of electrical installations in cases where no consultant has been employed. The book will also help them to specify and obtain good materials and workmanship, as well as to choose the most suitable available fittings and accessories for the job in hand. In addition it will give them a fair understanding of questions they are likely to be asked by consultant engineers or contractors when working on larger jobs, and so enable them to deal intelligently with any problems that may arise. The majority of the contents were first published in the *Architects' Journal*, but they have now been revised and enlarged for presentation in book form. The size of the book is 8½ x 5½ in. It contains 100 pages including some 100 line diagrams and half-tone illustrations. 16s. net, postage 10d.


THE ARCHITECTURAL PRESS 9-13 Queen Anne's Gate, S.W.1

CYLINDER JACKETS

BY

EETO

THE
UNIVERSAL
CHOICE




UNAPPROACH-
ABLE in quality
and performance.
EETO jackets are
still the finest in
the world.

EETO SERVICE
IS PROMPT
AND
EFFICIENT

EETO INSULATIONS
RIVER ST BOLTON LANCs
TEL BOLTON 3769

1986 (2074)



STAINLESS STEEL Island Wash Fountain

HAND OR FOOT OPERATED
(FOOT OPERATED MODELS ILLUSTRATED)

Round or Semi-circular to suit 3 to 8 persons

MODERATE COST · BEAUTIFUL FINISH

We can also supply sinks and sink units from a wide range of standard designs or built to your requirements

ASSOCIATED METAL WORKS
(GLASGOW) LTD.

30 ST. ANDREWS SQUARE, GLASGOW, C.I.
Telephone: BELL 2004 (3 lines) Telegrams: "STAINLESS, GLASGOW"

LONDON: 7 Grosvenor Gardens, S.W.1. Telephone: VICTORIA 1977/8
And at Edinburgh, Liverpool, Birmingham, Manchester, Newcastle, Belfast and Dublin

We thought you'd look at this - but try it from a distance of twelve feet



THE ENGRAVERS GUILD LTD

MAKERS OF PRINTING BLOCKS

WINDSOR HOUSE · CURSITOR STREET · LONDON · E.C.4

MARLEY MULTIPLE CONCRETE GARAGES



Of unsurpassed appearance and spacious dimensions, these fire-proof, rot-proof garages are virtually maintenance free. Choice of superb 'Welrise' up-and-over doors or traditional timber.

Supplied, delivered and erected by Marley experts at very competitive prices. Let us quote you . .

MARLEY CONCRETE LIMITED. Dept. X B 14

PEASMARSH, GUILDFORD, SURREY Guildford 62986 · SOUTH OCKENDON, NR. ROMFORD, ESSEX S. Ockendon 2201
SHURDINGTON, NR. CHELTENHAM Shurdington 334/5 · WATERLOO, POOLE DORSET Broadstone 626

ESTD. S.W. 1898

IRON STAIRCASES
STEELWORK

FARMER & SON LIMITED

BALUSTRADING
FENCING

FABRICATORS IN STEEL

STAIRWAY HOUSE, COURTHILL ROAD, LEWISHAM LONDON S.E.13. PHONE: LEE GREEN 4334-9.

**harder use
greater comfort
easier cleaning**

Durability

The upholstery of the entire arms, sides and back—where abrasion, scuffing and wear is at its greatest—is a rich hide; the frame is of tubular steel. The legs are of polished mahogany and fitted with Armstrong footrests



Cleaning

The back and seat cushions are removable and their covers can quickly and easily be detached for cleaning (cushion covers—and spare sets—are available in a wide range of fabrics: all treated for non-fray during cleaning)

Comfort

The seats and back cushions are of thick latex; the seat cushion is on Pirelli webbing

RACE furniture London

Write for our illustrated list to:
22 Union Road Clapham SW4 Telephone: MACaulay 2215/7

PART ONE OF THE DESIGN OF STRUCTURAL MEMBERS with model answers to R.I.B.A. intermediate examination questions by H. T. Jackson, F.R.I.B.A., A.M.I.Struct.E.

This book is addressed primarily to students of architecture who are preparing to take the R.I.B.A. Intermediate Examination, but at the same time, it will be found useful by all practising architects and assistants.

The book consists of a collection of typical R.I.B.A. Intermediate Examination questions accompanied by model answers; and the problems met in practice in the design and testing of structures are explained and solved. Thus, in a single volume, is brought together all the information required to design a simple structure, information which otherwise could be gleaned only from a score of text-books, technical journals, codes of practice, standard specifications and by-laws. All that is needed in addition to the present volume is a handbook of steel sections and a knowledge of elementary mathematics; since some readers will not have an engineering training, everything is explained in the simplest terms and all the stages of the mathematical processes are clearly shown. This part deals with simple structures, including beams, columns, floors and roofs, frames, walls and retaining walls in all the normally available materials. Part II will have special reference to the R.I.B.A. Final Examination and will deal with larger and more complex structures.

Part I: Size 8½ in. x 5½ in. 176 pages including 161 line diagrams. 25s. net. Postage 11d.

THE ARCHITECTURAL PRESS, 9-13 Queen Anne's Gate, S.W.1.

CLASSIFIED ADVERTISEMENTS

Advertisements should be addressed to the Advt. Manager, "The Architects' Journal," 3, 11 and 13, Queen Anne's Gate, Westminster, S.W.1, and should reach there by first post on Friday morning for inclusion in the following Thursday's paper.

Replies to Box Numbers should be addressed care of "The Architects' Journal," at the address given above.

Public and Official Announcements

30s. per inch; each additional line, 2s. 6d.

LONDON COUNTY COUNCIL
ARCHITECTS' DEPARTMENT

Vacancies for (1) ARCHITECTS, Grade III, starting salary up to £1,090 a year. (2) ARCHITECTURAL ASSISTANTS, starting salary up to £860.

Full and interesting programme of houses, flats, schools and general buildings.

Application form and full particulars from the Architect (AR/EK/5/58), The County Hall, S.E.1 (265) 8741

FIFE COUNTY COUNCIL

QUANTITY SURVEYORS required. Salary scale A. & P., VI, i.e., £865 to £935 per annum. Must be fully experienced in measuring and the final adjustments of all trades, particularly housing. Superannuation Scheme. House may be available. Applications, stating age and experience, with copies of recent testimonials, by 15th April, 1958, to the County Clerk, County Buildings, Cupar, Fife. 9142

DERBYSHIRE COUNTY COUNCIL

COUNTY PLANNING DEPARTMENT
Applications are invited from Qualified ARCHITECTS, preferably with experience in the layout and design of housing estates and central area redevelopment. Salary will be in the range £750-£1,030, and the commencing salary will be determined on the basis of experience.

Applications with one testimonial and the names of two referees should reach the County Planning Officer, 8A Bold Lane, Derby, by April 14th, 1958. 9107

FIFE COUNTY COUNCIL

DEPUTY COUNTY PLANNING OFFICER required. Salary scale £1,207-£1,533. Should be Member of Town Planning Institute and have wide experience in Town and County Planning, and good administrative and organising ability. Additional qualification an advantage. General information re County Development Plan, etc., obtainable from County Planning Officer. House may be available. No canvassing. Applications, giving full particulars and names of three referees, by 24th April, to the County Clerk, County Buildings, Cupar, Fife. 9141

GOVERNMENT OF NORTHERN IRELAND

ASSISTANT ARCHITECT CLASS II
Applications are invited for pensionable posts in the Chief Architect's Branch, Ministry of Finance. Candidates must be Registered Architects by examination, with at least 2 years' experience in an Architect's Office in the preparation of working drawings. Salary scale £780 (at age 25)-£1,055 (age 34 and over)-£1,215. Transfer of existing Pension rights may, in certain circumstances, be approved. Preference will be given to ex-Servicemen. Application forms may be obtained from the Secretary, Civil Service Commission, Stormont, Belfast. 9094

AIR MINISTRY WORKS Design Branch required in London and Provinces ARCHITECTURAL ASSISTANTS experienced in planning/preparation of working drawings and details for permanent and semi-permanent buildings. Salaries in London up to £1,015 per annum for men and £952 per annum for women. Somewhat lower in provinces. Starting pay dependent on age, qualifications and experience. Long term possibilities with pensionable and promotion prospects. 5-day week, 3 weeks 3 days leave a natural born British subjects. Write, stating age, qualifications, employment details, including type of work done, to any Employment Exchange, quoting Order No. Borough 100. 8582

THE UNIVERSITY OF MANCHESTER

Applications are invited for the post of LECTURER IN ARCHITECTURE from candidates with professional membership of the Royal Institute of British Architects, and not less than three years of practical experience. Salary on a scale from £900 to £1,650 per annum; initial salary according to qualifications and experience. Membership of the F.S.S.U. and Children's Allowance Scheme. Applications should be sent not later than 26th April, 1958, to the Registrar, the University, Manchester, 13, from whom further particulars and forms of application may be obtained. 9065

PADDDINGTON BOROUGH COUNCIL

ARCHITECTURAL ASSISTANT (£755-£875 p.a.)
Starting salary according to qualifications and experience of successful candidate. Applicants should be Inter-R.I.B.A., neat and accurate draughtsmen, and possess sound knowledge of modern building construction. National Conditions of Service. Applications, stating age, qualifications, present and past appointments, with details of experience, names and addresses of three referees, should reach me by 21st April, 1958, quoting A.374.

W. H. BENTLEY,

Town Clerk.

Town Hall, Paddington, W.2.

9139

LANCASHIRE COUNTY COUNCIL
APPOINTMENT OF COUNTY ARCHITECT

The Lancashire County Council invite applications from Fellows or Associate Members of the Royal Institute of British Architects for the post of COUNTY ARCHITECT.

The appointment will be made within the scale £3,390-£3,915 and will be subject to the provisions of the Local Government Superannuation Acts. The successful applicant will be required to pass a medical examination.

Forms of application, together with particulars of the terms and conditions of the appointment, may be obtained from the undersigned, to whom applications should be submitted not later than the 9th May, 1958.

R. ADCOCK,

Clerk of the County Council.

County Hall,
Preston.

9125

LONDON COUNTY COUNCIL
ARCHITECTS' DEPARTMENT

Vacancy in Historic Buildings Section for ARCHITECT, Grade III (starting salary up to £1,090 a year), for recording of buildings of architectural and historic interest. A.R.I.B.A. or equivalent preferred.

Particulars and Application Form, returnable by 24th April, from Hubert Bennett, F.R.I.B.A., Architect to Council, Ref. AR/EK/15/58, County Hall, S.E.1. (559) 9143

INVERNESS COUNTY COUNCIL requires COUNTY ARCHITECT AND PLANNING OFFICER. Salary on approved scale at maximum of £2,291. Post superannuable.

Applicants, whose age must not exceed 50, must hold the qualifications of A.R.I.B.A. and A.M.T.P.I.

Apply, giving age, qualifications, appointments held, and three referees, to County Clerk, County Buildings, Inverness, by 12th April. 9140

Architectural Appointments Vacant

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.

Box Number, including forwarding replies, 2s. extra

FREDERICK GIBBERD'S London office requires ARCHITECTURAL ASSISTANTS. Salary £600-£750 according to experience. Write giving full particulars to 8, Percy Street, London, W.1. 9149

NORMAN JONES, SONS & RIGBY require an ARCHITECTURAL ASSISTANT of Intermediate standard, good draughtsman, sound knowledge building construction, able to produce working drawings, surveys. Salary range £550-£650. Please write stating experience to 271, Lord Street, Southport, Lancashire. 9147

INTERMEDIATE ARCHITECTURAL ASSISTANT required by City Firm, capable of controlling small contracts of industrial character. Salary £600-£800 Box 9068.

EXPERIENCED SENIOR ASSISTANTS required to take charge of Contracts with minimum supervision. Medium sized office. General practice with present emphasis on local authority housing.

Apply in writing only, stating age, qualifications, experience and salary required to: Thomas Sibborth, F.R.I.B.A., A.R.I.C.S., A.M.T.P.I., 10, Manchester Square, London, W.1. 9086

F. W. WOOLWORTH AND CO. LTD., Architects' Department, Kensington District Office. Applications are invited for the following appointment:-

ARCHITECTURAL ASSISTANT of Intermediate R.I.B.A. standard, capable of carrying out surveys, preparing sketch schemes, working drawings and details.

The appointment is permanent and pensionable. Five-day week. Dining room facilities. Application stating age, experience, qualifications and salary to District Architect, F. W. Woolworth & Co. Ltd., 26/40 Kensington High Street, London, W.8. 9044

GOLLINS, MELVIN, WARD & PARTNERS require staff to work on hospital, office and University projects. Age and experience are less important than design ability and enthusiasm. Five-day week, quarterly bonuses, pension scheme. Telephone Welbeck 9991 for appointment. 9046

ARCHITECT'S Department in City requires two ASSISTANTS of about Intermediate R.I.B.A. standard with some office experience. Salary ranges £600-£800 and work of an interesting and varied nature. Secure future for suitable applicants. Write giving particulars of age, experience and salary required. Box 9061.

COMPETITION spare-time help required on design by practising Architect in Midlands. Preferably Associates with Competition successes or experience. Remuneration, etc., by arrangement.-Write, giving details with experience, Box 9109.

TREHARNE & NORMAN, PRESTON & PARTNERS have a vacancy for an ASSISTANT. Salary according to experience and qualifications.-Apply: 83, Kingsway, W.C. (HOL. 4071). 9113

ARCHITECTURAL DRAUGHTSMAN urgently required. Applications to Alfred H. Howard, L.R.I.B.A., West Way House, St. Thomas Street, Winchester. 9154

ARCHITECTURAL DRAUGHTSMAN required by large Building Company in Cornwall. Applicants should have at least 2 years' experience as a senior.-Apply, stating experience, age, and salary required, to Box 9130.

ASSISTANTS wanted. Write brief details to Eric Lyons, Mill House, Bridge Road, Hampton Court, Surrey. 9156

LANCHESTER & LODGE urgently require ASSISTANT, around Intermediate standard. Write full particulars, 10, Woburn Square, London, W.C.1. 9153

SENIOR and JUNIOR ARCHITECTURAL ASSISTANTS required in varied contemporary practice.-Apply in writing, stating age, experience and salary required, to H. A. Halpern, A.R.I.B.A., 26a, High Street, Chatham, Kent. 9131

W. S. ATKINS & PARTNERS announce that they have vacancies for qualified ARCHITECTS for work on major industrial projects.-Applications, giving full particulars to Personnel Manager, 158, Victoria Street, S.W.1. 9114

RONALD WARD & PARTNERS require ARCHITECTURAL ASSISTANTS with contemporary outlook, and willing to use own initiative. Salary range £600 to £900. Congenial working conditions. 5-day week.-Apply: 29, Chesham Place, Belgrave Square, S.W.1. Telephone Belgravia 3361. 9112

CADBURY BROS., LIMITED, require an ARCHITECTURAL ASSISTANT of Intermediate R.I.B.A. standard to work on a varied and interesting programme. Experience in Industrial and Commercial Building design desirable. Five-day week, attractive working conditions and amenities. Pension Scheme. Salary according to qualifications and experience. Write stating age, qualifications and salary required to CHIEF ARCHITECT, Cadbury Brothers, Limited, Bournville, Birmingham. 9159

Architectural Appointments Wanted

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.

Box Number, including forwarding replies, 2s. extra

ARCHITECTURAL work required by experienced Assistants with speed, efficiency, confidence and reliability. Any amount can be handled. Please phone BRIXTON 9318. 9145

ARCHITECT seeks position with firm of fabricators, estate developers, etc. Wide experience, good organiser with commercial ability, interest in research and development. Foreign languages, good contacts here and abroad. Box 9146.

A.R.I.B.A., 30, eight years' varied experience or private architects since completing full-time course, seeks architectural, contractual or industrial position, Herts. or N. London. Car driver. Available end April. Box 9150.

ARCHITECT'S ASSISTANT, 30, seeks position in architect's office, contractor's site office or architect's department of industrial firm in Birmingham-Midlands area. Fourteen years' experience factories, bakeries, offices, licensed premises, domestic work, housing estates, surveying and setting out of same including the use of theodolite and level. Multi-storey commercial premises detailing, setting out and supervision of site works. Detailing of steel framed and reinforced concrete multi-storey structures, including foundation works, ground beams, etc. Box 9151.

A.R.I.B.A., age 40, wide experience, seeks responsible position or undertake work as free-lance. Car owner. Box 9158.

Other Appointments Vacant

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.

Box Number, including forwarding replies, 2s. extra

CAWDOO WHARTON & CO. LTD. require TECHNICAL REPRESENTATIVES for their recently established Lightweight Roofing Department in the following areas:-

- Scotland.
- Yorkshire and the North East Coast.
- East Midlands and the Eastern Counties.

Applications will be considered from experienced technical representatives who possess a proven connection amongst architects in one of these areas and a general knowledge of building, but preference will be given to those with previous experience of roofing or structural work and/or possessing a structural or architectural qualification.

Applications for an interview, at which full details of the appointments (which are pensionable) will be given, must include age, present income and a summary of experience and be addressed to Staff Manager, Cawdoo Wharton & Co. Ltd., Southlands, Harrogate. 9148

Services Offered

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.

Box Number, including forwarding replies, 2s. extra

"DON" ARCHITECTURAL MODEL MAKERS. We offer the highest grade work with speed and reliability.-Please Phone BRIS 3843 or HASTINGS 1366. 1673

A.R.I.B.A. seeks part-time work, evenings or week-ends. Prefers complete small jobs. Write Box 9144.

ESTIMATES for Conversions, Industrial Developments, Single Houses; London and West Sussex.-Parsons & Co. (Builders), 18, Maplestead Road, S.W.2. TUL. 3052 for immediate attention. 8915

ARCHITECTURAL. Reinforced Concrete and Steel design and detailing work required. Over 30 Assistants available. MUS. 8753. 5145

SITE Surveys and Surveys of Buildings prepared at short notice anywhere in Britain. Museum 8753. 3103

THE SITE SURVEY COMPANY

Blackheath, S.E.3. Tel.: LEE Green 7444-5
Fully equipped to undertake urgent Engineering and Architectural surveys in any part of the country and abroad. Specialists in 1/4 in. scale detailed surveys for extensive city development areas. 1896

FIBREGLASS/PLASTICS ROOFING, CLADDING, PARTITIONING. Manufacturers producing all standard forms are also able to laminate your own decorative patterns, Sanderson prints, etc., in translucent or opaque materials to Specification.—Structural Plastics, Ltd., Elythorne, Dover, Kent. 8734

ASSOC. I.E.E. offers complete electrical design service for every type installation, including specifications, B of Q, preliminary estimates, etc. Box 8336.

NAMEPLATES, PLAQUES, CRESTS, etc., in bronze, brass, and plastic; quotations and lay-outs submitted.—Abbey Craftsmen, Ltd., Abbey Works, 109a, Old Street, London, E.C.1. CLE. 3845.

For Sale and Wanted

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.
Box Number, including forwarding replies, 2s. extra
MOTOR CAR TURN-TABLE. Avoids reversing. Indispensable in limited spaces. Write for terms.—Oscar Chess Limited, Port Talbot, Glam. 8337

SECONDHAND sectional timber buildings completely reconditioned, delivered free 100 miles. 24 ft. x 12 ft., £102. 30 ft. x 15 ft., £138. 30 ft. x 18 ft., £154. 60 ft. x 20 ft., £302. Floors extra. Universal Supplies, Crabtree Manorway, Belvedere, Kent. Erith 2948. 9152

Miscellaneous

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.
Box Number, including forwarding replies, 2s. extra
A. J. BINNS, LTD., Specialists in the supply and fixing of all types of Fencing, Gates and Cloakroom Equipment.—Harvest Works, 96/107 St Paul's Road, N.1. Cannonbury 2061

CANTEN and Restaurant Kitchens expertly planned and fitted. Reconditioned or new equipment available. Rental facilities if required. Designer will call. Commercial Catering Equipment Co. Ltd., 29, Abingdon Road, Kensington, W.8. Tel. WESTern 0936. 9042

ARCHITECTURAL METALWORK of all types supplied and fitted. Gates, doors, balustrades, staircases, steel structures. Design staff available.—Clayton & Bamber, Ltd., Cartersfield Road, Waltham Abbey, Essex. 5823

Educational Announcements

4 lines or under, 9s. 6d.; each additional line, 2s. 6d.
Box Number, including forwarding replies, 2s. extra
R. I.B.A. and T.P.I. EXAMS.—Stuart Stanley (Ex. Tutor Sch. of Arch., Lon. Univ.), and G. A. Crockett, M.A./B.A., F./F.R.I.B.A., M./A.M.T.P.I. prepare Students by correspondence, 10, Adelaide Street, Strand, W.C.2. TEM. 1605/4.

R. I.B.A. Inter. and Final EXAMS. • TUITION, BY POST.—C. W. BOX, F.R.I.B.A., 115, Gower Street, W.C.1. Tel. BUS. 3996. 1943

COURSES for all R.I.B.A. EXAMS.

Postal tuition in History, Testimonies, Design, Calculations, Materials, Construction, Structures, Hygiene, Specifications, Professional Practice, etc. Also in general educational subjects.

ELLIS SCHOOL OF ARCHITECTURE

Principal: A. B. Waters, M.B.E., G.M., F.R.I.B.A.
103B OLD BROMPTON RD., LONDON, S.W.7
and at Albany House, Worcester



EXTERIOR BRICK & CEMENT SURFACES

Best decorated with

Cementone



Write today for colour card.
JOSEPH FREEMAN SONS & Co. Ltd.
Cementone Works, London S.W.1

The 'number seven' range also includes Gloss, Interior Flat and Eggshell.

BUILDER & ELECTRICAL CONTRACTOR

F.M.B.

Invites enquiries from Architects, Surveyors, Etc., for contracts in the London or adjoining areas. Fully experienced in new building, conversion, alteration, and decorations. Highest references.

Write or 'phone:
SIMPSON & SONS (FRIERN BARNET) Ltd.
13, LYNHURST AVENUE, LONDON, N.12.
ENTERprise 4180

STRAMAX

HEATING • SOUND ABSORPTION • COOLING
Full details of STRAMAX RADIANT HEATED CEILINGS are given in the Architects Journal Information Sheet No. 29. H.5 dated Dec. 12th, 1957.
Copies of this and fully illustrated literature on request from
STRAMAX CEILINGS (G. B.) LTD.
19 REA STREET, BIRMINGHAM, S. Tel: MID 4674

Bridges PROTECT THEM Colliery headgear
Structural Steelwork FROM RUST Fencing gates
Pylons WITH Gutters

GALVAFROID

ZINC RICH PAINT

SECOMASTIC LIMITED BRACKNELL BERKSHIRE TEL. 910/9

Architectural Models

for

Completed Schemes, Planning Stage Models, Structural Design, Display Designers Prototypes, etc.

Consult

LYNCH & BAKER LTD.
DISPLAY & MODELMAKING SERVICES

3 Mark Rd., Hemel Hempstead, Herts.
Boxmoor 4788

THE WORLD'S GREATEST BOOKSHOP

FOYLES
FOR BOOKS
FAMED CENTRE FOR

Books on Art & Architecture

New, secondhand and rare Books on every subject

119-125 CHARING CROSS ROAD WC2
Gerrard 5660 (20 lines) ★ Open 9-6 (Incl. Sats.)
Two minutes from Tottenham Court Rd. Stn.

BROAD-ACHESON
BLOCKS for
unvarying quality

ALL PRODUCTION UNDER
LABORATORY CONTROL

BROAD & CO. LTD., PADDINGTON, W.2

'SYSTON' ROLLING SHUTTERS
IN STEEL, WOOD AND ALUMINIUM
'SYSTON' SERVERY HATCHES

MANUFACTURED TO YOUR OWN SPECIFICATION

AT COMPETITIVE PRICES WITH RAPID DELIVERY

J. TAYLOR (SYSTON) LTD. • SYSTON • LEICESTER

TEL: SYSTON 2133 - MANCHESTER: RINGWAY 3996

have you seen the new fluted

faience?

For further details and general information on Faience please write to—

by **HATHERNWARE**

THE TOUGHEST FAIENCE MADE

Hathernware Ltd., Loughborough, Leics. Tel: Hathern 273.

FIRST FOLD HERE

AJ enquiry service

If you require catalogues and further information on building products and services referred to in the advertisements appearing in this issue of the Architects' Journal please mark with a tick the relevant names given in the index to advertisers overleaf. Then detach this page, write in block letters, or type, your name, profession or trade and address in the space overleaf, fold the page so that the post-paid address is on the outside and despatch. We will ensure that your request reaches the advertisers concerned.

Postage
will be paid
by
Licensee

FOLD HERE

No Postage Stamp
necessary
if posted
in Great Britain or
Northern Ireland

BUSINESS REPLY FOLDER
Licence No. S.W. 1761

THE ARCHITECTS' JOURNAL

9-13 Queen Anne's Gate

London, S.W.1.

FOLD HERE

TUCK IN THIS END

Alphabetical index to advertisers

	PAGE	CODE
A.E.I. Lamp & Lighting Co., Ltd.	50	0830
Acme Flooring & Paving Co. (1904), Ltd.	111	0004
Adams, Robert, Ltd.	103	0006
Airscrew Co. & Jicwood, Ltd.	68	0014
Allom Heffer & Co., Ltd.	86	0987
Architectural Press, Ltd.	106, 110, 111, 113, 114,	0686
Armstrong Cork Co., Ltd.	83	0027
Associated Metal Works, Ltd.	114	0035
Association of Vermiculite Exfoliators	40	0707

B.I.P. Reinforced Products, Ltd.	54	0967
Batley, Ernest, Ltd.	110	0045
Beecham Buildings, Ltd.	46	0901
Bell & Webster, Ltd.	105	0051
Biddle, F. H., Ltd.	81	0059
Bilston Foundries, Ltd.	82	0614
Blackey Cabinet & Metal Works Co., Ltd.	104	0744
Bow Slate & Enamel Co., Ltd.	41	0075
Brady, Frederick, & Co., Ltd.	13	0077
Brady, G., & Co., Ltd.	60	0079
Brightside Heating & Engineering Co., Ltd.	3	0083
British Lime Manufacturers, Ltd.	106	0094
British Pens, Ltd.	112	0947
British Plaster Board Manufacturing, Ltd.	14	0099
British Plumber, Ltd.	95	0100
British Sanitary Fire Clay Association	63	0774
Broads Manufacturing Co., Ltd.	102	0109
Broad & Co., Ltd.	118	0784

C.T.C. Heat (London), Ltd.	62	0169
Cape Building Products, Ltd.	29	0120
Carrier Engineering Co., Ltd.	74	0857
Caxton Floors, Ltd.	103	0805
Celotex, Ltd.	18	0127
Compactom, Ltd.	33	0147
Concrete Development Co., Ltd.	79	0149
Corraglaze, Ltd.	26	0907
Costain, Richard, Ltd.	80	0157
Crane, Ltd.	30	0164
Crittall Manufacturing Co., Ltd.	10, 11	0165
Crittall, Richard, & Co., Ltd.	72	0955

De La Rue, Thomas, & Co., Ltd.	91	0176
Dexion, Ltd.	47	0181
Dreadnought Fireproof Doors, Ltd.	105	0191
Duresco Products, Ltd.	37	0197
Dusek Bitumen & Taroleum, Ltd.	104	0622

Econa Modern Products, Ltd.	121	0201
Eeto Insulations, Ltd.	114	0204
Ellard Sliding Door Gears, Ltd.	88	0210
Ellis, John, & Sons, Ltd.	59	0211
Ellis School of Architecture	118	0212
English Clock Systems, Ltd.	24	0214
Engravers Guild, Ltd.	115	
Evo-de, Ltd.	5	0939
Ezee Kitchens, Ltd.	85	0221

Factory Equipment Exhibition	101	0988
Farmer, S. W., & Son, Ltd.	116	0224
Farmiloe, T. W., Ltd.	27	0225
FEB (Gt. Britain), Ltd.	9	0226
Fibrolene, Ltd.	108	0231
Flexitella Fencing & Engineering, Ltd.	99	0944
Foyles, Ltd.	118	0242
Freeman, Joseph, & Sons, Ltd.	118	0244
French, Thomas, & Sons, Ltd.	8	0246
Frenger Ceilings, Ltd.	57	0247
Gay, R., & Co.	65	0252
General Electric Co., Ltd.	20, 21	0253
Greenwoods & Airvac Ventilating Co., Ltd.	2, 73	0260
Greenwood, George, & Sons, Ltd.	51	0896

Hall & Kay, Ltd.	112	0268
Hallam, Vic, Ltd.	100	0704
Harris & Sheldon, Ltd.	4	0275
Hartley, V. & N., Ltd.	109	0746
Harvey, G. A., & Co. (London), Ltd.	99	0276
Haskins Rolling Shutters, Ltd.	35	0278
Hathernware, Ltd.	118	0279
Henderson, P. C., Ltd.	76	0284
Hills, F., & Sons, Ltd.	39	0291
Hills Structures & Foundations	52	0279
Holoplast, Ltd.	31	0299
Hope, Henry, & Sons, Ltd.	77	0302

I.C.I. Metals, Ltd.	64	0307
I.C.I. Plastics, Ltd.	16	0309

James, W., & Co., Ltd.	121	0319
Johns, Edward, & Co., Ltd.	67	0771
Jones, T. C., & Co., Ltd.	36	0323

Kay, William, Ltd.	109	0324
Kay, E. & E., Ltd.	38	0980
Kenrick, Archibald, & Sons, Ltd.	111	0042
King, G. W., Ltd.	56	0327
Kingfisher, Ltd.	92	0329

Lamont, James H., & Co., Ltd.	102	0334
Lead Development Association	53	0337
Legal & General Assurance Society, Ltd.	96	0340
Leigh, W. & J., Ltd.	45	0341
Lewis, G. W., Tileries, Ltd.	96	0637
Libraco, Ltd.	111	0344
Linoleum Manufacturers' Association	84	0349
Liquitile Supply Co.	94	0923
London Brick Co., Ltd.	89	0353
London Electric Firm, Ltd.	49	0354
Lynch & Baker, Ltd.	118	0358

Marley Concrete, Ltd.	116	0370
Marley Tile Co., Ltd.	78	0371
Marryat & Scott, Ltd.	109	0372
Mellor Bromley & Co., Ltd.	98	0378
Metallic Seamless Tube Co., Ltd.	108	0382
Midland Electric Manufacturing Co., Ltd.	58	0386
Midland Woodworking Co., Ltd.	12	0387
Monsanto Chemicals, Ltd.	43	0395

Nairn, Michael, & Co., Ltd.	32	0402
National Coal Board	17	0404
Nestler Slide Rules	113	0833
Norwood Steel Equipment, Ltd.	68	0418

Olason, Martin, & Sons, Ltd.	34	0422
Omnia Constructions, Ltd.	42	0876

Phoenix Rubber Co., Ltd.	95	0438
Plus Gas Co., Ltd.	113	0712
Pritchett & Gold & E.P.S. Co., Ltd.	55	0644
Prodorite, Ltd.	107	0444

Quicktho (1928), Ltd.	90	0702
-----------------------	----	------

R.I.W. Protective Products Co., Ltd.	101	0847
Race, E.	116	0980
Redland Tiles, Ltd.	23	0461
Redpath Brown, Ltd.	22	0463
Reed Millican & Co., Ltd.	97	0464
Riley (IC) Products, Ltd.	44	0469
Robertson Thain, Ltd.	15	0472
Roffe, Ltd.	69	0990

Sanders, Wm., & Co., Ltd.	6	0489
Sankey-Sheldon, Ltd.	75	0493
Saro Laminated Wood Products, Ltd.	90	0494
Secomastic, Ltd.	118	0501
Simpson & Sons, Ltd.	118	0976
Smith & Davis, Ltd.	92	0772
Smith, Thomas, & Son, Ltd.	19	0531
Sommerfelds, Ltd.	93	0532
Standard Maclean, Ltd.	48	0809
Standard Patent Glazing Co., Ltd.	103	0529
Steels Engineering Installations, Ltd.	28	0750
Stent Precast Concrete	114	0533
Stramax Ceilings (G.B.), Ltd.	94, 118	0960
Syglas Co.	2	0927
Szerelmey, Ltd.	110	0928

Taylor, J. (Syston), Ltd.	118	0542
Templewood Hawksley, Ltd.	62	0892
Thames Plywood Manufacturers, Ltd.	107	0677
Thorn, J., & Sons, Ltd.	93	0550
Thorpe, F. W., Ltd.	98	0991
Tretol, Ltd.	7	0558
Trollope & Colls, Ltd.	25	0560
Trussed Concrete Steel Co., Ltd.	61	0563
Tubeclamps, Ltd.	100	0838

Venus Pencil Co., Ltd.	88	0581
Versatile Fittings, Ltd.	122	0583

Wall Paper Manufacturers	97	0587
Washington Engineering Co., Ltd.	66	0594
Weatherfoil Heating Systems, Ltd.	87	0597
Williams & Williams, Ltd.	70	0604
Williams & Williams Ltd.	71	0813
Woods of Colchester	112	0992

For Appointments (Wanted or Vacant), Competitions Open, Drawings, Tracings, etc., Education, Legal Notices, Miscellaneous Property and Land Sales, see 115, 116, 117, 118.

Write in block letters, or type, your name, profession and address below, and fold so that the post-paid address is on the outside.

NAME _____

PROFESSION _____

ADDRESS _____

CODE
0402
0404
0832
0410

0422
0870

0430
0712

0644
0440

0700

0847
0980
0462
0463
0464
0460
0472
0900

0400
0492

0494
0501
0976
0730
0501
0522
0800
0520

0750
0533
0900
0927
0928

0542
0892

0677
0550
0901
0558
0560
0563
0838

0581
0583

0587
0594
0597
0604
0812
0992

What is nesting time?

It's anytime—yet no time at all—with **KINGFISHER** Hardwood chairs. They are built to give comfort and take every punishment.

The unique metal-braced construction gives a rock-like rigidity and makes maintenance easy.

Proved in "performance tests" by 750,000 users in schools, works canteens and halls.

There are several variations of design in this chair—May we send you full details of our comprehensive range of furniture.


**KINGFISHER LTD., CHARLES STREET AND PHOENIX STREET,
WEST BROMWICH • STAFFS.**

Telephone: Tipton 1631

Telegrams: Kingfisher, Phone, West Bromwich.

London Office: 139 Knightsbridge, S.W.1.

Telephone: Kensington 1331




WN2

WN3

WN4

WN5


Kingfisher Nesting Furniture



WN8

JAMES make good METAL WINDOWS

W. JAMES & CO. LTD.
Hythe Rd. Willesden Junction
LADbroke 6471 (6 lines) N.W.10



Econa can't help you to unseal THIS NEW BOTTLE TRAP

It's simple, it's a thing of beauty, it's a foolproof resealing trap and it works. Like to know more?


Full details from

ECONA MODERN PRODUCTS LIMITED

AQUA WORKS • HIGHLANDS RD. • SHIRLEY • SOLIHULL • WARWICKSHIRE Tel. Solihull 3078

**THERE ARE
VIZUSELL
INSTAL-
LATIONS IN**

CANADA
EIRE
ENGLAND
FRANCE
GERMANY
HOLLAND
KENYA
LIBYA
MOROCCO
NEW ZEALAND
NIGERIA
NORWAY
NORTHERN
IRELAND
NYASALAND
PERSIAN GULF
SAUDI ARABIA
SCOTLAND
SPAIN
TANGANYIKA
TURKEY
U.S.A.
WALES



Full details from
VERSATILE FITTINGS (WHS) LTD.
55, FETTER LANE, LONDON E.C.4
Fleet Street 6262

As flexible as your imagination !

ALSO SHOWROOMS AT

MANCHESTER: VERSATILE FITTINGS (WHS) LTD., 33, BLACKFRIARS STREET, MANCHESTER
Deansgate 2564

GLASGOW: GRAHAM & WYLIE LTD., MILL STREET, BRIDGETON, GLASGOW. Bridgeton 4831
(Selling Agents for Scotland)

TER
2564
4831
and)